



DENVER
THE MILE HIGH CITY

EXECUTIVE SUMMARY

Contractor:Layne Heavy Civil, Inc

Proposed Contract Amount:\$6,282,737.00

Project Title:PARKHILL STORM PH IV-A 51ST & ST.PAUL SANITARY

Contract Control Number:201309641

Term of this proposed contract (start/end date):330 DAYS

Selection process:

- (a) Date of Bid process:March 29, 2013**
- (b) How many proposals were received:3**
- (c) Range: Low:\$6,282,737.00 High:\$7,593,450.00**

DSBO Assigned Goals:10% M/WBE

DSBO Goals Commitment:10.86%

Council District:8

Source of funds (CIP/BOND/GRANT/CDOT):PA77612_323/72801/5061102

Background:Parkhill Storm PH IV-A /51st and St. Paul Sanitary is the first portion of the Parkhill Storm PH IV. The project is a Storm and Sanitary open cut project that includes 2,356 LF of 84" diameter storm sewer and 2,124 LF of Sanitary (27" to 24"). There is approximately 143 LF of 84" storm that is to be jacked and bored under BNSF railroad and a similar amount of sanitary main to be jacked at this location as well. The storm and sanitary portion of this project starts at Colorado Blvd. and 48th Avenue and goes east on 48 Avenue to N. Dahlia Street then turns the corner and ends on the south side of the intersection of 48th Avenue and Dahlia Street. There is approximately half a mile of waterline that is to be relocated in Dahlia from 48th Avenue to Smith Road to allow for the construction of the storm and sanitary pipe that will be constructed in the future Parkhill Storm PH IV-B. Xcel will be relocating the gas mains in this area and coordination with Xcel and most of the Fiber Optics companies, Century Link and



Protecting the Present & Building the Future
Accountability, Innovation, Empowerment, Performance, Integrity,
Diversity, Teamwork, Respect, Excellence, Safety

Comcast will be required. Fastracks East Line is also being constructed adjacent to the UPRR at Smith and Dahlia and careful coordination will be required to ensure a successful project.