

CITY AND COUNTY OF DENVER

STATE OF COLORADO



DENVER
THE MILE HIGH CITY

**DEPARTMENT OF TRANSPORTATION &
INFRASTRUCTURE**

Contract Documents

Contract Number: 202057115

2021 Citywide Chip Seal and Crack Seal

December 16, 2020



NOTICE TO APPARENT LOW BIDDER

VANCE BROTHERS, INC.
380 W 62nd Ave
Denver, CO 80216

The EXECUTIVE DIRECTOR OF THE DEPARTMENT OF TRANSPORTATION AND INFRASTRUCTURE has considered the Bids submitted on **January 21, 2021**, for work to be done and materials to be furnished in and for:

CONTRACT 202057115 – 2021 CITYWIDE CHIP SEAL AND CRACK SEAL

as set forth in detail in the Contract Documents for the City and County of Denver, Colorado. It appears that your Bid is fair, equitable, and to the best interest of the City and County; therefore, said Bid is hereby accepted at the bid price contained herein, subject to the approval and execution of the Contract Documents by the City in accordance with the Charter of the City and County of Denver, and to your furnishing the items specified below. The award is based on the total bid items: **Twelve (12) bid items (408-1 through 630-2)** the total estimated cost thereof being: **Four Million Four Hundred Thirteen Thousand Nine Hundred Sixty Dollars and No Cents (\$4,413,960.00)**.

In accordance with the requirements set forth in the Contract Documents, you are required to furnish the following documents:

- a. Insurance Certificates: Commercial General Liability, Business Automobile, and Workers Compensation; and
- b. Payment and Performance Bond along with One original Power of Attorney relative to Performance and/or Payment Bond.

All construction Contracts made and entered into by the City and County of Denver are subject to Affirmative Action and Equal Opportunity Rules and Regulations, as adopted by the Manager of the Department of Transportation and Infrastructure, and each contract requiring payment by the City of one-half million dollars (\$500,000.00) or more shall first be approved by the City Council acting by ordinance and in accordance with Section 3.2.6 of the Charter of the City and County of Denver.

Prior to issuance of Notice to Proceed, all Equal Opportunity requirements must be completed. Additional information may be obtained by contacting the Director of DSBO at (720-913-1999).

City and County of Denver Department of Transportation & Infrastructure
Office of the Executive Director
201 W. Colfax Avenue, Dept. 608 | Denver, CO 80202
www.denvergov.org/doti
Phone: 720-865-8630



NOTICE TO APPARENT LOW BIDDER


CONTRACT NO. 202057115

Page 2

The Bid Security submitted with your Bid, will be returned upon execution of the Contract and furnishing of the Performance Bond. In the event you should fail to execute the Contract and to furnish the performance Bond within the time limit specified, said Bid Security will be retained by the City and County of Denver as liquidated damages, and not as a penalty for the delay and extra work caused thereby.

Dated at Denver, Colorado this 25th day of March 2021.

CITY AND COUNTY OF DENVER

By: 
Eulois Cleckley, Executive Director
Department of Transportation and Infrastructure

cc: Treasury, DSBO, PM, Prevailing Wage, PRO, File

CITY AND COUNTY OF DENVER

STATE OF COLORADO



DENVER
THE MILE HIGH CITY

**DEPARTMENT OF TRANSPORTATION &
INFRASTRUCTURE**

Bid Form Package

Contract Number: 202057115

2021 Citywide Chip Seal and Crack Seal

December 16, 2020

**CITY AND COUNTY OF DENVER
DEPARTMENT OF TRANSPORTATION AND INFRASTRUCTURE**

TABLE OF CONTENTS FOR BID FORM AND SUBMITTAL PACKAGE

| | |
|--|--------------|
| Table of Contents | BF-1 |
| Bidder's Checklist | BF-2 |
| Bid Form and Submittal Package Acknowledgment Form | BF-4 |
| Bid Form | BF-6 |
| 1A - List of Proposed Subcontractors, and/or Subconsultants, and/or Suppliers | BF-9 |
| Commitment to MWBE Participation | BF-13 |
| Letter(s) of Intent | BF-14 |
| Bid Bond | BF-15 |
| Diversity and Inclusiveness in City Solicitations Form | BF-16 |



DENVER

THE MILE HIGH CITY

This Checklist is provided solely for the assistance of the bidders, and need not be returned by Bidders with your BID FORM PACKAGE.

BIDDER'S CHECKLIST

These forms comprise the Bid Form and Submittal Package. Please note that a copy of the executed bid bond is to be submitted via QuestCDN at the time of bid opening, and that the original bid bond must be mailed and received within 7 calendar days after the bid due date.

Bidders must utilize the Bid Worksheet in the online bidding section of QuestCDN to submit their bid item pricing. The totals from the worksheet are required on page BF-7 of the Submittal Package.

| FORM/ PAGE NO. | COMMENTS | COMPLETE |
|---------------------------|--|--|
| BF-4 – BF-5 | a.) Legal name, address, Acknowledgment signature and attestation (if required) | <input type="checkbox"/> |
| BF-6+ | a.) Complete all blanks b.) Legal name required | <input type="checkbox"/> <input type="checkbox"/> |
| BF-7 | a.) Write out bid total or bid totals in words and figures in the blank form space(s) provided. b.) Calculate Textura® Construction Payment Management System Fee from chart on pg. BF-3 and write fee in the space provided. | <input type="checkbox"/> <input type="checkbox"/> |
| BF-8 | a.) List all subcontractors who are performing work on this project. | <input type="checkbox"/> |
| BF-9 – BF-10 | a.) Fully complete Form 1A - List of Proposed Subcontractors, Subconsultants, and/or Suppliers ('Base Bid Total' from BF-7 = 'Total Contract Value') | <input type="checkbox"/> |
| BF-11 | a.) Complete all blanks b.) If Addenda have been issued, complete bottom section. | <input type="checkbox"/> <input type="checkbox"/> |
| BF-12 | a.) Complete appropriate sections - signature(s) required. b.) If corporation, then corporate seal required. | <input type="checkbox"/> <input type="checkbox"/> |
| BF-13 | a.) Fully complete Commitment to Participation | <input type="checkbox"/> |
| BF-14 | a.) Fully complete Letter(s) of Intent | <input type="checkbox"/> |
| BF-16 | a.) Fill in all Bid Bond blanks b.) Signatures required c.) Corporate Seal if required d.) Dated e.) Attach Surety Agents Power of Attorney or Certified or cashier's check made out to the Manager of Revenue referencing Bidder's Company and Contract Number. | <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> |
| BF-17- BF-20 | a.) Each bidder, as a condition of responsiveness to this solicitation, shall <u>complete and return</u> the "Diversity and Inclusiveness in City Solicitations Information Request Form" with their Bid. | <input type="checkbox"/> |

Textura® Construction Payment Management System (“Textura”)

Bidder recognizes and agrees that it shall be required to use the Textura® Construction Payment Management System (“Textura”) for this Project to request payment from the City and to pay all first tier subcontractors and suppliers and further record payment to all certified subcontractors or suppliers that are listed for participation towards any assigned program goal. All fees associated with Textura are to be paid by the bidder for billings for work performed. Bidders are required, when preparing a bid, to enter the price of Textura on the line provided for the service on the Bid Worksheet. The fee is all inclusive of all subcontractor, project and subscription fees associated with Textura. The bidder will calculate the fee based on their Base Bid Total (including Force Accounts and Allowances but not including any alternates, if applicable) and the table below, and then include it on the line item provided in the bid form labeled “Textura® Fee”. This expense becomes part of the contract and billable to the City. All costs including, but not limited to, costs associated with training, entering data, and/or utilizing Textura other than the Textura Construction Payment Management System Fee are overhead and shall not be reimbursed by the City. Bidder will be responsible for any tax on the Textura fee. As with other taxes, the City will not reimburse bidder for this cost and therefore this cost should be included in bidder’s bid. Textura will invoice the awarded bidder directly.

| Project Value | Project Fee (GC + Sub Usage) |
|--------------------------------------|---------------------------------|
| \$100,000 – 249,999.99 | \$780 |
| \$250,000 - \$499,999.99 | \$1,625 |
| \$500,000 - \$999,999.99 | \$3,250 |
| \$1,000,000 - \$2,999,999.99 | \$5,850 |
| \$3,000,000 - \$4,999,999.99 | \$9,100 |
| \$5,000,000 - \$9,999,999.99 | \$12,220 |
| \$10,000,000 - \$19,999,999.99 | \$20,345 |
| \$20,000,000 - \$49,999,999.99 | \$32,500 |
| \$50,000,000 - \$99,999,999.99 | \$48,750 |
| \$100,000,000 - \$199,999,999.99 | \$69,095 |
| \$200,000,000 - \$299,999,999.99 | \$85,345 |
| \$300,000,000 - \$399,999,999.99 | \$109,720 |
| \$400,000,000 - \$499,999,999.99 | \$142,220 |
| \$500,000,000 - \$999,999,999.99 | \$162,500 |
| \$1,000,000,000 - \$1,999,999,999.99 | \$345,345 |
| \$2,000,000,000 - \$4,999,999,999.99 | \$650,000 |
| \$5,000,000,000 - \$9,999,999,999.99 | \$1,015,625 |
| \$10,000,000,000 or greater | \$1,503,125 |

For more information:

<http://www.denvergov.org/content/denvergov/en/contract-administration/bidding-process.html>

[REMAINDER OF PAGE INTENTIONALLY LEFT BLANK]

**CITY AND COUNTY OF DENVER
DEPARTMENT OF TRANSPORTATION AND INFRASTRUCTURE
BID FORM AND SUBMITTAL PACKAGE ACKNOWLEDGMENT**

CONTRACT NO. 202057115

2021 CITYWIDE CHIP SEAL AND CRACK SEAL

BIDDER: Vance Brothers, Inc.
(Legal Name per Colorado Secretary of State)

ADDRESS: 380 West 62nd Avenue
Denver, CO 80216

CONTACT PERSON FOR ALL MATTERS RELATING TO THIS DOCUMENT

NAME: Katherine Miller **TITLE:** Contract Administrator
EMAIL: kmiller@vancebrothers.com **PHONE NUMBER:** (303) 341-2604

AUTHORIZED ELECTRONIC SIGNATORY

NAME: Michael W. Vance
EMAIL: mvance@vancebrothers.com

The undersigned bidder states that the undersigned bidder has received and had an opportunity to fully and thoroughly examine a complete set of the Contract Documents for **Contract No. 202057115 - 2021 Citywide Chip Seal and Crack Seal**, made available to the undersigned bidder pursuant to Notice of Invitation for Bids dated December 16, 2020.

The undersigned bidder acknowledges that a complete and final set of the Contract Documents for the referenced Project, the components of which are identified below, are bound and maintained as the record set of Contract Documents by the Contract Administration Division of the Department of Transportation and Infrastructure and that this Record Set is available for examination by the undersigned bidder.

The undersigned bidder, having thoroughly examined each of the components identified below and contained in Contract Documents, **HEREBY SUBMITS THIS BID FORM AND SUBMITTAL PACKAGE**, fully understanding that the Contract Documents, as defined in Paragraph 1 of the contract, including this executed Bid Form and Submittal Package, constitute all of the terms, conditions and requirements upon which this submission is based and further understanding that, by submission of this Bid Form and Submittal Package, the City shall rely on the representations and commitments of the undersigned bidder contained herein.

The following completed documents comprising this Bid Form and Submittal Package will be included with and, by this reference, are expressly incorporated into the Contract Documents specified at Paragraph 1 of the Contract:

Bid Form and Submittal Package Acknowledgment Form
Bid Form
List of Proposed Minority/Women Owned Business Enterprise(s)
Commitment to Minority/Women Owned Business Enterprise Participation
Minority/Women Owned Business Enterprise(s) of Intent
Letter of Intent
Bid Bond
Certificate of Insurance

The following designated documents constitute that portion of the Contract Documents made available by the Notice of Invitation for Bids, but not included in the Bid Form and Submittal Package:

Notice of Invitation for Bids
Instructions to Bidders
Addenda (as applicable)
Equal Employment Opportunity Provisions (Appendix A and Appendix F)
Contract Form
General Contract Conditions
Special Contract Conditions
Performance and Payment Bond
Notice to Apparent Low Bidder
Notice to Proceed
Contractor's Certification of Payment Form
Final Release and Certificate of Payment
Certificate of Contract Receipt
Change Orders (as applicable)
Federal Requirements (as applicable)
Prevailing Wage Rate Schedule(s)
Technical Specifications
Contract Drawings
Accepted Shop Drawings

The undersigned bidder expressly assumes responsibility for the complete contents of these designated documents as bound together with the Bid Form and Submittal Package submitted herewith and designated the Contract Documents.

IN WITNESS WHEREOF, the undersigned bidder has signed personally or by duly authorized officer or agent and duly attested.

BIDDER:

Name: Vance Brothers, Inc.

By: 

Title: Michael W. Vance, Vice President

ATTEST:

By: 

Joshua C. Williams, Secretary

[SEAL]



**CITY AND COUNTY OF DENVER
DEPARTMENT OF TRANSPORTATION AND INFRASTRUCTURE**

BID FORM

CONTRACT NO. 202057115

2021 CITYWIDE CHIP SEAL AND CRACK SEAL

BIDDER: Vance Brothers, Inc.
(Legal Name per Colorado Secretary of State)

TO: The Manager of the Department of Transportation and Infrastructure
City and County of Denver
c/o Contract Administration
201 West Colfax, Dept. 614
Denver, Colorado 80202

The Undersigned Bidder, having examined the plans, technical specifications, and remainder of the proposed Contract Documents as designated and enumerated in the General and Special Contract Conditions and any and all addenda thereto; having investigated the location of and conditions affecting the proposed Work; and being acquainted with and fully understanding the extent and character of the Work covered by this bid, and all factors and conditions affecting or which may be affected by Work, HEREBY SUBMITS THIS BID, pursuant to an advertisement of a Notice of Invitation for Bids as published on **December 16, 2020**, to furnish all required materials, tools, appliances, equipment and plant; to perform all necessary labor and to undertake and complete: **Contract No. 202057115 - 2021 Citywide Chip Seal and Crack Seal**, in Denver, Colorado, in full accordance with and conformity to the Plans, Technical Specifications, and Contract Documents hereto attached or by reference made a part hereof, at and for the following price(s) set forth on this Bid Form.

The following documents, which taken as a whole constitute the Contract Documents for this Project, and which are incorporated herein, by reference, were made available to the Bidder as provided in the Advertisement of Notice of Invitation for Bids, were received by the bidder, and form the basis for this bid:

Advertisement of Notice of Invitation for Bids
Instructions to Bidders
Commitment to MWBE Participation
Article III, Divisions 1 and 3 of Chapter 28, D.R.M.C.
Bid Bond
Addenda (as applicable)
Equal Employment Opportunity Provisions (Appendix A and Appendix F)
Bid Form
Contract Form
General Contract Conditions
Special Contract Conditions
Performance and Payment Bond
Notice to Apparent Low Bidder
Notice to Proceed
Contractor's Certification of Payment Form
Final Release and Certificate of Payment
Certificate of Contract Receipt
Change Orders (as applicable)
Federal Requirements (as applicable)
Prevailing Wage Rate Schedule(s)
Technical Specifications
Contract Drawing
Accepted Shop Drawings
Certificate of Insurance

2021 Citywide Chip Seal and Crack Seal

120 days

VANCE BROTHERS, INC.: Liberty Mutual
Insurance Company

Contract No. 202057115

| Bid Item | Description | Units | Qty | Unit Cost | Total Cost | Unit Bid | Total Bid |
|--|--|-------|-------|------------|-----------------------|------------|----------------|
| 408-1 | Crack Seal | TON | 155 | \$3,200.00 | \$496,000.00 | \$3,120.00 | \$483,600.00 |
| 408-2 | Mastic | LB | 2E+05 | \$2.10 | \$420,000.00 | \$1.88 | \$376,000.00 |
| 409-3 | Cape Seal (CRS-2P) | SY | 7E+05 | \$4.50 | \$3,105,000.00 | \$4.87 | \$3,360,300.00 |
| 626-1 | Remobilization | EA | 1 | \$5,000.00 | \$5,000.00 | \$5,000.00 | \$5,000.00 |
| 627-1 | Pavement Marking Paint (Waterborne) | GAL | 15 | \$120.00 | \$1,800.00 | \$150.00 | \$2,250.00 |
| 627-2 | Epoxy (Lane Marking Alternative) | GAL | 35 | \$630.00 | \$22,050.00 | \$280.00 | \$9,800.00 |
| 627-3 | Thermoplastic Pavement Marking (Lane markings) | SF | 1000 | \$10.00 | \$10,000.00 | \$7.70 | \$7,700.00 |
| 627-4 | Preformed Thermoplastic Pavement Marking (X-Walk, Stop Line) | SF | 3000 | \$12.00 | \$36,000.00 | \$11.00 | \$33,000.00 |
| 627-5 | Preformed Thermoplastic Pavement Marking (Word Symbol) | SF | 30 | \$24.00 | \$720.00 | \$17.00 | \$510.00 |
| 627-6 | Pavement Tabs | EA | 2000 | \$2.00 | \$4,000.00 | \$2.00 | \$4,000.00 |
| 630-1 | Traffic Control Arterial Streets | LS/DA | 12 | \$3,000.00 | \$36,000.00 | \$1,900.00 | \$22,800.00 |
| 630-2 | Traffic Control Collector/Local Streets | LS/DA | 37 | \$1,100.00 | \$40,700.00 | \$2,700.00 | \$99,900.00 |
| Engineers Estimate of Base Bid Total: | | | | | \$4,177,270.00 | | |

| | |
|-------------------------------|----------------|
| BID ITEMS TOTAL AMOUNT | \$4,404,860.00 |
|-------------------------------|----------------|

| | |
|--------------------|------------|
| TEXTURA FEE | \$9,100.00 |
|--------------------|------------|

| | |
|--|-----------------------|
| | \$4,413,960.00 |
|--|-----------------------|

Sum of estimated cost for item numbers (408-1 through 630-2) and the Textura Fee equals Total Base Bid Amount:
four million, four hundred thirteen thousand, nine hundred sixty dollars & no cents

Dollars (\$ 4,413,960.00)

If the Manager mails a written Notice of Apparent Low Bidder, addressed to the Bidder's business address stated on this Bid Form, the Undersigned Bidder shall, in accordance with the Contract Documents, be ready to, and shall, within five (5) days after the date of the Notice: (i) execute the attached form of Contract in conformity with this bid; (ii) furnish the required proofs of insurance; and (iii) furnish the required bond or bonds in the sum of the full amount of this bid, executed by a surety company acceptable to the Manager.

The Liberty Mutual Insurance Company, a corporation of the State of MA, is hereby offered as Surety on said bond. If such surety is not approved by the Manager, another and satisfactory surety company shall be furnished.

Enclosed with this bid is a bid guarantee, as defined in the attached Instructions to Bidders, in the amount of 5%. The Undersigned Bidder agrees that the entire amount of this bid guarantee is to be paid to and become the property of the City as liquidated damages, and not as a penalty, if: (i) the bid is considered to be the best by the City; (ii) the City notifies the Undersigned Bidder that it is the Apparent Low Bidder; and (iii) the Undersigned Bidder fails to execute the Contract in the form prescribed or to furnish the required bond and proofs of insurance, within five (5) days after the date of such notification.

The following persons, firms or corporations are interested with the Undersigned Bidder in this bid:

Name: Vance Brothers, Inc. Name: N/A

Address: 380 West 62nd Avenue Address: N/A
Denver, CO 80216

If there are no such persons, firms, or corporations, please so state in the following space:

The Undersigned Bidder proposes to subcontract the following Work in accordance with General Contract Conditions, Title 5, SUBCONTRACTS, and represents that, to the greatest degree practical, all subcontractors known at the time of bid submittal have been identified.

| Item of Work | Percent (%) of Total; Work | Proposed Subcontractor and Address |
|-------------------------|----------------------------|---|
| <u>trucking</u> | <u>3.62%</u> | <u>Tom Calabrese Trucking, Inc.</u> 6441 Osceola Street Arvada, CO 80003 |
| <u>traffic control</u> | <u>2.72%</u> | <u>American Sign & Striping Company</u> 14883 E Hindsdale Ave #3 Englewood, CO 80112 |
| <u>sweeping</u> | <u>1.41%</u> | <u>Allstate Sweeping, Inc.</u> 10150 E 106th Ave Brighton, CO 80601 |
| <u>crackseal,mastic</u> | <u>18%</u> | <u>Coatings Inc.</u> 5903 Lamar Street Arvada, CO 80003 |
| <u>striping</u> | <u>1.25%</u> | <u>American Striping Company</u> 6829 S Dawson Cir Centennial, CO 80112 |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

(Copy this page if additional room is required.)



**DIVISION OF SMALL BUSINESS OPPORTUNITY (DSBO)
1A - LIST OF PROPOSED SUBCONTRACTORS, SUBCONSULTANTS,
AND/OR SUPPLIERS**

City & County of Denver Contract No.: 202057115

The undersigned proposes to utilize all listed firms. Any certified firm listed must be certified by the City and County of Denver and a **Letter of Intent (LOI)** submitted for each. If additional pages are required, please copy and attach the second page. This form must be updated and submitted to DSBO when subcontractors, subconsultants, and/or suppliers are added throughout the contract duration.

| Contractor/Consultant | | |
|--|---------------------------------|--|
| Name of Firm: Vance Brothers, Inc. | | <input type="checkbox"/> MWBE (v) <input type="checkbox"/> SBE (v) <input type="checkbox"/> DBE (v) <input type="checkbox"/> EBE (v) |
| Firm's Representative: Heath Russo | | |
| Signature:  | | Date: 01/21/2021 |
| Address: 380 West 62nd Avenue | | |
| City: Denver | State: CO | Zip: 80602 |
| Phone: (303) 341-2604 | Email: hrusso@vancebrothers.com | |
| Total Contract Value \$: 4,413,960.00 | | Self-Performing Contract Value \$: 3,378,400.00 |

| Subcontractors, Subconsultants, and/or Suppliers | |
|--|---|
| Name of Firm: American Striping Company | <input checked="" type="checkbox"/> MWBE (v) <input checked="" type="checkbox"/> SBE (v) <input type="checkbox"/> DBE (v) <input checked="" type="checkbox"/> EBE (v) |
| Firm's Representative: Alejandra Harvey | |
| Phone: (303) 495-5950 | Email: alejandra@americanstripingcompany.com |
| Type of Service: striping | Contract Value \$: 55,000.00 |
| Anticipated Start Date: 05/2021 | Anticipated Completion Date: 09/2021 |

| | |
|--|--|
| Name of Firm: American Sign & Striping | <input checked="" type="checkbox"/> MWBE (v) <input checked="" type="checkbox"/> SBE (v) <input type="checkbox"/> DBE (v) <input type="checkbox"/> EBE (v) |
| Firm's Representative: Rhonda Collins | |
| Phone: (303) 680-3909 | Email: rhonda@americansgn.com |
| Type of Service: traffic control | Contract Value \$: 120,000.00 |
| Anticipated Start Date: 05/2021 | Anticipated Completion Date: 09/2021 |

| | |
|--|--|
| Name of Firm: Tom Calabrese Trucking, Inc. | <input checked="" type="checkbox"/> MWBE (v) <input checked="" type="checkbox"/> SBE (v) <input type="checkbox"/> DBE (v) <input type="checkbox"/> EBE (v) |
| Firm's Representative: Carol Calabrese | |
| Phone: (303) 487-8668 | Email: carol@tcalabresetrucking.com |
| Type of Service: trucking | Contract Value \$: 160,000.00 |
| Anticipated Start Date: 05/2021 | Anticipated Completion Date: 09/2021 |

| | |
|---|--------------------------------------|
| Name of Firm: Allstate Sweeping, Inc. <input checked="" type="checkbox"/> MWBE (v) <input checked="" type="checkbox"/> SBE (v) <input type="checkbox"/> DBE (v) <input checked="" type="checkbox"/> EBE (v) | |
| Firm's Representative: Martha Krueger | |
| Phone: (303) 293-8700 | Email: bhollis@allstatesweeping.net |
| Type of Service: sweeping | Contract Value \$: 62,500.00 |
| Anticipated Start Date: 05/2021 | Anticipated Completion Date: 09/2021 |

| | |
|--|------------------------------|
| Name of Firm: <input type="checkbox"/> MWBE (v) <input type="checkbox"/> SBE (v) <input type="checkbox"/> DBE (v) <input type="checkbox"/> EBE (v) | |
| Firm's Representative: | |
| Phone: | Email: |
| Type of Service: | Contract Value \$: |
| Anticipated Start Date: | Anticipated Completion Date: |

| | |
|--|------------------------------|
| Name of Firm: <input type="checkbox"/> MWBE (v) <input type="checkbox"/> SBE (v) <input type="checkbox"/> DBE (v) <input type="checkbox"/> EBE (v) | |
| Firm's Representative: | |
| Phone: | Email: |
| Type of Service: | Contract Value \$: |
| Anticipated Start Date: | Anticipated Completion Date: |

| | |
|--|------------------------------|
| Name of Firm: <input type="checkbox"/> MWBE (v) <input type="checkbox"/> SBE (v) <input type="checkbox"/> DBE (v) <input type="checkbox"/> EBE (v) | |
| Firm's Representative: | |
| Phone: | Email: |
| Type of Service: | Contract Value \$: |
| Anticipated Start Date: | Anticipated Completion Date: |

| | |
|--|------------------------------|
| Name of Firm: <input type="checkbox"/> MWBE (v) <input type="checkbox"/> SBE (v) <input type="checkbox"/> DBE (v) <input type="checkbox"/> EBE (v) | |
| Firm's Representative: | |
| Phone: | Email: |
| Type of Service: | Contract Value \$: |
| Anticipated Start Date: | Anticipated Completion Date: |

| | |
|--|------------------------------|
| Name of Firm: <input type="checkbox"/> MWBE (v) <input type="checkbox"/> SBE (v) <input type="checkbox"/> DBE (v) <input type="checkbox"/> EBE (v) | |
| Firm's Representative: | |
| Phone: | Email: |
| Type of Service: | Contract Value \$: |
| Anticipated Start Date: | Anticipated Completion Date: |

The undersigned Bidder acknowledges the right of the City to reject any or all bids submitted, to waive informalities in bids and to re-advertise this Project for bids.

The undersigned certifies that it has carefully checked all works and figures and all statements made in these Bid Forms.

This bid is submitted upon the declaration that neither, I (we), nor, to the best of my (our) knowledge, none of the members of my (our) firm or company have either directly or indirectly entered into any agreement, participated in any collusion or otherwise taken any action in restraint of free competitive bidding in connection with this bid.

Business Address of Bidder: 380 West 62nd Avenue

City, State, Zip Code: Denver, CO 80216

Telephone Number of Bidder: (303) 341-2604

Fax No. (303) 341-2036

Social Security or Federal Employer ID Number of Bidder: 44-0577983

Name and location of the last work of this kind herein contemplated upon which the Bidder was engaged:

2019 Citywide Chipseal & Crackseal

For information relative thereto, please refer to:

Name: Derek Miles

Title: Project Manager

Address: 201 W Colfax Avenue Denver, CO 80202

The undersigned acknowledges receipt, understanding, and full consideration of the following addenda to the Contract Documents:

Addenda Number 1 Date 01/08/2021

Addenda Number _____ Date _____


Addenda Number _____ Date _____


Dated this 21st day of January, 2021.

Signature of Bidder:

If an Individual: _____ doing business
as _____.

If a Partnership: _____
by: _____ General Partner.

If a Corporation: Vance Brothers, Inc.
a Missouri Corporation,
by: , its President.
Michael W. Vance, Vice President

Attest:
 Joshua C. Williams, Secretary
Secretary (Corporate Seal)



If a Joint Venture, signature of all Joint Venture participants.

Firm: _____

Corporation (), Partnership () or () Limited Liability Company

By: _____ (If a Corporation)
Attest: _____
Title: _____ Secretary (Corporate Seal)

Firm: _____

Corporation (), Partnership () or () Limited Liability Company

By: _____ (If a Corporation)
Attest: _____
Title: _____ Secretary (Corporate Seal)

Firm: _____

Corporation (), Partnership () or () Limited Liability Company

By: _____ (If a Corporation)
Attest: _____
Title: _____ Secretary (Corporate Seal)



**DIVISION OF SMALL BUSINESS OPPORTUNITY (DSBO)
COMMITMENT TO MWBE PARTICIPATION**

This page must be completed by all Bidders/Proposers to indicate their commitment towards satisfying the MWBE participation goal. The commitment will be incorporated into the contract and thereby the selected Bidder/Proposer's will be held to that commitment. (Please check the appropriate box):

COMPLETE IF YOU ARE A NON MWBE PRIME:

The City and County of Denver has specified a 9 % MWBE Participation goal on this project. The Bidder/Proposer is committed to meeting 9 % MWBE Participation on the contract.

COMPLETE IF YOU ARE A MWBE PRIME:

The City and County of Denver has specified a _____ % MWBE Participation goal on this project. The Bidder/Proposer is a certified MWBE with the City and County of Denver and is committed to meeting _____ % MWBE Participation on the contract.

COMPLETE IF YOU ARE UNABLE TO MEET PROJECT GOAL:

The City and County of Denver has specified a _____ % MWBE Participation goal on this project. The Bidder/Proposer is unable to meet this project goal but is committed to a _____ % MWBE Participation on the contract. The Bidder/Proposer must make adequate good faith efforts to meet this goal in order to be deemed responsive. The Bidder/Proposer must submit a detailed statement and documentation of their good faith efforts. Award of the contract will be conditioned on meeting the requirements of this section, in accordance of Chapter 28 of the D.R.M.C. to the Division of Small Business Opportunity.

The undersigned Bidder/Proposer hereby agrees and understands that they must comply with their MWBE commitments in this project in conformity with the Requirements, Terms, and Conditions of this MWBE Procurement/Contract Language.

Bidder/Proposer (Name of Firm): Vance Brothers, Inc.

Firm's Representative: Heath Russo

Title: Project Manager/Estimator

Signature (Firm's Representative): 

Date: 01/21/2021

Address: 380 West 62nd Avenue

| | | |
|-----------------------|---------------------------------|------------|
| City: Denver | State: CO | Zip: 80216 |
| Phone: (303) 341-2604 | Email: hrusso@vancebrothers.com | |

Revised 7/14/2020



DIVISION OF SMALL BUSINESS OPPORTUNITY (DSBO) LETTER OF INTENT (LOI)

Contract No.: 202057115

Project Name: 2021 Citywide Chip Seal & Crack Seal

A. The undersigned Bidder/Proposer intends to engage the undersigned MWBE, SBE, EBE or DBE to perform work if awarded the contract. This Letter of Intent Must be Signed by the Bidder/Proposer and MWBE, SBE, EBE or DBE. Certified self-performing Prime must complete both sections A and B. If the MWBE, SBE, EBE or DBE is a lower tier, section C must be completed and signed by the firm directly utilizing the certified firm.

Bidder/Proposer (Name of Firm): Vance Brothers, Inc. Self-Performing: [] Yes [x] No
Firm's Representative: Heath Russo Title: Project Manager/Estimator
Signature (Firm's Representative): [Signature] Date: 01/21/2021
Address: 380 West 62nd Avenue
City: Denver State: CO Zip: 80602
Phone: (303) 341-2604 Email: hrusso@vancebrothers.com

B. The Following Section is To Be Completed by the MWBE, SBE, EBE or DBE, at any tier. Identify the scope of the work and NAICS code(s) to be performed and/or supply item that will be provided by the MWBE, SBE, EBE or DBE.

Name of Firm: American Striping Company [x] MWBE(v) [x] SBE(v) [x] EBE(v) [] DBE(v)
Firm's Representative: Alejandra Harvey Title: Owner
Signature: [Signature] Date: 01/21/2021
Address: 6829 S Dawson Circle
City: Centennial State: CO Zip: 80112
Phone: (303) 495-5950 Email: alejandra@americanstripingcompany.com

Scope of Work: striping
NAICS Code(s): 237310

The Bidder/Proposer intends to utilize the aforementioned MWBE, SBE, EBE or DBE for the Work/Supply described above. The cost of the work and percentage of the total subcontractor MWBE, SBE, EBE or DBE bid amount is:

\$ 55,000.00 1.25 %

C. Lower Tier Utilization: If the certified firm is not a direct first tier subcontractor, subconsultant, and/or supplier to the Bidder/Proposer, please indicate the name of the firm that is utilizing the certified firm:

Name of Firm:
Firm's Representative: Title:
Signature: Date:

If the above-named Bidder/Proposer is not determined to be the successful Bidder/Proposer, this Letter of Intent shall be null and void.

DSBO Version 1 Last Revised: June 5, 2020



DIVISION OF SMALL BUSINESS OPPORTUNITY (DSBO) LETTER OF INTENT (LOI)

Contract No.:

Project Name:

A. The undersigned Bidder/Proposer intends to engage the undersigned MWBE, SBE, EBE or DBE to perform work if awarded the contract. This Letter of Intent Must be Signed by the Bidder/Proposer and MWBE, SBE, EBE or DBE. Certified self-performing Prime must complete both sections A and B. If the MWBE, SBE, EBE or DBE is a lower tier, section C must be completed and signed by the firm directly utilizing the certified firm.

Bidder/Proposer (Name of Firm): Vance Brothers, Inc. Self-Performing: [] Yes [x] No
Firm's Representative: Heath Russo Title: Project Manager/Estimator
Signature (Firm's Representative): [Signature] Date: 01/21/2021
Address: 380 West 62nd Avenue
City: Denver State: CO Zip: 80216
Phone: (303) 341-2604 Email: hrusso@vancebrothers.com

B. The Following Section is To Be Completed by the MWBE, SBE, EBE or DBE, at any tier. Identify the scope of the work and NAICS code(s) to be performed and/or supply item that will be provided by the MWBE, SBE, EBE or DBE.

Name of Firm: American Sign [x] MWBE(v) [x] SBE(v) [x] EBE(v) [] DBE(v)
Firm's Representative: Rhonda Collins Title: Owner
Signature: Rhonda Collins Date: 01/21/2021
Address: 14883 E Hindsdale Ave Unit 3
City: Englewood State: CO Zip: 80112
Phone: (303) 680-3909 Email: rhonda@americansgn.com
Scope of Work: traffic control

NAICS Code(s): 561990

The Bidder/Proposer intends to utilize the aforementioned MWBE, SBE, EBE or DBE for the Work/Supply described above. The cost of the work and percentage of the total subcontractor MWBE, SBE, EBE or DBE bid amount is:

\$ 120,000.00 % 2.72

C. Lower Tier Utilization: If the certified firm is not a direct first tier subcontractor, subconsultant, and/or supplier to the Bidder/Proposer, please indicate the name of the firm that is utilizing the certified firm:

Name of Firm:
Firm's Representative: Title:
Signature: Date:

If the above-named Bidder/Proposer is not determined to be the successful Bidder/Proposer, this Letter of Intent shall be null and void.

DSBO Version 1 Last Revised: June 5, 2020



DIVISION OF SMALL BUSINESS OPPORTUNITY (DSBO) LETTER OF INTENT (LOI)

Contract No.:

Project Name:

A. The undersigned Bidder/Proposer intends to engage the undersigned MWBE, SBE, EBE or DBE to perform work if awarded the contract. This Letter of Intent Must be Signed by the Bidder/Proposer and MWBE, SBE, EBE or DBE. Certified self-performing Prime must complete both sections A and B. If the MWBE, SBE, EBE or DBE is a lower tier, section C must be completed and signed by the firm directly utilizing the certified firm.

Bidder/Proposer (Name of Firm): Vance Brothers, Inc. Self-Performing: [] Yes [x] No

Firm's Representative: Heath Russo Title: Project Manager/Estimator

Signature (Firm's Representative): [Signature] Date: 01/21/2021

Address: 380 West 62nd Avenue

City: Denver State: CO Zip: 80216

Phone: (303) 341-2604 Email: hrusso@vancebrothers.com

B. The Following Section is To Be Completed by the MWBE, SBE, EBE or DBE, at any tier. Identify the scope of the work and NAICS code(s) to be performed and/or supply item that will be provided by the MWBE, SBE, EBE or DBE.

Name of Firm: Tom Calabrese Trucking, Inc. [x] MWBE(v) [x] SBE(v) [] EBE(v) [] DBE(v)

Firm's Representative: Carol Calabrese Title: President

Signature: [Signature] Date: 01/21/2021

Address: 6441 Osceola Street

City: Arvada State: CO Zip: 80003

Phone: (303) 487-8668 Email: carol@tcalabresetrucking.com

Scope of Work: trucking

NAICS Code(s): 484220

The Bidder/Proposer intends to utilize the aforementioned MWBE, SBE, EBE or DBE for the Work/Supply described above. The cost of the work and percentage of the total subcontractor MWBE, SBE, EBE or DBE bid amount is:

\$ 160,000.00 3.62 %

C. Lower Tier Utilization: If the certified firm is not a direct first tier subcontractor, subconsultant, and/or supplier to the Bidder/Proposer, please indicate the name of the firm that is utilizing the certified firm:

Name of Firm:

Firm's Representative: Title:

Signature: Date:

If the above-named Bidder/Proposer is not determined to be the successful Bidder/Proposer, this Letter of Intent shall be null and void.

DSBO Version 1 Last Revised: June 5, 2020



DIVISION OF SMALL BUSINESS OPPORTUNITY (DSBO) LETTER OF INTENT (LOI)

Contract No.:

Project Name:

A. The undersigned Bidder/Proposer intends to engage the undersigned MWBE, SBE, EBE or DBE to perform work if awarded the contract. This Letter of Intent Must be Signed by the Bidder/Proposer and MWBE, SBE, EBE or DBE. Certified self-performing Prime must complete both sections A and B. If the MWBE, SBE, EBE or DBE is a lower tier, section C must be completed and signed by the firm directly utilizing the certified firm.

Bidder/Proposer (Name of Firm): Vance Brothers, Inc. Self-Performing: [] Yes [x] No
Firm's Representative: Heath Russo Title: Project Manager/Estimator
Signature (Firm's Representative): [Signature] Date: 01/21/2021
Address: 380 West 62nd Avenue
City: Denver State: CO Zip: 80216
Phone: (303) 341-2604 Email: hrusso@vancebrothers.com

B. The Following Section is To Be Completed by the MWBE, SBE, EBE or DBE, at any tier. Identify the scope of the work and NAICS code(s) to be performed and/or supply item that will be provided by the MWBE, SBE, EBE or DBE.

Name of Firm: Allstate Sweeping, Inc. [x] MWBE(v) [x] SBE(v) [x] EBE(v) [] DBE(v)
Firm's Representative: Barbara C. Hollis Title: Vice President
Signature: [Signature] Date: 01/21/2021
Address: 10150 E 160th Ave
City: Brighton State: CO Zip: 80601
Phone: (303) 293-8700 Email: bhollis@allstatesweeping.net
Scope of Work: sweeping

NAICS Code(s): 488490

The Bidder/Proposer intends to utilize the aforementioned MWBE, SBE, EBE or DBE for the Work/Supply described above. The cost of the work and percentage of the total subcontractor MWBE, SBE, EBE or DBE bid amount is:

Table with 2 columns: Amount (\$), Percentage (%). Row 1: 62,500.00, 1.42

C. Lower Tier Utilization: If the certified firm is not a direct first tier subcontractor, subconsultant, and/or supplier to the Bidder/Proposer, please indicate the name of the firm that is utilizing the certified firm:

Name of Firm:
Firm's Representative: Title:
Signature: Date:

If the above-named Bidder/Proposer is not determined to be the successful Bidder/Proposer, this Letter of Intent shall be null and void.

DSBO Version 1 Last Revised: June 5, 2020

CITY AND COUNTY OF DENVER
DEPARTMENT OF TRANSPORTATION AND INFRASTRUCTURE

BID BOND

KNOW ALL MEN BY THESE PRESENTS:


THAT Vance Brothers, Inc., 360 West 62nd Avenue, Denver, CO 80326, as Liberty Principal, and Liberty Mutual Insurance Company Phone No. 610-832-8240, a corporation organized and existing under and by virtue of the laws of the State of Massachusetts, and authorized to do business within the State of Colorado, as Surety, are held and firmly bound unto the City and County of Denver, Colorado, as Obligee, in full and just sum of FIVE (5%) PERCENT OF TOTAL AMOUNT BID Dollars, (\$ 5% of total amount bid), lawful money of the United States, for the payment of which sum, well and truly to be made, we bind ourselves, our heirs, executors, administrators, successors and assigns, jointly and severally, firmly by these presents:

WHEREAS, the said Principal is hcrewith submitting its bid, dated January 21, 2021, 20 , for the construction of: **Contract No. 202057115 - 2021 Citywide Chip Seal and Crack Seal**, as set forth in detail in the Contract Documents for the City and County of Denver, Colorado, and said Obligee has required as a condition for receiving said bid that the Principal deposit specified bid security in the amount of not less than five percent (5%) of the amount of said bid, as it relates to work to be performed for the City, conditioned that in event of failure of the Principal to execute the Contract, for such construction and furnish required Performance and Payment Bond if the contract is offered him that said sum be paid immediately to the Obligee as liquidated damages, and not as a penalty, for the Principal's failure to perform.

The condition of this obligation is such that if the aforesaid Principal shall, within the period specified therefore, on the prescribed form presented to him for signature, enter into a written contract with the Obligee in accordance with his bid as accepted and give Performance and Payment Bond with good and sufficient surety or sureties, upon the form prescribed by the Obligee, for the faithful performance and the proper fulfillment of said Contract, or in the event of withdrawal of said bid within the time specified, or upon the payment to the Obligee of the sum determined upon herein, as liquidated damages and not as penalty, in the event the Principal fails to enter into said contract and give such Performance and Payment Bond within the time specified, then this Obligation shall be null and void, otherwise to remain in full force and effect.


Signed, sealed and delivered this 21st day of January, 2021.

ATTEST


Secretary Joshua C. Williams

Vance Brothers, Inc.

Principal

By: 

Title: Michael W. Vance, Vice President

Liberty Mutual Insurance Company
2200 Renaissance Boulevard, Ste. 400, King of Prussia, PA 19406-2755

Surety

By: 
Linda L. Nutt, Attorney-in-Fact

[SEAL]

Seal if Bidder is Corporation
(Attach Power-of-Attorney)

This Power of Attorney limits the acts of those named herein, and they have no authority to bind the Company except in the manner and to the extent herein stated. Not valid for mortgage, note, loan, letter of credit, bank deposit, currency rate, interest rate or residual value guarantees. To confirm the validity of this Power of Attorney call 610-832-8240 between 9:00 am and 4:30 pm EST on any business day.



Liberty Mutual
SURETY

Liberty Mutual Insurance Company
The Ohio Casualty Insurance Company
West American Insurance Company

POWER OF ATTORNEY

KNOWN ALL PERSONS BY THESE PRESENTS: That The Ohio Casualty Insurance Company is a corporation duly organized under the laws of the State of New Hampshire, that Liberty Mutual Insurance Company is a corporation duly organized under the laws of the State of Massachusetts, and West American Insurance Company is a corporation duly organized under the laws of the State of Indiana (herein collectively called the "Companies"), pursuant to and by authority herein set forth, does hereby name, constitute and appoint, Linda L. Nutt of the city of Kansas City, state of MO its true and lawful attorney-in-fact, with full power and authority hereby conferred to sign, execute and acknowledge the following surety bond:

Principal Name: Vance Brothers, Inc.

Obligee Name: City & County of Denver

Surety Bond Number: Bid Bond

Bond Amount: See Bond Form

IN WITNESS WHEREOF, this Power of Attorney has been subscribed by an authorized officer or official of the Companies and the corporate seals of the Companies have been affixed thereto this 12th day of December, 2018.



The Ohio Casualty Insurance Company
Liberty Mutual Insurance Company
West American Insurance Company

By: David M. Carey
David M. Carey, Assistant Secretary

STATE OF PENNSYLVANIA ss
COUNTY OF MONTGOMERY

On this 12th day of December, 2018, before me personally appeared David M. Carey, who acknowledged himself to be the Assistant Secretary of Liberty Mutual Insurance Company, The Ohio Casualty Company, and West American Insurance Company, and that he, as such, being authorized so to do, execute the foregoing instrument for the purposes therein contained by signing on behalf of the corporations by himself as a duly authorized officer.

IN WITNESS WHEREOF, I have hereunto subscribed my name and affixed my notarial seal at King of Prussia, Pennsylvania, on the day and year first above written.



COMMONWEALTH OF PENNSYLVANIA
Notarial Seal
Teresa Pastella, Notary Public
Upper Merion Twp., Montgomery County
My Commission Expires March 28, 2021
Member, Pennsylvania Association of Notaries

By: Teresa Pastella
Teresa Pastella, Notary Public

This Power of Attorney is made and executed pursuant to and by authority of the following By-laws and Authorizations of Liberty Mutual Insurance Company, The Ohio Casualty Insurance Company, and West American Insurance Company which resolutions are now in full force and effect reading as follows:

ARTICLE IV – OFFICERS – Section 12. Power of Attorney. Any officer or other official of the Corporation authorized for that purpose in writing by the Chairman or the President, and subject to such limitation as the Chairman or the President may prescribe, shall appoint such attorneys-in-fact, as may be necessary to act in behalf of the Corporation to make, execute, seal, acknowledge and deliver as surety any and all undertakings, bonds, recognizances and other surety obligations. Such attorneys-in-fact, subject to the limitations set forth in their respective powers of attorney, shall have full power to bind the Corporation by their signature and execution of any such instruments and to attach thereto the seal of the Corporation. When so executed, such instruments shall be as binding as if signed by the President and attested to by the Secretary. Any power or authority granted to any representative or attorney-in-fact under the provisions of this article may be revoked at any time by the Board, the Chairman, the President or by the officer or officers granting such power or authority.

ARTICLE XIII – Execution of Contracts – SECTION 5. Surety Bonds and Undertakings. Any officer of the Company authorized for that purpose in writing by the chairman or the president, and subject to such limitations as the chairman or the president may prescribe, shall appoint such attorneys-in-fact, as may be necessary to act in behalf of the Company to make, execute, seal, acknowledge and deliver as surety any and all undertakings, bonds, recognizances and other surety obligations. Such attorneys-in-fact subject to the limitations set forth in their respective powers of attorney, shall have full power to bind the Company by their signature and execution of any such instruments and to attach thereto the seal of the Company. When so executed such instruments shall be as binding as if signed by the president and attested by the secretary.

Certificate of Designation – The President of the Company, acting pursuant to the Bylaws of the Company, authorizes David M. Carey, Assistant Secretary to appoint such attorneys-in-fact as may be necessary to act on behalf of the Company to make, execute, seal, acknowledge and deliver as surety any and all undertakings, bonds, recognizances and other surety obligations.


Authorization – By unanimous consent of the Company's Board of Directors, the Company consents that facsimile or mechanically reproduced signature of any assistant secretary of the Company, wherever appearing upon a certified copy of any power of attorney issued by the Company in connection with surety bonds, shall be valid and binding upon the Company with the same force and effect as though manually affixed.

I, Renee C. Llewellyn, the undersigned, Assistant Secretary, of Liberty Mutual Insurance Company, The Ohio Casualty Insurance Company, and West American Insurance Company do hereby certify that this power of attorney executed by said Companies is in full force and effect and has not been revoked.

IN TESTIMONY WHEREOF, I have hereunto set my hand and affixed the seals of said Companies this 21st day of January, 2021.



By: Renee C. Llewellyn
Renee C. Llewellyn, Assistant Secretary



Diversity and Inclusiveness* in City Solicitations Information Request Form

Denver Executive Order No. 101 establishes strategies between the City and private industry to use diversity and inclusiveness to promote economic development in the City and County of Denver and to encourage more businesses to compete for City contracts and procurements. The Executive Order requires, among other things, the collection of certain information regarding the practices of the City's contractors and consultants toward diversity and inclusiveness and encourages/requires City agencies to include diversity and inclusiveness policies in selection criteria where legally permitted in solicitations for City services or goods.

Answer each question below. Missing or incomplete responses will be recorded as "no", "not applicable", or "none". **A proposal or response to a solicitation by a contractor/consultant that does not include this completed form shall be deemed non-responsive and rejected.**

Business Email Address * mhughes@vancebrothers.com

Enter Email Address of City and County of Denver contact person facilitating this solicitation * pw.procurement@denvergov.org

Project Name * 2021 Citywide Chip Seal & Crack Seal

Solicitation No. (Check Below if Not Applicable) * 202057115

Check Here if Solicitation No. is N/A

Name of Your Company * Vance Brothers, Inc.

What Industry is Your Business? *

- | | | |
|---|---|---|
| <input type="checkbox"/> Technology | <input type="checkbox"/> Financial | <input type="checkbox"/> Manufacturing |
| <input checked="" type="checkbox"/> Construction, Landscape, Maintenance Services | <input type="checkbox"/> Goods/Services | <input type="checkbox"/> Wholesale/Retail Trade |
| <input type="checkbox"/> Professional | <input type="checkbox"/> Transportation/Hauling | <input type="checkbox"/> Other |

Address * 380 West 62nd Avenue

City * Denver **State** CO **Zip Code *** 80602

Business Phone Number * (303) 341-2604

Business Facsimile Number (303) 341-2036

1. How many employees does your company employ? *

- 1-10 51-100
 11-50 Over 100

1.1 How many of your employees are:

Number of Full Time: * 229 **Number of Part Time: *** 0

2. Do you have a Diversity and Inclusiveness Program? *

- Yes No

If **No**, and your company size is less than 10 employees continue to question 10. Complete and sign the form.

If **Yes**, does it address:

2.1. Employment and retention? *

- Yes No

2.2. Procurement and supply chain activities? *

- Yes No

2.3. Customer Service? *

- Yes No

3. Provide a detailed narrative of your company's diversity and inclusiveness principles and programs. This may include, for example, (i) diversity and inclusiveness employee training programs, equal opportunity policies, and the budget amount spent on an annual basis for workplace diversity; or (ii) diversity and inclusiveness training and information to improve customer service. (If Not Applicable, please type N/A below) *

EEO Policy & Affirmative Action Plan

4. Does your company regularly communicate its diversity and inclusiveness policies to employees? *

- Yes No

If you answered Yes to Question 4, how does your company regularly communicate its diversity and inclusiveness policies to employees? (Select all that apply) *

- Employee Training
 Pamphlets
 Public EEO Postings
 Other: *EMPLOYEE HANDBOOK*

5. How often do you provide training and diversity and inclusiveness principles? *

- Monthly
- Quarterly
- Annually
- N/A
- Other: *Upon hire and recall*

5.1 What percentage of the total number of employees generally participate? *

- 0-25%
- 26-50%
- 51-75%
- 76-100% *of incoming*
- N/A

6. State how you achieve diversity and inclusiveness in supply and procurement activities. This may include, for example, narratives of training programs, equal opportunity policies, diversity or inclusiveness partnership programs, mentoring and outreach programs, and the amount and description of budget spent on an annual basis for procurement and supplier diversity and inclusiveness. (If Not Applicable, please type N/A below) *

EEO Policy & Affirmative Action Plan

7. Do you have a diversity and inclusiveness committee? *

- Yes
- No

7.1 If Yes, how often does it meet? *

- Monthly
- Quarterly
- Annually
- Other:

7.2. If you responded that you do not have a diversity and inclusiveness committee, describe any plans your company may have to establish such a committee. (If Not Applicable, please type N/A below) *

NONE

8. Do you have a budget for diversity and inclusiveness efforts? *

Yes No

9. Does your company integrate diversity and inclusion competencies into executive/manager performance evaluation plans? *

Yes No

10. If you responded that you do not have a diversity and inclusiveness program, describe any plans your company may have to adopt such a program.

11. Would you like information detailing how to implement a Diversity and Inclusiveness program? *

Yes No

If yes, please email XO101@denvergov.org.

I attest that the information represented herein is true, correct and complete, to the best of my knowledge. *

Marianne Hughes 1/19/2021
Signature of Person Completing Form * Date

MARIANNE HUGHES
Printed Name of Person Completing Form

NOTE: Attach additional sheets or documentation as necessary for a complete response.

*"Diversity and Inclusiveness Program" means a program that invites values, perspectives and contributions of people from diverse backgrounds, and integrates diversity into its hiring and retention policies, training opportunities, and business development methods to provide an equal opportunity for each person to participate, contribute, and succeed within the organization's workplace. "Diversity" encompasses a wide variety of human differences, including differences such as race, age, gender, gender identity, sexual orientation, ethnicity, physical disabilities, appearance, historically underutilized and disadvantaged persons, as well as social identities such as religion, marital status, socio-economic status, lifestyle, education, parental status, geographic background, language ability, and veteran status."

CITY AND COUNTY OF DENVER

STATE OF COLORADO



DENVER
THE MILE HIGH CITY

**DEPARTMENT OF TRANSPORTATION &
INFRASTRUCTURE**

Bid Documents Package

Contract Number: 202057115

2021 Citywide Chip Seal and Crack Seal

December 16, 2020

**CITY AND COUNTY OF DENVER
DEPARTMENT OF TRANSPORTATION AND INFRASTRUCTURE**

TABLE OF CONTENTS FOR CONTRACT DOCUMENTS

| <u>BID FORM AND SUBMITTAL PACKAGE</u> | <u>PAGE</u> |
|---|--------------------|
| Bid Form and Submittal Package (returned separately and incorporated as part of these contract documents) | |
| Table of Contents | BF-1 |
| Bidder's Checklist | BF-2 |
| Bid Form and Submittal Package Acknowledgment Form | BF-4 |
| Bid Form | BF-6 |
| 1A - List of Proposed Subcontractors, Subconsultants, and/or Suppliers | BF-9 |
| Commitment to MWBE Participation | BF-13 |
| Letter(s) of Intent | BF-14 |
| Bid Bond | BF-15 |
| Diversity and Inclusiveness in City Solicitations Form | BF-16 |
| <u>BID DOCUMENTS</u> | |
| Table of Contents | BDP-1 |
| Statement of Quantities | SQ-1 |
| Notice of Invitation for Bids | BDP-2 |
| Instructions to Bidders | BDP-4 |
| Equal Employment Opportunity Provisions | BDP-15 |
| Appendix A | BDP-19 |
| Appendix F | BDP-21 |
| Contract Form | BDP-31 |
| Index of the General Contract Conditions | BDP-36 |
| Special Contract Conditions | BDP-41 |
| Performance and Payment Bond Form | BDP-51 |
| Performance and Payment Bond Surety Authorization Letter (Sample)..... | BDP-53 |
| Notice to Apparent Low Bidder (Sample) | BDP-54 |
| Notice to Proceed (Sample) | BDP-56 |
| Certificate of Contract Release (Sample)..... | BDP-57 |
| Prevailing Wage Rate Schedule | 7 pages |
| Technical Specifications | 24 pages |



DENVER
THE MILE HIGH CITY

**CITY AND COUNTY OF DENVER
DEPARTMENT OF TRANSPORTATION AND INFRASTRUCTURE**

STATEMENT OF QUANTITIES

| Item No. | Description | Estimated Quantity |
|-----------------|--|---------------------------|
| 408-1 | Crack Seal | 155 TON |
| 408-2 | Mastic | 200,000 LB |
| 409-3 | Cape Seal (CRS-2P) | 690,000 SY |
| 626-1 | Remobilization | 1 EA |
| 627-1 | Pavement Marking Paint (Waterborne) | 15 GAL |
| 627-2 | Epoxy (Lane Marking Alternative) | 35 GAL |
| 627-3 | Thermoplastic Pavement Marking (Lane markings) | 1,000 SF |
| 627-4 | Preformed Thermoplastic Pavement Marking (X-Walk, Stop Line) | 3,000 SF |
| 627-5 | Preformed Thermoplastic Pavement Marking (Word Symbol) | 30 SF |
| 627-6 | Pavement Tabs | 2,000 EA |
| 630-1 | Traffic Control Arterial Streets | 12 LS/DAY |
| 630-2 | Traffic Control Collector/Local Streets | 37 LS/DAY |

CITY AND COUNTY OF DENVER

**NOTICE OF INVITATION FOR BIDS
FOR CONTRACT NO. 202057115**

2021 CITYWIDE CHIP SEAL AND CRACK SEAL

**BID SCHEDULE:
11:00 a.m., Local Time
January 21, 2021**

Bids will be received and accepted via the online electronic bid service, www.QuestCDN.com. Bids must be submitted via QuestCDN no later than **January 21, 2021 at 11:00 a.m.** To access the electronic bid form, download the required documents from QuestCDN and click the online bidding button at the top of the advertisement. Prospective bidders must be on the plan holders list at QuestCDN for bids to be accepted. Bidders will be charged a fee of \$30.00 to submit a bid electronically. All properly uploaded bids will then be opened, witnessed and read aloud.

GENERAL STATEMENT OF WORK:

Cape Seal and Crack Seal in various locations throughout the City and County of Denver. Approximately 95 lane miles of mostly local streets to be treated with chip/cape seal resurfacing. Crack Seal ahead of cape seal as well as other selected streets.

ESTIMATED CONSTRUCTION COST:

The estimated cost of construction for this project is between \$4,000,000.00 and \$4,400,000.00.

DOCUMENTS AND BID INFORMATION AVAILABLE:

Contract Documents complete with Technical Specifications and, if applicable, construction drawings will be available on the first day of publication at: www.work4denver.com. To download digital Contract Documents at a cost of \$15 per download, reference eBid Document Number #7450515. Contact QuestCDN at 952-233-1632 or info@questcdn.com for assistance.

PRE-BID MEETING:

A **virtual pre-bid meeting** will be held for this Project at 1:00 p.m., local time, on December 29, 2020. The teleconference call-in number and conference ID can be found on the project page at www.work4denver.com.

DEADLINE TO SUBMIT QUESTIONS: January 7, 2021 by 10:00 a.m. local time.

PREQUALIFICATION REQUIREMENTS:

Each bidder must be prequalified in category **1F(4) ASPHALT PAVEMENT REHABILITATION** at or above the **\$6,000,000.00** monetary level in accordance with the City's Rules and Regulations Governing Prequalification of Contractors. Each bidder must have submitted a prequalification application a minimum of ten (10) calendar days prior to the response due date. Applications must be submitted via email to pw.prequal@denvergov.org. To view the Rules and Regulations and to obtain a prequalification application, please visit our website at www.denvergov.org/prequalification.

MINORITY AND WOMEN-OWNED BUSINESS ENTERPRISE PARTICIPATION:

Article III, Division 3 of Chapter 28 of the D.R.M.C. states the Director of the Division of Small Business Opportunity has the authority to establish a project goal for expenditure contracted by the City and County of Denver. The specific goal for this project is:

9% Minority and Women-Owned Business Enterprise (MWBE) Participation

Project goals must be met with certified participants as set forth in Section 28-62, D.R.M.C. or through the demonstration of a sufficient good faith effort under Section 28-60 D.R.M.C.

MISCELLANEOUS:

Contracts for construction, reconstruction, and remodeling are subject to the City prevailing wage rate requirements established pursuant to Section 20-76, D.R.M.C.

City contracts are subject to payment of City Minimum Wage established pursuant to Section 20-82 through 20-84 D.R.M.C.

As its best interest may appear, the City and County of Denver reserves the right to reject any or all bids and to waive informalities in bids.

A modified version of this Notice of Invitation for Bids and the project's Statement of Quantities is available on the City and County of Denver's website at: www.work4denver.com.

Publication Dates: December 16, 17, 18, 2020

Published In: The Daily Journal

CITY AND COUNTY OF DENVER INSTRUCTIONS TO BIDDERS

IB-1 INSTRUCTION TO BIDDERS

These Instructions to Bidders are a part of the Contract Documents and are intended to serve as a guide to bidders. They are general in nature and may be amended or supplemented as needed to support any one specific invitation to bid. Each bidder shall prepare its bid in strict compliance with all requirements of the Contract Documents and by careful application of these instructions.

IB-2 BIDDING

The copy of the Contract Documents contains the Bid Form and Submittal Package for this Project, which must be used to submit a bid hereunder. The bidder must fully complete, execute and submit this Bid Form and Submittal Package, along with any other specified components of the Contract Documents, via QuestCDN's electronic bidding platform as its bid for the referenced Project.

A bidder is not required to submit as part of its bid the entire set of Contract Documents distributed by the City pursuant to the Notice of Invitation for Bids, if the bidder executes and submits the Bidder Acknowledgment Form included with the Bid Form and Submittal Package as part of its bid. However, each bidder, by submitting its bid, shall be conclusively presumed to have received and reviewed all of the information contained in the Contract Documents as this term is further defined herein.

Bid guarantee will be accepted electronically as part of the Bid packet submitted via QuestCDN. The bid guarantee must be received by the City within seven calendar days following the bid opening date to:

Department of Transportation and Infrastructure
Attention: Contract Administration
201 W. Colfax Ave. Dept. 614
Denver, CO 80202

IB-3 CONTRACT DOCUMENTS AS PUBLISHED BY CITY

Each bidder shall be responsible for, and shall be deemed to have received, all the information contained in the Contract Documents as distributed by the City pursuant to the Notice of Invitation for Bids, including addenda, whether or not such bidder has reviewed all or part of the Contract Documents in either its hard copy form or in any other format. If organizations or companies other than the City or its design professional distribute the City's Contract Documents for review by prospective bidders, whether in hard copy or via electronic or other media, neither the City nor its design professional shall be responsible for the content, completeness or accuracy of any information distributed or transmitted by any such organization or company.

IB-4 COMPLETING AND SIGNING THE BID FORMS

The bidder must complete the Bid Form by legibly writing or printing in ink, in words and figures as required, all the bidder's prices offered for the Work to be performed. All blank spaces, which require a response of the bidder, must be properly completed in full. If in the process of evaluating a bid, words and figures, as written on the Bid Form by the bidder, do not agree, the written words will govern.

For Bid Forms requiring unit price bids, the bidder shall write in the Bid Worksheet spaces provided a unit price for each item for which a quantity is given and shall also write the product of each unit price and the quantity specified in the "Amount" or "Total" space provided.

Each bidder must sign the Bid Form and give the bidder's current business address. If an individual, the signature must be of the individual offering the bid; if a partnership, the signature must be that of a general

partner; and if a corporation, both the president and the secretary must sign and the seal of the corporation must be affixed. Signatures of other persons may be acceptable if the bid contains sufficient evidence, satisfactory to the City in its sole discretion, to indicate that the other persons are authorized to bind the bidder.

IB-5 UNACCEPTABLE BIDS

The City will not accept bids from Bidders not prequalified with the City (if prequalification is required for this project), in arrears to the City upon debt or contract, or which are defaulters (as surety or otherwise) upon any obligation to the City.

IB-6 INFORMAL AND UNBALANCED BIDS

Any alteration, interlineations, erasure, omission, deletion or addition by the bidder to the Bid Form and Submittal Package or other parts of the Contract Documents submitted with the Bid Form and Submittal Package, as originally issued to the bidder, shall render the accompanying bid informal and may constitute cause for rejection.

Any unauthorized addition, conditional or alternate bids, failure to provide a unit price, lump sum amount or authorized alternate item specified or other irregularities of any kind which tend to render the bid incomplete, indefinite or ambiguous shall render the bid informal and may constitute cause for rejection.

Bids that are unbalanced so that each item does not reasonably carry its own proportion of cost or that contain inadequate or unreasonable prices for any item may be rejected. Bids, which have not acknowledged all addenda to the Contract Documents issued for this bid, may also be rejected.

The right is reserved by the City to reject any or all bids and to waive any informalities where it is deemed by the City to be in the best interests of the City to do so.

IB-7 ONLY ONE BID ACCEPTED

The City will accept only one bid for the same work from any one bidder. This includes bids that may be submitted under different names by one business enterprise.

IB-8 BID GUARANTEE

As a guarantee of good faith on the part of the bidder, each bid must be accompanied by a bid guarantee, consisting of either a certified or cashier's check made payable without condition to the order of the City and County of Denver or a bid bond written by an approved corporate surety in favor of the City and County of Denver. If the bid of a bidder is acceptable and the bidder is notified by the Manager that it is considered to be the Apparent Low Bidder and said bidder fails to execute a contract in the form prescribed or to furnish a performance and payment bond with a legally responsible and approved surety or to furnish the required evidence of insurance or satisfy all conditions precedent to contract execution within five (5) days after such notice is made by the City, said bid guarantee shall be forfeited to the City as liquidated damages and not as a penalty.

The bid guarantee shall be in the amount of five percent (5%) of the total bid unless otherwise specified in the Notice of Invitation for Bids and on the form appearing in the Contract Documents in the Bid Form and Submittal Package. Failure to submit a properly executed bid guarantee, on the form provided herein may, in the City's sole discretion, constitute cause for rejection.

Following award and execution of the Contract by the Apparent Low Bidder, or earlier in the sole discretion of the City, bid guarantees of all but the Apparent Low Bidder will be returned. When the Apparent Low Bidder executes the Contract and delivers to the City satisfactory performance and payment bonds, required insurance documentation, and has satisfied all conditions precedent to contract execution by the City, and

after approval, if any, by the Council of the City of the proposed Contract with the Apparent Low Bidder, the bid guarantee of the Apparent Low Bidder shall be returned. Such return shall be made within one hundred twenty (120) days from date bids are opened unless otherwise specified in the Special Contract Conditions.

IB-9 SITE INSPECTION AND INVESTIGATIONS

Prior to submitting a bid, the bidder is invited to inspect the work site and its surroundings. Although the bidder is not required to make such an inspection before bidding, for purposes of the Contract it shall be conclusively presumed that by failing to make such an inspection, the bidder has waived the right to later claim additional compensation or time extensions for conditions which would have been evident had the site been inspected.

Drawings and Technical Specifications, defining the Work to be done, were prepared on the basis of interpretation by the design professionals of information derived from investigations of the work site. Such information and data are subject to sampling errors, and the interpretation of the information and data depends to a degree on the judgment of the design professional. In view of this, the bidder is invited to make such additional investigations as the bidder's judgment dictates the need for such investigations. Information about the degree of difficulty of the Work to be done cannot totally be derived from either the Drawings or Technical Specifications or from the Manager or his representatives.

Since the bid information cannot be guaranteed, the Contractor shall have assumed the risks attendant to successful performance of the Work and shall never make claim for additional compensation or time extensions on the grounds that the nature or amount of work to be done was not understood by the bidder at the time of the bidding.

IB-10 INCONSISTENCIES

Any seeming inconsistencies or ambiguities between different provisions of the Contract Documents or any point which the bidder believes requires a decision or interpretation by the City must be inquired into by the bidder by addressing a formal written communication to the Manager of the Department of Transportation and Infrastructure and sending or delivering it to the office advertising this Project for bid at least forty-eight (48) hours, excluding Saturdays, Sundays, and holidays, before the time set for the opening of bids.

Information about the decision or interpretation made in response to any inquiry will be posted on www.work4denver.com. If the matter raised requires, in the sole discretion of the Manager, that an addendum to the bid documents be issued, such addendum will be published, and each bidder shall be required to acknowledge the addendum by signing and identifying it in the Bid Form when submitting the bid.

After bids are opened, all bidders must abide by the formal response of the Manager, as to any interpretation. The City shall not be bound, and the bidder shall not rely on any oral communication, interpretation clarification or determination of the Contract Documents prior to bid opening.

IB-11 WITHDRAWAL OF BID

A bidder may withdraw its bid at any time prior to the time for receipt of bids set forth in the Notice of Invitation for Bids by making written request upon the Manager of the Department of Transportation and Infrastructure. After such time, no bid may be withdrawn or modified.

Such request must be signed by the persons authorized to bind the bidder as defined in IB-4, COMPLETING AND SIGNING THE BID FORMS.

IB-12 WEBSITE

It shall be conclusively presumed that the bidder has, before submitting any bid, read and shall take full responsibility for all addenda, posted decisions, and other information relevant to the bid posted by the City on the www.QuestCDN.com website.

IB-13 PRE-BID MEETING

Bidders are urged to attend the pre-bid meeting(s) scheduled for this Project. Attendance is not mandatory; however, bidders will be held responsible for all information presented at such meeting(s).

IB-14 ADDENDA

As its best interests may require, the City may issue addenda to the Contract Documents. Such addenda shall be made available to all persons having purchased a set of Contract Documents as set forth in the Notice of Invitation for Bids contained herein. All bidders must acknowledge receipt of all addenda on the Bid Form at the time of submission of the bid.

IB-15 VIRTUAL BID OPENING

Unless otherwise suspended, delayed or canceled by posted notice from the Manager, bid opening will occur via teleconference at the time designated in the Notice of Invitation for Bid.

IB-16 EVALUATION OF BIDS AND BASIS OF BID SELECTION

Bids will be evaluated after being read out loud on the date and at the time designated in the legal advertisement. All bids will be reviewed for responsiveness to the requirements of the Contract Documents and whether or not the bids contain irregularities which could give any bidder an unfair advantage.

The Base Bid Total shall include the Textura Fee and any applicable allowances and/or force accounts. Alternates, if any are included in the bid, will be selected in the priority shown on the Bid Form, subject to the limits of available funds. Selection will be made on the basis of the lowest, total, responsive, qualified base bid plus the total of any alternates set forth on the Bid Form and selected by the City during evaluation. Bid selection will be subject to all requirements and special bidder qualifications contained herein and subject to approval of such resulting Contract in accordance with the Charter and Revised Municipal Code of the City and County of Denver. In addition to all other specified requirements, the City will correct arithmetical errors in all bids and corrected totals only will be considered as the basis of selection.

Upon concluding that the bid is, in fact, the lowest, total, responsive bid to the bidding conditions and that of a responsible, qualified bidder, the City will notify the Apparent Low Bidder.

As its best interests may appear, the City and County of Denver reserves the right to waive informalities in bids, to reject any and all bids and to rebid the Project.

IB-17 NOTICE TO APPARENT LOW BIDDER

The Notice to Apparent Low Bidder, a form of which is included in the Contract Special Conditions Section of the Contract Documents, is issued by the City directly to the selected bidder and informs the bidder that the Manager intends to seek approval of the execution of the Contract by the City in accordance with the Charter and Revised Municipal Code of the City and County of Denver. Specifically, it informs the bidder of its obligations with respect to execution of the Contract and instructs the bidder on how to proceed toward execution of the Contract. The City reserves the right to notify the Apparent Low Bidder, at any time within one hundred twenty (120) days from the date of the opening of the bids, that approval to contract with the Apparent Low Bidder shall be sought in accordance with the Charter and Revised Municipal Code of the City and County of Denver.

In accordance with the terms and conditions contained in the Bid Form and Submittal Package and any additional requirements set forth in the Notice to Apparent Low Bidder or elsewhere in the Contract Documents, the Apparent Low Bidder shall execute the Contract Form contained in the Contract Documents made available by the City for execution in the appropriate number of counterparts. The Apparent Low Bidder shall return the fully executed Contract Document sets, along with any supplemental documents required herein, to the City and shall comply with all other conditions, precedent to Contract execution within five (5) days of the date of issuance of the Notice to Apparent Low Bidder by the City. Failure to comply with each of these requirements within five (5) days of the date of issuance of the Notice to Apparent Low Bidder by the City shall render the bid nonresponsive and may constitute cause for rejection.

Issuance of such Notice shall not, however, constitute a commitment on the part of the City or create any rights in the Apparent Low Bidder to any contract with the City.

IB-18 EXECUTION OF CONTRACT

The process of executing a contract requires action by both the apparent low bidder and the City. After it notifies the Apparent Low Bidder, the City will prepare the Contract Documents by incorporating all of the documents submitted by the Apparent Low Bidder into one or more executable copies. Upon notification that contracts documents are ready for execution the Apparent Low Bidder shall execute the contract documents. At this time, the successful bidder shall also provide certain supplemental documents for incorporation into the Contract Documents. These supplemental documents shall include: the properly executed Certificate of Insurance Forms evidencing the apparent low bidder's satisfactory compliance with the insurance requirements set forth in the Contract Documents; a properly executed Payment and Performance Bond Form and appropriate Power of Attorney evidencing the Apparent Low Bidder's satisfactory compliance with the bonding requirements set forth in the Contract Documents; and documentation of compliance with any other conditions precedent to execution of the Contract by the City set forth in the Contract Documents. The insurance and bond forms contained in the Contract Special Conditions Section of the Contract Documents must be used in satisfying these supplemental document requirements.

These documents are then delivered to the City within the prescribed time period for examination of the documents to determine whether or not the Contractor has correctly executed the Contract and has correctly provided the required supplemental documents and that these documents are satisfactorily and properly completed. From here, all of the documents are forwarded to the City Attorney who will, if the insurance and bonding offered is acceptable and if all other elements of the Contract Documents are in order, recommend that the Manager and the Mayor approve the documents and, when required by the City Charter, prepare an ordinance for submittal to City Council authorizing the execution of the Contract. The City Attorney shall in all applicable instances submit the proposed contract and ordinance to City Council. After City Council approval, the Contract shall be reviewed by the City Attorney and routed for execution by the Mayor, the Clerk for attestation and the Auditor for countersignature and registration. When the total process of contract execution is complete, a Notice to Proceed will be issued and a single executed copy of the Contract will be delivered to the Contractor. Any work performed or a material purchased prior to the issuance of Notice to Proceed is at the Contractor's risk.

IB-19 BONDING REQUIREMENTS

In accordance with the provisions of General Contract Conditions, Title 15, PERFORMANCE AND PAYMENT BONDS, the minimum bonding requirements for this Contract are set forth in the form **CITY AND COUNTY OF DENVER PERFORMANCE AND PAYMENT BOND** contained in the Special Conditions Section of the Contract Documents. Upon receipt of Notice to Apparent Low Bidder, the apparent low bidder must cause this form bond to be purchased, executed and furnished, along with

appropriate Powers of Attorney and a surety authorization letter (in form similar to the one attached), to the City in accordance with the instructions contained herein.

IB-20 INSURANCE REQUIREMENTS

The minimum insurance requirements for this Contract are set forth in the Special Conditions Section of the Contract Documents. Bidders are urged to consider, in preparing a bid hereunder, that each condition, requirement or specification set forth in the form certificate must be complied with by the Contractor and all subcontractors performing Work on the Project, unless such requirements are specifically accepted in writing by the City's Risk Management Office. The Contractor must either include all subcontractors performing work hereunder as insureds under each required policy or furnish a separate certificate for each subcontractor. In either case, the Contractor shall insure that each subcontractor complies with all of the coverage requirements.

IB-21 PERMITS AND LICENSES

All permits, licenses and approvals required in the prosecution of the work shall be obtained and paid for by the Contractor.

IB-22 PREVAILING WAGE REQUIREMENTS

Contractor shall comply with, and agrees to be bound by, all requirements, conditions and City determinations regarding the Payment of Prevailing Wages Ordinance, Sections 20-76 through 20-79, D.R.M.C. including, but not limited to, the requirement that every covered worker working on a City owned or leased building or on City-owned land shall be paid no less than the prevailing wages and fringe benefits **in effect on the date the bid** or request for proposal was advertised. In the event a request for bids, or a request for proposal, was not advertised, Contractor shall pay every covered worker no less than the prevailing wages and fringe benefits in effect on the date funds for the contract were encumbered.

Date bid or proposal issuance was advertised **December 16, 2020**.

Prevailing wage and fringe rates will adjust on the yearly anniversary of the actual date of bid or proposal issuance, if applicable, or the date of the written encumbrance if no bid/proposal issuance date is applicable. Unless expressly provided for in this Agreement, Contractor will receive no additional compensation for increases in prevailing wages or fringe benefits.

Contractor shall provide the Auditor with a list of all subcontractors providing any services under the contract.

Contractor shall provide the Auditor with electronically-certified payroll records for all covered workers employed under the contract.

Contractor shall prominently post at the work site the current prevailing wage and fringe benefit rates. The posting must inform workers that any complaints regarding the payment of prevailing wages or fringe benefits may be submitted to the Denver Auditor by calling 720-913-5000 or emailing auditor@denvergov.org.

If Contractor fails to pay workers as required by the Prevailing Wage Ordinance, Contractor will not be paid until documentation of payment satisfactory to the Auditor has been provided. The City may, by written notice, suspend or terminate work if Contractor fails to pay required wages and fringe benefits.

IB-23 PAYMENT OF CITY MINIMUM WAGE

Contractor shall comply with, and agrees to be bound by, all requirements, conditions, and City determinations regarding the City’s Minimum Wage Ordinance, Sections 20-82 through 20-84 D.R.M.C, including, but not limited to, the requirement that every covered worker shall be paid no less than the City Minimum Wage in accordance with the foregoing D.R.M.C. Sections.

Instances in which a worker is covered by both Prevailing Wage rate requirements and City Minimum Wage rate requirements, Contractor shall pay every covered worker the greater of the two.

The services being requested in this solicitation may involve services that are covered pursuant to Division 3.75 of Article IV of Chapter 20 of the Denver Revised Municipal Code (“D.R.M.C.”), which is designed to address the issue of wage equity and cost of living affordability in the City & County of Denver. Contractor agrees that any contract with the City shall include a requirement that Contractor will comply with the provisions of D.R.M.C. §§20-82 through 20-84, including, but not limited to, paying all covered workers no less than the City Minimum Wage for all covered services rendered in connection with the Contract. Additionally, Contractor agrees that the contract shall require compliance with all current and future federal and state laws and City ordinances.

IB-24 TAX REQUIREMENTS

General. Bidders are referred to the General Contract Condition 323, TAXES, as to taxes to which they may be subject in performing the Work under this Contract, including but not limited to sales and use taxes and the Denver Occupational Privilege Tax. The following instructions are to be considered along with the General Contract Conditions and not in lieu of them.

Sales and Use Tax. The City of Denver imposes consumer use tax on all construction and building materials used on any construction project located in Denver. Denver does not exempt governmental or charitable projects.

It is the responsibility of the Contractor and its subcontractors to apply to the Colorado Department of Revenue (“CDOR”) for a certificate, or certificates, of exemption indicating that their purchase of construction or building materials is for a public project, and to deliver to the City copies of such applications as soon as possible after approval by the CDOR. Bidders shall include Denver sales/use tax, Occupational Privilege taxes, and shall not include in their bid amounts the exempt state, RTD, and Cultural Facilities District Sales and Use Taxes.

Denver Occupational Privilege Tax. Any employee working for a contractor, or a subcontractor, who earns \$500 or more working in Denver during a calendar month, is subject to the payment of the Employee Occupational Privilege Tax. The Contractor and any subcontractor must pay the Business Occupational Privilege Tax for each of its employees who are subject to such tax.

IB-25 DIVERSITY AND INCLUSIVENESS IN CITY SOLICITATIONS

Each bidder shall, as a condition of responsiveness to this solicitation, complete and return the “Diversity and Inclusiveness in City Solicitations Information Request Form” with their Bid.

Using the “Diversity and Inclusiveness in City Solicitations Information Request Form” provided, please state whether you have a diversity and inclusiveness program for employment and retention, procurement and supply chain activities, or customer service and provide the additional information requested on the form. The information provided on the “Diversity and Inclusiveness in City Solicitations Information Request Form” will provide an opportunity for City contractors to describe their own diversity and inclusiveness practices. Contractors are not expected to conduct intrusive examinations of its employees,

managers, or business partners in order to describe diversity and inclusiveness measures. Rather, the City simply seeks a description of the contractor's current practices, if any.

Diversity and Inclusiveness information provided by City contractors in response to City solicitations for services or goods will be collated, analyzed, and made available in reports consistent with City Executive Order No. 101. However, no personally identifiable provided by or obtained from contractor's will be in such reports.

IB-26 MINORITY AND WOMEN-OWNED BUSINESS ENTERPRISE (MWBE) REQUIREMENTS

Article III, Divisions 1 and 3 of Chapter 28, Denver Revised Municipal Code (D.R.M.C.), referred to in these Bid Documents as the "MWBE Ordinance" and any Rules or Regulations promulgated pursuant thereto apply to this Project and are incorporated into these Bid Documents by reference. Under the MWBE Ordinance, the Director of DSBO ("Director") has the authority to establish participation goals on contracts for construction, reconstruction, remodeling, professional and design work with the City and County of Denver. The participation goal is stated in the Notice of Invitation for Bids found herein. In order to comply with the bid requirements of the MWBE Ordinance, or any additional requirements, a bidder shall either meet the established participation goal or, in the alternative, demonstrate that the bidder has demonstrated sufficient good faith efforts to meet the goal in accordance with the MWBE Ordinance. A bidder's failure to comply with the MWBE Ordinance, any Rules or Regulations promulgated pursuant thereto, or any additional requirement contained herein shall render the bid non-responsive and shall constitute cause for rejection. Failure by the contractor awarded the contract to comply with MWBE Ordinance requirements during the performance of the contract is a material breach of the contract, which may result in the imposition of sanctions on the Contractor, as deemed appropriate by DSBO. Copies of the MWBE Ordinance and its accompanying Rules and Regulations are available for the use and review of bidders from DSBO. As well as additional MWBE Guidance which can be found here: <https://www.denvergov.org/dsbo>.

Meeting Established Goal

1. All MWBEs listed for participation toward meeting the goal must be properly certified by the City on or before the date bids are opened. The MWBE(s) must be certified in the NAICS code(s) that coincide with the scope of work the identified firm will be performing to count towards the participation goal. DSBO maintains an MWBE Directory ("Directory"), which is a current list of MWBEs certified by the City. A copy of the Directory is located at the DSBO web site at <https://www.denvergov.org/dsbo>. Bidders are encouraged to use the Directory to assist in identifying MWBEs for the work and supplies required for the Project. Bidders are reminded that changes may be made to the Directory at any time in accordance with the City's MWBE Ordinance. Procedures established to administer this program and a current copy of the Directory must always be used in preparing a bid. MWBE certification or listing in the Directory is not a representation or warranty by the City regarding the qualifications of any listed MWBE.
2. If a bidder is participating in a joint venture with a certified MWBE firm, bidders must submit the Joint Venture Agreement to the DSBO **at least ten (10) business days prior to the bid opening**. The Joint Venture must be approved prior to the bid opening by the DSBO. Approval by the DSBO includes determining the amount the Joint Venture will count towards the participation goal.
3. Each bidder shall submit Bid Form pages entitled Commitment to MWBE Participation, 1A- List of Proposed Subcontractors, Subconsultants, and/or Suppliers, and Letter(s) of Intent for all tiers with the bid at the time of bid opening. DSBO will evaluate each bid to determine responsiveness of the bid with regard to MWBE Ordinance requirements. **An MWBE Prime Bidder must submit a Letter of Intent for itself for self-performed work.** The MWBE Letter of Intent evidences the Bidder's

understanding that the Bidder has or will enter into a contractual relationship with the MWBE or that the Bidder's subcontractor(s), subconsultant(s), and/or supplier(s) will do so. Bidders are urged to carefully review these Letters of Intent before submission to the City to ensure the documents are properly completed and executed by the appropriate parties. **Only the MWBEs identified and the precise levels of participation listed for each, at the time of bid opening, will be considered in determining whether the bidder has met the designated participation goal. Additional, participation submitted after bid opening will not be considered in determining responsiveness.**

- a. In determining whether a bidder's committed level of participation meets the stated MWBE goal, DSBO shall base its calculation of applicable dollar amounts and percentages on the total base bid amount. If a bid contains alternates, participation contained in any alternate will not count towards satisfaction of the Participation goal at time of bid opening. However, should any designated alternate be selected by the City for inclusion in the contract ultimately awarded, the MWBE goal percentage level submitted at time of bid opening, on the base bid, will also apply to the selected alternates and must be maintained through the remaining term of the contract on the total contract amount, including any alternate work. Therefore, bidders are urged to consider participation in preparing bids for designated alternates.
- b. In utilizing the MWBE participation of a Supplier the following will count towards satisfaction of the goal:
 - i. If the materials or supplies are obtained from a MWBE manufacturer, count one hundred percent (100%) of the cost of the materials or supplies toward the participation goal.
 - ii. Only sixty percent (60%) of the value of the commercially useful function performed by MWBE Regular Dealers shall count toward satisfaction of the participation goal.
 - iii. Only the bona fide commissions earned by such Manufacturer Representatives or Brokers for its performance of a commercially useful function will count toward meeting the participation goals. The bidder must separate the bona fide brokerage commissions from the actual cost of the supplies or materials provided to determine the actual dollar amount of participation that can be counted towards meeting the goal.
- c. Any agreement between a bidder and an MWBE in which the bidder requires that the MWBE not provide subcontracting quotations to other bidders is prohibited and shall render a bidder's bid nonresponsive. D.R.M.C. 28-68(f)

Good Faith Effort

If the bidder has not fully met the participation goal as provided in D.R.M.C. Section 28-62, then it shall demonstrate that it has made good faith efforts to meet such goal. The bidder shall furnish to the Director, with the bid at time of bid opening by the City a detailed statement of its good faith efforts to meet the participation goal established by the Director. The statement of good faith efforts shall include a specific response to address each of the categories, as outlined in the MWBE Ordinance, D.R.M.C. Section 28-62, and any additional criteria that the Director may establish by rule or regulation consistent with the purposes of the MWBE Ordinance. A bidder may include any additional information it believes may be relevant. Good faith efforts must be demonstrated to be substantive and not merely for formalistic compliance with the MWBE Ordinance. The scope and adequacy of the efforts will be considered in determining whether

the bidder has achieved a good faith effort. Failure of a bidder to show good faith efforts shall render its overall good faith effort showing insufficient and its bid nonresponsive.

IB-27 DISCLOSURE OF INFORMATION

All submissions and other materials provided or produced pursuant to this Invitation for Bids may be subject to the Colorado Open Records Law, C.R.S. 24-72-201, et seq. As such, bidders are urged to review these disclosure requirements and any exceptions to disclosure of information furnished by another party and, prior to submission of a bid to the City, appropriately identify materials that are not subject to disclosure. In the event of a request to the City for disclosure of such information, the City shall advise the bidder of such request to give the bidder an opportunity to object to the disclosure of designated confidential materials furnished to the City. In the event of the filing of a lawsuit to compel such disclosure, the City will tender all such material to the court for judicial determination of the issue of disclosure and each bidder agrees to intervene in such lawsuit to protect and assert its claims of privilege against disclosure of such material. Each bidder further agrees to defend, indemnify and save and hold harmless the City, its officers, agents and employees, from any claim, damages, expense, loss or costs arising out of the bidder's intervention to protect and assert its claims of privilege against disclosure under the Open Records Law including, but not limited to, prompt reimbursement to the City of all reasonable attorney fees, costs and damages that the City may incur directly or may be ordered to pay by such court.

IB-28 GENERAL BIDDING INFORMATION

Bidders are instructed to contact the Contract Administrator designated below for this Project for pre-bid, post-bid and general City bidding information. Bidders can also visit www.work4denver.com for information, both general and project specific. The Contract Administrator assigned to this project is **Katie Ragland** who can be reached via email at pw.procurement@denvergov.org.

[REMAINDER OF PAGE INTENTIONALLY LEFT BLANK]

IB-29 PAYMENT PROCEDURE REQUIREMENTS

Textura® Construction Payment Management System (“Textura”)

Bidder recognizes and agrees that it shall be required to use the Textura® Construction Payment Management System (“Textura”) for this Project to request payment from the City and to pay all first tier subcontractors and suppliers and further record payment to all certified subcontractors or suppliers that are listed for participation towards any assigned program goal. All fees associated with Textura are to be paid by the bidder for billings for work performed. Bidders are required, when preparing a bid, to enter the price of Textura on the line provided for the service on the Bid Worksheet. The fee is all inclusive of all subcontractor, project and subscription fees associated with Textura. The bidder will calculate the fee based on their Base Bid Total (including Force Accounts and Allowances but not including any alternates, if applicable) and the table below, and then include it on the line item provided in the bid form labeled “Textura® Fee”. This expense becomes part of the contract and billable to the City. All costs including, but not limited to, costs associated with training, entering data, and/or utilizing Textura other than the Textura Construction Payment Management System Fee are overhead and shall not be reimbursed by the City. Bidder will be responsible for any tax on the Textura fee. As with other taxes, the City will not reimburse bidder for this cost and therefore this cost should be included in bidder’s bid. Textura will invoice the awarded bidder directly.

| Project Value | Project Fee (GC + Sub Usage) |
|--------------------------------|---------------------------------|
| \$100,000 – 249,999.99 | \$780 |
| \$250,000 - \$499,999.99 | \$1,625 |
| \$500,000 - \$999,999.99 | \$3,250 |
| \$1,000,000 - \$2,999,999.99 | \$5,850 |
| \$3,000,000 - \$4,999,999.99 | \$9,100 |
| \$5,000,000 - \$9,999,999.99 | \$12,220 |
| \$10,000,000 - \$19,999,999.99 | \$20,345 |
| \$20,000,000 - \$49,999,999.99 | \$32,500 |

[REMAINDER OF PAGE INTENTIONALLY LEFT BLANK]

**RULES AND REGULATIONS
REGARDING
EQUAL EMPLOYMENT OPPORTUNITY**

Promulgated and adopted by the Manager of Public Works pursuant to and by authority of Article III, Division 2, Chapter 28 of the Revised Municipal Code of the City and County of Denver, and for the purpose of insuring that contractors, subcontractors and suppliers soliciting and receiving compensation for contract work from or through the City and County of Denver provide equal opportunity in employment without regard to race, color, creed, sex, national origin, age, religion, marital status, political opinion or affiliation or mental or physical handicap and meet certain requirements for the hiring, training, promotion and treatment during employment of members of ethnic groups subjected to differential treatment, including persons of African descent (Black), Spanish-surnamed (Hispanic), Asian-American and American Indian groups.

**RULE I
DEFINITIONS**

- A. "City" means the City and County of Denver.
- B. "Manager" shall mean the Manager of Public Works for the City and County of Denver.
- C. "Contract" means a contract entered into with the City and County of Denver, financed in whole or in part by local resources or funds of the City and County of Denver, for the construction of any public building or prosecution or completion of any public work.
- D. "Contractor" means the original party to a contract with the City and County of Denver, also referred to as the "general" or "prime" contractor.
- E. "Director" means the Director of the Mayor's Office of Contract Compliance.
- F. "Subcontractor" means any person company, association, partnership, corporation, or other entity which assumes by subordinate agreement some or all of the obligations of the general or prime contractor.
- G. The Phrase "Bidding Specifications" as used in Article III, Division 2 of Chapter 28 of the Revised Municipal Code shall include **BID CONDITION, INVITATION TO BID AND NOTICE OF PROPOSAL.**
- H. "Affirmative Action Program" means a set of specific and result-oriented procedures or steps to which a contractor commits himself to apply every good faith effort to employ members of ethnic minority groups, to include persons of African descent (Black), Spanish surnamed (Hispanic), Asian-American, American Indians, and persons with mental or physical handicap.
- I. "Mayor's Office of Contract Compliance" means the City agency established pursuant to Article III, Division 1 of Chapter 28 of the Denver Revised Municipal Code.

Revised: 10/19/93

EEO-2

RULE II
NOTICE OF HEARING

When results of conciliation efforts are unsatisfactory to the Manager and he is informed in accordance with Article III, Division 2 of Chapter 28 of the Revised Municipal Code that a contractor or subcontractor has apparently failed to meet affirmative action and equal employment opportunity requirements after a reasonable period of notice to correct deficiencies, the Manager will, prior to imposition of any sanctions, afford the general contractor a hearing in order to determine whether the contractor or his subcontractors have failed to comply with the affirmative action and equal employment opportunity requirements of Article III, Division 2 of Chapter 28 of the Revised Municipal Code or of the contract. Written notice of such hearing shall be delivered personally or sent by certified mail return receipt requested, to the contractor and to any subcontractor involved at least ten days prior to the date scheduled for the hearing.

RULE III
HEARING

- A. Contractors will appear at hearings and may be represented by counsel, and may present testimony orally and other evidence.
- B. Hearings shall be conducted by one or more hearing examiners designated as such by the Manager.
- C. The Director of the Mayor's Office of Contract Compliance may participate in hearings as a witness.
- D. Hearings shall be held at the place specified in the notice of hearing.
- E. All oral testimony shall be given under oath or affirmation and a record of such proceedings shall be made.
- F. All hearings shall be open to the public.
- G. The hearing officer shall make recommendations to the Manager who shall make a final decision.

REGULATIONS

REGULATION NO. 1. **ORDINANCE:** The Rules and Regulations of the Manager shall be inserted in the bidding specifications for every contract for which bidding is required.

REGULATION NO. 2. **EXEMPTIONS:** Each contract and subcontract, regardless of dollar amount, shall be subject to affirmative action requirements unless specifically exempted in writing individually by the Manager. Exemptions apply only to "affirmative action" in equal employment opportunity, and are not to be construed as condonation in any manner of "discrimination" or "discriminatory practices" in employment because of race, color, creed, sex, age, national origin, religion, marital status, political opinion or mental or physical handicap.

Revised: 10/19/93

EEO-3

REGULATION NO. 3. DIRECTOR OF CONTRACT COMPLIANCE: The Director of the Mayor's Office of Contract Compliance shall perform the duties assigned to such official by Article III, Division 2 of Chapter 28 of the Revised Municipal Code and by the Manager. (1) The Director of the Mayor's Office of Contract Compliance or designated representatives shall inform bidders and contractors of affirmative action procedures, programs, and goals in accordance with the ordinance at pre-bid and pre-construction conference; (2) make regular on-site inspections; (3) supply contractors and subcontractors with report forms to be completed by them when requested, and furnished to the Director of the Mayor's Office of Contract Compliance; and (4) review payroll records, employment records and practices of general contractors and their subcontractors and suppliers during the performance of any contract. The Director of the Mayor's Office of Contract Compliance shall promptly report apparent affirmative action deficiencies to the Manager.

REGULATION NO. 4. GOALS AND TIMETABLES: In general, goals and timetables should take into account anticipated vacancies and the availability of skills in the market place from which employees should be drawn. In addition, where discrimination in employment by a general contractor or any of his subcontractors is indicated, a corrective action program will take into account the need by the general contractor and his subcontractors to correct past discriminatory practices and reach goals of minority manpower utilization on a timely basis through such recruiting and advertising efforts as are necessary and appropriate.

REGULATION NO. 5. AWARD OF CONTRACTS: It shall be the responsibility of the Director of the Mayor's Office of Contract Compliance to determine the affirmative action capability of bidders, contractors and subcontractors and to recommend to the Manager the award of contracts to those bidders, contractors and subcontractors and suppliers who demonstrate the ability and willingness to comply with the terms of their contract.

REGULATION NO. 6. PUBLICATION AND DUPLICATION: Copies of these Rules and Regulations as amended by the Manager from time to time, shall as soon as practicable and after Notice being published will be made a part of all City Contracts.

REGULATION NO. 7. NOTICE TO PROCEED: Prior to issuance of Notice to Proceed a sign-off will be required of the Director of the Mayor's Office of Contract Compliance or his designee.

REGULATION NO. 8. CONTRACTS WITH SUBCONTRACTORS: To the greatest extent possible the contractor shall make a good faith effort to contract with minority contractors, subcontractors and suppliers for services and supplies by taking affirmative actions which include but are not limited to the following:

1. Advertise invitations for subcontractor bids in minority community news media.
2. Contact minority contractor organizations for referral of prospective subcontractors.
3. Purchase materials and supplies from minority material suppliers.

Revised: 10/19/93

EEO-4

REGULATION NO. 9. AGENCY REFERRALS: it shall be no excuse that the union with which the contractor or subcontractor has an agreement providing for referral, exclusive or otherwise, failed to refer minority employees.

REGULATION NO. 10. CLAUSES: The Manager shall include the appropriate clauses in every contract and the contractor shall cause to be inserted in every subcontract the appropriate clauses:

1. **APPENDIX A:** City and County of Denver Equal Opportunity Clause-ALL CONTRACTS funded only with City & County of Denver monies.
2. **APPENDIX B:** Equal Opportunity Clause (11246)-ALL FEDERAL ASSISTED
3. **APPENDIX C:** Section 3-Assurance of Compliance-HUD ASSISTED PROJECTS.
4. **APPENDIX D:** Section 3-Clause-HUD ASSISTED PROJECTS.

All amendments to the appendices shall be included by reference.

REGULATION NO. 11. SHOW CAUSE NOTICES: When the Manager has reasonable cause to believe that a contractor has violated Article III, Division 2 of Chapter 28 of the Revised Municipal Code, he may issue a notice requiring the contractor to show cause, within fifteen days why enforcement procedures, or other appropriate action to insure compliance, should not be instituted.

REGULATION NO. 12. **BID CONDITIONS-AFFIRMATIVE ACTION
REQUIREMENTS-
EQUAL EMPLOYMENT OPPORTUNITY:**

1. **APPENDIX E:**

The Bid Conditions-Affirmative Action Requirements-Equal Employment Opportunity as amended and published by the U.S. Department of Labor, Employment Standards Administration, Office of Federal Contract Compliance, shall be inserted verbatim for bidding specification for every non-exempt contract involving the use of Federal funds.

2. **APPENDIX F:**

The Bid Conditions-Affirmative Action Requirements-Equal Employment Opportunity as published by the Department of Public Works, City and County of Denver shall be inserted verbatim as bidding specifications for every non-exempt contract using City funds.

Revised: 04/12/91

EEO-5

APPENDIX A

CITY AND COUNTY OF DENVER EQUAL OPPORTUNITY CLAUSE-ALL CONTRACTS

1. The contractor will not discriminate against any employee or applicant for employment because of race, creed, color, sex, age, national origin, religion, marital status, political opinion or affiliation, or mental or physical handicap. The contractor will take affirmative action to ensure that applicants are employed, and that employees are treated during employment without regard to their race, creed, color, sex, age, national origin, religion, marital status, political opinion or affiliation, or mental or physical handicap. Such action shall include, but not be limited to the following: employment, upgrading, demotion, or transfer; recruitment or recruitment advertising; layoff or termination; rates of pay or other forms of compensation; and selection for training, including apprenticeship. The contractor agrees to post in conspicuous places, available to employees and applicants for employment, notices to be provided setting forth the provisions of this nondiscrimination clause.
2. The contractor will, in all solicitations or advertisements for employees placed by or on behalf of the contractor, state that all qualified applicants will receive consideration for employment without regard to race, creed, color, sex, age, national origin, religion, marital status, political opinion or affiliation, or mental or physical handicap.
3. The contractor will send to each labor union or representative of workers with which he has a collective bargaining agreement or other contract or understanding, a notice to be provided, advising the said labor union or workers' representatives of the contractor's commitments under this section, and shall post copies of the notice in conspicuous places available to employees and applicants for employment.
4. Each contractor will comply with all provisions of Article III, Division 2, Chapter 28 of the Revised Municipal Code, and the rules, regulations, and relevant orders of the Manager and Director.
5. The contractor will furnish all information and reports required by Article III, Division 2, Chapter 28 of the Revised Municipal Code, and by rules, regulations and orders of the Manager and Director or pursuant thereto, and will permit access to his books, records, and accounts by the Manager, Director or their designee for purposes of investigation to ascertain compliance with such rules, regulations, and orders.
6. In the event of the contractor's noncompliance with the nondiscrimination clauses of this contract or with any of the said rules, regulations or orders this contract may be cancelled, terminated, or suspended in whole or in part and the contractor may be declared ineligible for further City contracts in accordance with procedures authorized in Article III, Division 2, Chapter 28 of the Revised Municipal Code, or by rules, regulations, or order of the Manager.

Revised: 09/28/90

EEO-A1

7. The contractor will include Regulation 12 Paragraph 2 and the provisions of paragraphs (1) through (6) in every subcontract or purchase order unless, exempted by rules, regulations, or orders of the Manager issued pursuant to Article III, Division 2, Chapter 28 of the Revised Municipal Code, so that such provisions will be binding upon each subcontractor or suppliers. The contractor will take such action with respect to any subcontract or purchase order as the administering agency may direct as a means of enforcing such provisions, including sanctions for noncompliance.

The applicant further agrees to be bound by the above equal opportunity clauses with respect to its own employment practices when it participates in City contracts. The contractor agrees to assist and cooperate actively with the Manager and the Director in obtaining compliance of subcontractors and suppliers with the equal opportunity clause and the rules, regulations and relevant orders of the Manager, and will furnish the Manager and the Director such information as they may require for the supervision of compliance, and will otherwise assist the Manager and Director in the discharge of the City's primary responsibility for securing compliance. The contractor further agrees to refrain from entering into any contract or contract modification subject to Article III, Division 2, Chapter 28 of the Revised Municipal Code with a contractor debarred from, or who has not demonstrated eligibility for, City contracts.

The contractor will carry out such sanctions and penalties for violation of the equal opportunity clause as may be imposed upon contractors and subcontractors by the Manager and Director. In addition, the contractor agrees that failure or refusal to comply with these undertakings the Manager may take any or all of the following actions:

- (A) Cancellation, termination, or suspension in whole or in part of this contract.
- (B) Refrain from extending any further assistance to the applicant under the program with respect to which the failure occurred until satisfactory assurance of future compliance has been received from such applicant.
- (C) Refer the case to the City Attorney for appropriate legal proceedings.

SUBCONTRACTS: Each prime contractor or subcontractor shall include the equal opportunity clause in each of its subcontracts.

Revised: 10/02/90

EEO-A2

APPENDIX F
BID CONDITIONS
AFFIRMATIVE ACTION REQUIREMENTS
EQUAL EMPLOYMENT OPPORTUNITY

For all Non-Exempt Construction Contracts to be Awarded by
the City and County of Denver, Department of Public Works

NOTICE

EACH BIDDER, CONTRACTOR OR SUBCONTRACTOR (HEREINAFTER THE CONTRACTOR) MUST FULLY COMPLY WITH THE REQUIREMENTS OF THESE BID CONDITIONS AS TO EACH CONSTRUCTION TRADE IT INTENDS TO USE ON THIS CONSTRUCTION CONTRACT, AND ALL OTHER CONSTRUCTION WORK (BOTH CITY AND NON-CITY) IN THE DENVER AREA DURING THE PERFORMANCE OF THIS CONTRACT OR SUBCONTRACT. THE CONTRACTOR COMMITS ITSELF TO THE GOALS FOR MINORITY MANPOWER UTILIZATION, AS APPLICABLE, AND ALL OTHER REQUIREMENTS, TERMS AND CONDITION OF THESE BID CONDITIONS BY SUBMITTING A PROPERLY SIGNED BID.

THE CONTRACTOR SHALL APPOINT A COMPANY EXECUTIVE TO ASSUME THE RESPONSIBILITY FOR THE IMPLEMENTATION OF THE REQUIREMENTS, TERMS AND CONDITIONS OF THESE BID CONDITIONS.

MICHAEL D. MUSGRAVE
Manager of Public Works
City and County of Denver

Revised: 10/19/93

EEO-F1

A. **REQUIREMENTS --AN AFFIRMATIVE ACTION PLAN:**

Contractors shall be subject to the provisions and requirements of these bid conditions including the goals and timetables for minority' and female utilization, and specific affirmative action steps set forth by the Office of Contract Compliance. The contractor's commitment to the goals for minority, and female utilization as required constitutes a commitment that it will make every good faith effort to meet such goals.

1. **GOALS AND TIMETABLES:**

The goals and timetables for minority and female participation, expressed in percentage terms for the contractor's aggregate workforce in each trade are as follows:

| GOALS FOR MINORITY PARTICIPATION | GOALS FOR FEMALE PARTICIPATION |
|---|---------------------------------------|
| FOR EACH TRADE | FOR EACH TRADE |
| From January 1, 1982 | From January 1, 1982 |
| to 21.7% - 23.5% | to 6.9% |
| Until Further Notice | Until Further Notice |

The goals for minority and female utilization above are expressed in terms of hours of training and employment as a proportion of the total number of hours to be worked by the contractor's aggregate workforce, which includes all supervisory personnel, in each trade, on all projects for the City and County of Denver during the performance of its contract (i.e., The period beginning with the first day of work on the City and County of Denver funded construction contract and ending with the last day of work).

¹"Minority" is defined as including, Blacks, Spanish Surname Americans, Asian-Americans, and American Indians, and includes both men and Minority women.

Revised: 10/02/90

EEO-F2

The hours of minority and female employment and training must be substantially uniform throughout the length of the contract in each trade and minorities and females must be employed evenly on each of a contractor's projects. Therefore, the transfer of minority or female employees from contractor to contractor or from project to project for the purpose of meeting the contractor's goals shall be a violation of these Bid Conditions.

If the contractor counts the nonworking hours of apprentices they must be employed by the contractor during the training period; the contractor must have made a commitment to employ apprentices at the completion of their training subject to the availability of employment opportunities; and the apprentices must be trained pursuant to training programs approved by the Bureau of Apprenticeship and Training.

2. **SPECIFIC AFFIRMATIVE ACTION STEPS:**

No contractor shall be found to be in noncompliance solely on account of its failure to meet its goals, but will be given an opportunity to demonstrate that the contractor has instituted all the specific affirmative action steps specified and has made every good faith effort to make these steps work toward the attainment of its goals within the timetables, all to the purpose of expanding minority and female utilization in its aggregate workforce. A contractor, who fails to comply with its obligation under the Equal Opportunity Clause of its contract and fails to achieve its commitments to the goals for minority and female utilization has the burden of proving that it has engaged in an Affirmative Action Program directed at increasing minority and female utilization and that such efforts were at least as extensive and as specific as the following:

Revised: 11/12/82

EEO-F3

- a. The contractor should have notified minority and female organizations when employment opportunities were available and should have maintained records of the organization's response.
- b. The contractor should have maintained a file of the names and addresses of each minority and female referred to it by any individual or organization and what action was taken with respect to each such referred individual, and if the individual was not employed by the contractor, the reasons. If such individual was sent to the union hiring hall for referral and not referred back by the union or if referred, not employed by the contractor, the file should have documented this and their reasons.
- c. The contractor should have promptly notified the Department of Public Works, and Mayor's Office of Contract Compliance when the union or unions with which the contractor has collective bargaining agreements did not refer to the contractor a minority or female sent by the contractor, or when the contractor has other information that the union referral process has impeded efforts to meet its goals.
- d. The contractor should have disseminated its EEO policy within its organization by including it in any employee handbook or policy manual; by publicizing it in company newspapers and annual reports and by advertising such policy at reasonable intervals in union publications. The EEO policy should be further disseminated by conducting staff meetings to explain and discuss the policy; by posting of the policy; and by review of the policy with minority and female employees.

Revised: 10/19/93

EEO-F4

- e. The contractor should have disseminated its EEO policy externally by informing and discussing it with all recruitment sources; by advertising in news media, specifically including minority and female news media; and by notifying and discussing it with all subcontractors.
- f. The contractor should have made both specific and reasonably recurrent written and oral recruitment efforts. Such efforts should have been directed at minority and female organizations, schools with substantial minority and female enrollment, and minority and female recruitment and training organizations within the contractor's recruitment area.
- g. The contractor should have evidence available for inspection that all tests and other selection techniques used to select from among candidates for hire, transfer, promotion, training, or retention are being used in a manner that does not violate the OFCCP Testing Guidelines in 41 CFR Part 60-3.
- h. The contractor should have made sure that seniority practices and job classifications do not have a discriminatory effect.
- i. The contractor should have made certain that all facilities are not segregated by race.
- j. The contractor should have continually monitored all personnel activities to ensure that its EEO policy was being carried out including the evaluation of minority and female employees for promotional

Revised: 10/19/93

EEO-F5

opportunities on a quarterly basis and the encouragement of such employees to seek those opportunities.

k. The contractor should have solicited bids for subcontracts from available minority and female subcontractors engaged in the trades covered by these Bid conditions, including circulation of minority and female contractor associations.

NOTE: The Director and the Mayor's Office of Contract Compliance will provide technical assistance on questions pertaining to minority and female recruitment sources, minority and female community organizations, and minority and female news media upon receipt of a request for assistance from a contractor.

3. **NON-DISCRIMINATION:** In no event may a contractor utilize the goals and affirmative action steps required in such a manner as to cause or result in discrimination against any person on account of race, color, religion, sex, marital status, national origin, age, mental or physical handicap, political opinion or affiliation.

4. **COMPLIANCE AND ENFORCEMENT:** In all cases, the compliance of a contractor will be determined in accordance with its obligations under the terms of these Bid Conditions. All contractors performing or to perform work on projects subject to these Bid Conditions hereby agree to inform their subcontractors in writing of their respective obligations under the terms and requirements of these Bid Conditions, including the provisions relating to goals of minority and female employment and training.

Revised: 10/19/93

EEO-F6

A. **Contractors Subject to these Bid Conditions:**

In regard to these Bid Conditions, if the contractor meets the goals set forth therein or can demonstrate that it has made every good faith effort to meet these goals, the contractor shall be presumed to be in compliance with Article III, Division 2, Chapter 28 of the Revised Municipal Code, the implementing regulations and its obligations under these Bid Conditions. In the event, no formal sanctions or proceedings leading toward sanctions shall be instituted unless the contracting or administering agency otherwise determines that the contractor is violating the Equal Opportunity Clause.

1. Where the Office of Contract Compliance finds that a contractor failed to comply with the requirements of Article III, Division 2, Chapter 28 of the Revised Municipal Code or the implementing regulations and the obligations under these Bid Conditions, and so informs the Manager, the Manager shall take such action and impose such sanctions, which include suspension, termination, cancellation, and debarment, as may be appropriate under the Ordinance and its regulations. When the Manager proceeds with such formal action it has the burden of proving that the contractor has not met the goals contained in these Bid Conditions. The contractor's failure to meet its goals shall shift to it the requirement to come forward with evidence to show that it has met the good faith requirements of these Bid Conditions.
2. The pendency of such proceedings shall be taken into consideration by the Department of Public Works in determining whether such contractor can comply with the requirements of Article III, Division 2, Chapter 28 of the Revised Municipal Code, and is therefore a "responsible prospective contractor".

Revised: 09/26/90

EEO-F7

3. The Mayor's Office of Contract Compliance shall review the contractor's employment practices during the performance of the contract. If the Mayor's Office of Contract Compliance determines that the contractor's Affirmative Action Plan is no longer an acceptable program, the Director shall notify the Manager.

B. **Obligations Applicable to Contractors:**

It shall be no excuse that the union with which the contractor has a collective bargaining agreement providing for exclusive referral failed to refer minority or female employees. Discrimination in referral for employment, even if pursuant to provisions of a collective bargaining agreement, is prohibited by the National Labor Relations Act, as amended, Title VI of the Civil Rights Act of 1964, as amended, and Article III, Division 2, Chapter 28 of the Revised Municipal Code. It is the policy of the Department of Public Works that contractors have a responsibility to provide equal employment opportunity, if they wish to participate in City and County of Denver contracts. To the extent they have delegated the responsibility for some of their employment practices to a labor organization and, as a result, are prevented from meeting their obligations pursuant to Article III, Division 2, Chapter 28 of the Revised Municipal Code, such Contractors cannot be considered to be in compliance with Article III, Division 2, Chapter 28 of the Revised Municipal Code, or its implementing rules and regulations.

Revised: 10/19/93

EEO-F8

C. **General Requirements**

Contractors are responsible for informing their subcontractors in writing regardless of tier, as to their respective obligations. Whenever a contractor subcontracts a portion of work in any trade covered by these Bid Conditions, it shall include these Bid Conditions in such subcontracts and each subcontractor shall be bound by these Bid Conditions to the full extent as if it were the prime contractor. The contractor shall not, however, be held accountable for the failure of its subcontractors to fulfill their obligations under these Bid Conditions. However, the prime contractor shall give notice to the Director of any refusal or failure of any subcontractor to fulfill the obligations under these Bid Conditions. A subcontractor's failure to comply will be treated in the same manner as such failure by a prime contractor.

1. Contractors hereby agree to refrain from entering into any contract or contract modification subject to Article III, Division 2, Chapter 28 of the Revised Municipal Code with a contractor debarred from, or who is determined not to be a "responsive" bidder for the City and County of Denver contracts pursuant to the Ordinance.

2. The contractor shall carry out such sanctions and penalties for violation of these Bid Conditions and the Equal Opportunity Clause including suspension, termination and cancellation of existing subcontracts and debarment from future contracts as may be ordered by the Manager pursuant to Article III, Division 2, Chapter 28 of the Revised Municipal Code and its implementing regulations.

Revised: 04/12/91

EEO-F9

3. Nothing herein is intended to relieve any contractor during the term of its contract from compliance with Article III, Division 2, Chapter 28 of the Revised Municipal Code, and the Equal Opportunity Clause of its contract with respect to matters not covered in these Bid Conditions.

4. Contractors must keep such records and file such reports relating to the provisions of these Bid Conditions as shall be required by the Office of Contract Compliance.

5. Requests for exemptions from these Bid Conditions must be made in writing, with justification, to the Manager of Public Works, City and County Building, Room 379, Denver, Colorado 80202, and shall be forwarded through and with the endorsement of the Director.

Revised: 04/12/91

EEO-F10

**CITY AND COUNTY OF DENVER
CONTRACT NO. 202057115**

2021 CITYWIDE CHIP SEAL AND CRACK SEAL

CONTRACT

THIS CONTRACT AND AGREEMENT, made and entered into by and between the City and County of Denver, a municipal corporation of the State of Colorado, hereinafter referred to as the "City," party of the first part, and contractor listed below, hereinafter referred to as the "Contractor," party of the second part,

**VANCE BROTHERS, INC.
380 W 62nd Ave
Denver, CO 80216**

WITNESSETH, commencing on **December 16, 2020**, and for at least three (3) days the City advertised that sealed bids would be received for furnishing all labor, tools, supplies, equipment, materials, and everything necessary and required for the following:

| |
|---|
| <p>CONTRACT NO. 202057115</p> <p>2021 CITYWIDE CHIP SEAL AND CRACK SEAL</p> |
|---|

WHEREAS, bids pursuant to said advertisement have been received by the Manager of the Department of Transportation and Infrastructure, who has recommended that a Contract for said work be made and entered into with the above named Contractor who was the lowest, responsive, qualified bidder therefore, and

WHEREAS, said Contractor is now willing and able to perform all of said work in accordance with said advertisement and its bid.

NOW THEREFORE, in consideration of the compensation to be paid the Contractor, the mutual agreements hereinafter contained, and subject to the terms hereinafter stated, it is mutually agreed as follows:

1. CONTRACT DOCUMENTS

It is agreed by the parties hereto that the following list of documents, instruments, technical specifications, plans, drawings and other materials which are attached hereto and bound herewith, incorporated herein by reference or otherwise referenced in these documents constitute and shall be referred to either as the "Contract Documents" or the "Contract," and all of said documents, instruments, technical specifications, Plans, Drawings and other materials taken together as a whole constitute the Contract between the parties hereto, and they are as fully a part of this agreement as if they were set out verbatim and in full herein:

Advertisement of Notice of Invitation for Bids
Instructions to Bidders
Commitment to MWBE Participation
Letters(s) of Intent
IA - List of Proposed Subcontractors, Subconsultants, and/or Suppliers
Article III, Divisions 1, 2, and 3 of Chapter 28, D.R.M.C.
Bid Bond
Addenda (as applicable)
Equal Employment Opportunity Provisions (Appendix A and Appendix F)

Bid Form
Contract Form
General Contract Conditions
Special Contract Conditions
Performance and Payment Bond
Notice to Apparent Low Bidder
Notice to Proceed
Contractor's Certification of Payment Form
Final Release and Certificate of Payment
Certificate of Contract Release
Change Orders (as applicable)
Federal Requirements (as applicable)
Prevailing Wage Rate Schedule(s)
Technical Specifications
Contract Drawings
Accepted Shop Drawings

2. SCOPE OF WORK

The Contractor agrees to and shall furnish all labor, tools, supplies, equipment, materials and everything necessary for and required to do, perform and complete all of the Work described, drawn, set forth, shown and included in said Contract Documents.

3. TERMS OF PERFORMANCE

The Contractor agrees to undertake the performance of the Work under this Contract within ten (10) days after being notified to commence work by issuance of a Notice to Proceed in substantially the form contained herein from the Manager and agrees to fully complete said Work within **120 (One Hundred Twenty)** consecutive calendar days from the effective date of said Notice, plus such extension or extensions of time as may be granted in accordance with the provisions of the General Contract Conditions and any applicable Special Contract Conditions.

4. TERMS OF PAYMENT

The City agrees to pay the Contractor for the performance of all of the Work required under this Contract, and the Contractor agrees to accept as the Contractor's full and only compensation therefore, such sum or sums of money as may be proper in accordance with the price or prices set forth in the Contractor's Bid Form hereto attached and made a part hereof for **bid item numbers 408-1 through 630-2 (Twelve [12]) total bid items**, the total estimated cost thereof being **Four Million Four Hundred Thirteen Thousand Nine Hundred Sixty Dollars and No Cents (\$4,413,960.00)**. Adjustments to said Contract Amount and payment of amounts due hereunder shall be made in accordance with the provisions of the General Contract Conditions and any applicable Special Contract Conditions.

5. NO DISCRIMINATION IN EMPLOYMENT

In connection with the performance of work under this contract, the Contractor may not refuse to hire, discharge, promote or demote, or discriminate in matters of compensation against any person otherwise qualified, solely because of race, color, religion, national origin, gender, age, military status, sexual orientation, gender identity or gender expression, marital status, or physical or mental disability. The Contractor shall insert the foregoing provision in all subcontracts.

6. COMPLIANCE WITH MWBE REQUIREMENTS

This Contract is subject to all applicable provisions of Divisions 1 and 3 of Article III, of Chapter 28, Denver Revised Municipal Code (D.R.M.C.) referred to in this Contract as the "MWBE Ordinance" any corresponding Rules and Regulations, and any additional requirements contained herein. Without limiting

the general applicability of the foregoing, the Contractor/Consultant acknowledges its continuing duty, pursuant to the D.R.M.C., to maintain throughout the duration of this Contract, and compliance with the MWBE commitment of 9%, upon which the City approved the award of this Contract to the Contractor/Consultant. The Contractor/Consultant further acknowledges that failure to maintain such participation commitments or otherwise comply with the requirements of the MWBE Ordinance, any corresponding Rules and Regulations, and any additional requirements contained herein, shall subject the Contractor/Consultant to sanctions in accordance with Section 28-76 of the D.R.M.C. Nothing contained in this provision or in the MWBE Ordinance shall negate the City's right to prior approval of subcontractors, or substitutes therefore, under this Contract.

7. WAGE RATE REQUIREMENTS

In performance of all Work hereunder, the Contractor agrees to comply with and be bound by all requirements and conditions of the City's Payment of Prevailing Wages Ordinance, Sections 20-76 through 20-79, D.R.M.C. and any determinations made by the City pursuant thereto as well as the City's Minimum Wage Protections Sections 20-82 through 20-84 D.R.M.C. and any determinations made by the City pursuant thereto. In the event a covered worker falls under both ordinances, Contractor shall pay the greater of the two rates.

8. APPLICABILITY OF LAWS

The Agreement between the Contractor and the City shall be deemed to have been made in the City and County of Denver, State of Colorado and shall be subject to, governed by, and interpreted and construed by or in accordance with the laws of the State of Colorado and the Charter, Revised Municipal Code, Rules, Regulations, Executive Orders and fiscal rules of the City. As such, the Contractor shall at all times comply with the provisions of the Charter, Revised Municipal Code, Rules, Regulations, Executive Orders and fiscal rules of the City, and those State of Colorado and Federal Laws, Rules and Regulations, which in any manner limit, control or apply to the actions or operations of the Contractor, any subcontractors, employees, agents or servants of the Contractor engaged in the Work or affecting the materials and equipment used in the performance of the Work, as the same may be, from time to time, promulgated, revised or amended. The Charter and Revised Municipal Code of the City and County of Denver, as the same may be amended from time to time, are hereby expressly incorporated into this Agreement as if fully set out herein by this reference.

9. APPROPRIATION

The amount of money, which has been appropriated and encumbered for the purpose of this contract, to date, is equal to or in excess of the Contract Amount. The Manager, upon reasonable written request, will advise the Contractor in writing of the total amount of appropriated and encumbered funds, which remain available for payment for all Work under the Contract.

The issuance of any change order or other form or order or directive by the City which would cause the aggregate payable under the contract to exceed the amount appropriated for the contract is expressly prohibited. In no event shall the issuance of any change order or other form of order or directive by the City be considered valid or binding if it requires additional compensable work to be performed, which work will cause the aggregate amount available under the Contract to exceed the amount appropriated and encumbered for this Contract, unless and until such time as the Contractor has been advised in writing by the Manager that a lawful appropriation, sufficient to cover the entire cost of such additional work, has been made.

It shall be the responsibility of the Contractor to verify that the amounts already appropriated for this Contract are sufficient to cover the entire cost of such work, and any work undertaken or performed in excess of the amount appropriated is undertaken or performed in violation of the terms of this contract, without the proper authorization for such work, and at the Contractor's own risk.

10. [RESERVED]

11. ASSIGNMENT

The Contractor shall not assign any of its rights, benefits, obligations or duties under this Contract except upon the prior written consent and approval of the Manager to such assignment.

12. DISPUTES RESOLUTION PROCESS

It is the express intention of the parties to this Contract that all disputes of any nature whatsoever regarding the Contract including, but not limited to, any claims for compensation or damages arising out of breach or default under this Contract, shall be resolved by administrative hearing pursuant to the provisions of Section 56-106, D.R.M.C., or, as applicable, Section 28-69 D.R.M.C. for Minority and Women-Owned Business Enterprise disputes. The Contractor expressly agrees that this dispute resolution process is the only dispute resolution mechanism that will be recognized by the parties for any claims put forward by the Contractor, notwithstanding any other claimed theory of entitlement on the part of the Contractor or its subcontractors or suppliers.

13. CONTRACT BINDING

It is agreed that this Contract shall be binding on and inure to the benefit of the parties hereto, their heirs, executors, administrators, assigns and successors.

14. PARAGRAPH HEADINGS

The captions and headings set forth herein are for convenience of reference only and shall not be construed so as to define or limit the terms and provisions hereof.

15. SEVERABILITY

It is understood and agreed by the parties hereto that, if any part, term, or provision of this Contract, except for the provisions of this Contract requiring prior appropriation and limiting the total amount to be paid by the City, is by the courts held to be illegal or in conflict with any law of the State of Colorado, the validity of the remaining portions or provisions shall not be affected, and the rights and obligations of the parties shall be construed and enforced as if the Contract did not contain the particular part, term or provision held to be invalid.

16. ELECTRONIC SIGNATURES AND ELECTRONIC RECORDS

Contractor consents to the use of electronic signatures by the City. The Agreement, and any other documents requiring a signature hereunder, may be signed electronically by the City in the manner specified by the City. The Parties agree not to deny the legal effect or enforceability of the Agreement solely because it is in electronic form or because an electronic record was used in its formation. The Parties agree not to object to the admissibility of the Agreement in the form of an electronic record, or a paper copy of an electronic document, or a paper copy of a document bearing an electronic signature, on the ground that it is an electronic record or electronic signature or that it is not in its original form or is not an original.

[REMAINDER OF PAGE INTENTIONALLY LEFT BLANK]

Contract Control Number: DOTI-202057115-00
Contractor Name: VANCE BROTHERS, INC.

IN WITNESS WHEREOF, the parties have set their hands and affixed their seals at Denver, Colorado as of:

SEAL

CITY AND COUNTY OF DENVER:

ATTEST:

By:

APPROVED AS TO FORM:

REGISTERED AND COUNTERSIGNED:

Attorney for the City and County of Denver

By:

By:

By:

Contract Control Number:
Contractor Name:

DOTI-202057115-00
VANCE BROTHERS, INC.

By: 

Name: Michael W. Vance
(please print)

Title: Vice President
(please print)

ATTEST: [if required]

By: 

Name: Andrew W. Vance
(please print)

Title: Secretary
(please print)

**STANDARD SPECIFICATIONS FOR CONSTRUCTION
GENERAL CONTRACT CONDITIONS**

INDEX

TITLE 1

DEFINITIONS..... 1

101 CITY 1

102 CONTRACT..... 1

103 CONTRACT AMOUNT 1

104 CONTRACT DOCUMENTS 1

105 CONTRACT TIME 1

106 CONTRACTOR 2

107 CONTRACTOR PERSONNEL 2

108 DAYS 2

109 DEPUTY MANAGER 2

110 DESIGNER 2

111 FINAL COMPLETION..... 2

112 MANAGER..... 3

113 PRODUCT DATA..... 3

114 PROJECT 3

115 PROJECT MANAGER 3

116 SAMPLES 3

117 SHOP DRAWINGS..... 3

118 SUBCONTRACTOR 3

119 SUBSTANTIAL COMPLETION 3

120 SUPPLIER..... 4

121 WORK..... 4

TITLE 2

CITY ADMINISTRATIVE ORGANIZATIONS; LINE OF AUTHORITY 5

201 DEPARTMENT OF AVIATION..... 5

202 MANAGER OF AVIATION..... 5

203 DEPARTMENT OF PUBLIC WORKS 5

204 MANAGER OF PUBLIC WORKS..... 5

205 BUILDING INSPECTION..... 5

206 ZONING..... 5

207 DIVISION OF SMALL BUSINESS OPPORTUNITY..... 6

208 CITY AUDITOR 6

209 MANAGER OF FINANCE..... 6

210 CITY ATTORNEY 6

211 OFFICE OF RISK MANAGEMENT..... 6

212 CITY’S CONTRACT ADMINISTRATION LINE OF AUTHORITY 6

213 CITY’S COMMUNICATION WITH THE CONTRACTOR..... 7

TITLE 3

CONTRACTOR PERFORMANCE AND SERVICES..... 8

301 CONSIDERATION
(CONTRACTOR’S PROMISE OF PERFORMANCE)..... 8

302 NOTICE TO PROCEED AND COMPLETION OF THE WORK 8

303 EXACT CONTRACTOR PERFORMANCE..... 8

304 SUBSTITUTED PERFORMANCE 8

305 WORK PERFORMED UNDER ADVERSE
WEATHER CONDITIONS..... 9

| | | |
|-----|---|----|
| 306 | WORKING HOURS AND SCHEDULE | 9 |
| 307 | CONTRACTOR'S SUPERINTENDENT | 10 |
| 308 | COMMUNICATIONS | 10 |
| 309 | CONTRACTOR SUBMITTALS AND OTHER WRITTEN COMMUNICATIONS TO THE CITY | 10 |
| 310 | COMPETENCE OF CONTRACTOR'S WORK FORCE | 11 |
| 311 | NO EMPLOYMENT OF ILLEGAL ALIENS TO PERFORM WORK UNDER THE CONTRACT | 11 |
| 312 | CONDUCT OF CONTRACTOR'S PERSONNEL | 12 |
| 313 | SUGGESTIONS TO CONTRACTOR | 12 |
| 314 | WORK FORCE | 12 |
| 315 | CONSTRUCTION MACHINES AND STANDBY EQUIPMENT | 13 |
| 316 | CUTTING AND PATCHING THE WORK | 13 |
| 317 | PERMITS AND LICENSES | 13 |
| 318 | CONSTRUCTION SURVEYS | 14 |
| 319 | PRESERVATION OF PERMANENT LAND SURVEY CONTROL MARKERS | 14 |
| 320 | TRADEMARKS, COPYRIGHTS AND PATENTED DEVICES, MATERIALS, AND PROCESSES | 15 |
| 321 | PROJECT SIGNS | 15 |
| 322 | PUBLICITY AND ADVERTISING | 16 |
| 323 | TAXES | 16 |
| 324 | DOCUMENTS AND SAMPLES AT THE SITE | 17 |
| 325 | CLEANUP DURING CONSTRUCTION | 17 |
| 326 | SANITARY FACILITIES | 18 |
| 327 | POWER, LIGHTING, HEATING, VENTILATING, AIR CONDITIONING AND WATER SERVICES | 18 |

TITLE 4

| | |
|--|-----------|
| CONTRACT DOCUMENTS (DRAWINGS AND TECHNICAL SPECIFICATIONS) | 19 |
| 401 CONTRACT DOCUMENTS - REVIEW AND INTERPRETATION | 19 |
| 402 OWNERSHIP OF CONTRACT DRAWINGS AND TECHNICAL SPECIFICATIONS | 20 |
| 403 CONTRACT DRAWINGS AND TECHNICAL SPECIFICATIONS ISSUED TO THE CONTRACTOR | 20 |
| 404 REQUESTS FOR INFORMATION OR CLARIFICATION | 21 |
| 405 SHOP DRAWINGS, PRODUCT DATA AND SAMPLES | 21 |
| 406 SUBSTITUTION OF MATERIALS AND EQUIPMENT | 22 |

TITLE 5

| | |
|------------------------------------|-----------|
| SUBCONTRACTS | 24 |
| 501 SUBCONTRACTS | 24 |
| 502 SUBCONTRACTOR ACCEPTANCE | 24 |

TITLE 6

| | |
|---|-----------|
| TIME OF COMMENCEMENT AND COMPLETION | 27 |
| 601 BEGINNING, PROGRESS AND TIME OF COMPLETION | 27 |
| 602 LIQUIDATED DAMAGES; ADMINISTRATIVE COSTS; ACTUAL DAMAGES | 27 |
| 603 DELAY DAMAGES | 28 |

| | |
|--|-----------|
| TITLE 7 | |
| COOPERATION, COORDINATION AND RATE OF PROGRESS | 29 |
| 701 COOPERATION WITH OTHER WORK FORCES | 29 |
| 702 COORDINATION OF THE WORK..... | 30 |
| 703 COORDINATION OF PUBLIC CONTACT..... | 30 |
| 704 RATE OF PROGRESS..... | 30 |
| TITLE 8 | |
| PROTECTION OF PERSONS AND PROPERTY | 32 |
| 801 SAFETY OF PERSONS..... | 32 |
| 802 PROTECTIVE DEVICES AND SAFETY PRECAUTIONS | 33 |
| 803 PROTECTION OF PROPERTY AND WORK IN PROGRESS | 33 |
| 804 PROTECTION OF MUNICIPAL, PUBLIC SERVICE OR PUBLIC UTILITY SYSTEMS | 34 |
| 805 PROTECTION OF STREET AND ROAD SYSTEM | 35 |
| 806 PROTECTION OF DRAINAGE WAYS..... | 36 |
| 807 PROTECTION OF THE ENVIRONMENT..... | 36 |
| 808 HAZARDOUS AND EXPLOSIVE MATERIALS OR SUBSTANCES | 37 |
| 809 ARCHAEOLOGICAL AND HISTORICAL DISCOVERIES..... | 37 |
| TITLE 9 | |
| COMPENSATION | 38 |
| 901 CONSIDERATION (CITY’S PROMISE TO PAY) | 38 |
| 902 PAYMENT PROCEDURE | 38 |
| 903 SCHEDULE OF VALUES IN LUMP SUM CONTRACTS | 39 |
| 904 UNIT PRICE CONTRACTS..... | 39 |
| 905 PROGRESS PERIOD..... | 39 |
| 906 APPLICATIONS FOR PAYMENT | 40 |
| 907 RELEASES AND CONTRACTORS CERTIFICATIONS OF PAYMENT | 41 |
| 908 RETAINAGE | 41 |
| 909 ADDITIONAL WITHHOLDING OF PROGRESS PAYMENTS | 42 |
| 910 FINAL ESTIMATE AND PAYMENT | 43 |
| 911 ACCOUNTING OF COSTS AND AUDIT..... | 43 |
| TITLE 10 | |
| WAGE..... | 45 |
| 1001 PREVAILING WAGE ORDINANCE | 45 |
| 1002 POSTING OF THE APPLICABLE WAGE RATES | 45 |
| 1003 RATE AND FREQUENCY OF WAGES PAID..... | 45 |
| 1004 REPORTING WAGES PAID | 45 |
| 1005 FAILURE TO PAY PREVAILING WAGES | 46 |
| TITLE 11 | |
| CHANGES IN THE WORK, CONTRACT PRICE OR CONTRACT TIME | 47 |
| 1101 CHANGE ORDER..... | 47 |
| 1102 CITY INITIATED CHANGES | 47 |
| 1103 CONTRACTOR CHANGE REQUEST..... | 48 |
| 1104 ADJUSTMENT TO CONTRACT AMOUNT | 51 |
| 1105 TIME EXTENSIONS..... | 54 |

| | |
|--|-----------|
| TITLE 12 | |
| CONTRACTOR CLAIMS FOR ADJUSTMENT AND DISPUTES..... | 56 |
| 1201 NOTICE OF INTENT TO CLAIM | 56 |
| 1202 SUBMITTAL OF CLAIMS | 56 |
| 1203 WAIVER OF CLAIMS | 58 |
| | |
| TITLE 13 | |
| DISPUTES..... | 59 |
| 1301 DISPUTES..... | 59 |
| | |
| TITLE 14 | |
| SITE CONDITIONS | 60 |
| 1401 DIFFERING SITE CONDITIONS..... | 60 |
| 1402 SITE INSPECTIONS AND INVESTIGATIONS..... | 60 |
| | |
| TITLE 15 | |
| PERFORMANCE AND PAYMENT BONDS | 62 |
| 1501 SURETY BONDS | 62 |
| 1502 PERFORMANCE BOND..... | 62 |
| 1503 PAYMENT BOND..... | 62 |
| | |
| TITLE 16 | |
| INSURANCE AND INDEMNIFICATION | 63 |
| 1601 INSURANCE | 63 |
| 1602 DEFENSE AND INDEMNIFICATION | 63 |
| | |
| TITLE 17 | |
| INSPECTION AND DEFECTS..... | 64 |
| 1701 CONSTRUCTION INSPECTION BY THE CITY | 64 |
| 1702 AUTHORITY OF INSPECTORS | 64 |
| 1703 OBSERVABLE DEFECTS | 64 |
| 1704 DEFECTS - UNCOVERING WORK | 64 |
| 1705 LATENT DEFECTS | 65 |
| 1706 REMOVAL OF DEFECTIVE MATERIALS AND WORK | 65 |
| | |
| TITLE 18 | |
| WARRANTIES, GUARANTEES AND CORRECTIVE WORK..... | 66 |
| 1801 CONTRACTOR’S WARRANTIES, GUARANTEES AND CORRECTION OF WORK | 66 |
| 1802 PERFORMANCE DURING WARRANTY PERIOD | 67 |
| | |
| TITLE 19 | |
| SUBSTANTIAL COMPLETION OF THE WORK..... | 69 |
| 1901 CONTRACTOR’S NOTICE OF SUBSTANTIAL COMPLETION | 69 |
| 1902 INSPECTION AND PUNCH LIST..... | 69 |
| 1903 CERTIFICATE OF SUBSTANTIAL COMPLETION | 69 |
| 1904 RIGHT OF EARLY OCCUPANCY OR USE | 69 |
| | |
| TITLE 20 | |
| FINAL COMPLETION AND ACCEPTANCE OF THE WORK | 71 |
| 2001 CLEAN-UP UPON COMPLETION | 71 |
| 2002 FINAL COMPLETION AND ACCEPTANCE OF THE WORK | 71 |
| 2003 FINAL SETTLEMENT | 71 |

| | |
|---|-----------|
| TITLE 21 | |
| SUSPENSION OF WORK..... | 74 |
| 2101 SUSPENSION OF WORK..... | 74 |
| 2102 SUSPENSION OF THE WORK FOR THE CITY'S CONVENIENCE | 74 |
| 2103 SUSPENSION BECAUSE OF ORDER OF CITY, STATE OR FEDERAL COURT OR AGENCY | 75 |
| 2104 SUSPENSION RESULTING FROM CONTRACTOR'S FAILURE TO PERFORM..... | 75 |
| TITLE 22 | |
| CITY'S RIGHT TO TERMINATE THE CONTRACT | 76 |
| 2201 TERMINATION OF CONTRACT FOR CAUSE | 76 |
| 2202 TERMINATION OF CONTRACT FOR CONVENIENCE OF THE CITY | 77 |
| TITLE 23 | |
| MISCELLANEOUS PROVISIONS..... | 80 |
| 2301 PARTIES TO THE CONTRACT..... | 80 |
| 2302 FEDERAL AID PROVISIONS..... | 80 |
| 2303 NO WAIVER OF RIGHTS | 80 |
| 2304 NO THIRD PARTY BENEFICIARY | 80 |
| 2305 GOVERNING LAW; VENUE | 81 |
| 2306 ABBREVIATIONS | 81 |
| 2307 STATUTE OF LIMITATIONS IN C.R.S. § 13-80-102(1)(h) | 81 |

[REMAINDER OF PAGE INTENTIONALLY LEFT BLANK]

CITY AND COUNTY OF DENVER
SPECIAL CONTRACT CONDITIONS

SC-1 CONSTRUCTION SPECIFICATIONS

Except as amended herein or in the attached/incorporated Technical Specifications, all Work performed under the terms of this Contract shall be governed by the applicable provisions of the following latest editions:

City and County of Denver:

Standard Specifications for Construction, GENERAL CONTRACT CONDITIONS,
(2011 Edition)

Transportation Standards and Details for the Engineering Division

City and County of Denver Traffic Standard Drawings

Wastewater Capital Projects Management

<https://www.denvergov.org/content/denvergov/en/wastewater-management/capital-projects-management.html>

Colorado Department of Transportation:

Standard Specifications for Road and Bridge Construction
(Sections 200 through 700 of the 2019 Edition)

Federal Highway Administration:

Manual on Uniform Traffic Control Devices for Streets & Highways (MUTCD)

Building & Fire Codes:

Building Code of the City and County of Denver

(International Building Code 2018 Series, City and County of Denver Amendments 2019)

<https://www.denvergov.org/content/denvergov/en/denver-development-services/help-me-find/building-codes-and-policies.html>

National Fire Protection Association Standards

(As referenced in the Building Code of the City and County of Denver)

The aforementioned City and County of Denver documents are available for review at the Capital Projects Management Office, 201 W. Colfax Ave., Dept. 506, (5th floor), Denver, CO 80202. The *Standard Specifications for Construction, GENERAL CONTRACT CONDITIONS* is available at: <https://www.denvergov.org/content/denvergov/en/contract-administration/contractor-resources.html> *Transportation Standards and Details for the Engineering Division* and the Wastewater Management Division – *Standard Detail Drawings*, are available at <http://www.denvergov.org>.

The “*Colorado Department of Transportation Standard Specifications for Road and Bridge Construction*” is available for review on CDOT’s website at <http://www.coloradodot.info/> and can be purchased from the Colorado Department of Transportation.

The *Manual on Uniform Traffic Control Devices for Streets & Highways* is available for review at the Federal Highway Administration Website at: www.fhwa.dot.gov, The FHWA website also contains purchasing information.

SC-2 DEPARTMENT OF TRANSPORTATION AND INFRASTRUCTURE (REPLACES GENERAL CONTRACT CONDITION 203)

As of January 1, 2020, the functions of Public Works are housed in the new Department of Transportation and Infrastructure. For purposes of this Contract all references (including, but not limited to, references appearing in the body of the contract, General Conditions, Special Conditions, Exhibits, Contract Documents or Policies and Procedures) to the Department of Public Works will have the same meaning as the Department of Transportation and Infrastructure.

Vested exclusively in the Department of Transportation and Infrastructure is the management and control of the design and construction of general and local public improvements undertaken by the City and County of Denver, except for: (i) work which is under the management and control of the Department of Aviation; (ii) that work performed by the Denver Board of Water Commissioners; (iii) any such work that the Mayor has specifically assigned to another department or agency; and (iv) work under the authority of the Department of Transportation and Infrastructure that is performed with the permission of the Manager of Transportation and Infrastructure by private entities at their own expense.

SC-3 MANAGER OF DEPARTMENT OF TRANSPORTATION AND INFRASTRUCTURE (REPLACES GENERAL CONTRACT CONDITION 204)

General Condition 204 "Manager of Public Works" is hereby deleted in its entirety and replaced with the following:

As of January 1, 2020, the functions of Public Works are housed in the new Department of Transportation and Infrastructure. The Manager of Public Works / Executive Director of Public Works will become the Executive Director of Transportation and Infrastructure. Manager of Public Works, Executive Director of Public Works, Executive Director of Transportation and Infrastructure and Manager of Transportation and Infrastructure will have the same meaning for purposes of this Agreement.

SC-4 DEPUTY MANAGER / CITY ENGINEER

General condition 109 DEPUTY MANAGER is hereby deleted in its entirety and replaced with the following:

The "Deputy Manager" means the official who reports directly to the Manager and exercises supervisory responsibility in the City agency defined in Title 2 herein that is responsible for the Project. The Manager hereby designates the City Engineer as the Deputy Manager for purposes of this Contract. The City Engineer shall have responsibility for this Project and shall undertake all duties, responsibilities, rights and authority, including specific actions and decisions, delegated to the Deputy Manager under the various terms and conditions of this Contract.

SC-5 PROJECT DELIVERY ADMINISTRATION / CITY ENGINEER

Project Delivery Administration is a division of the Department of Transportation and Infrastructure and is supervised by the City Engineer, who is subordinate to the Manager of Transportation and Infrastructure. This Division is responsible for the planning, design, construction, operation and maintenance of all of the City's transportation facilities and the planning, design and construction of all of the City's wastewater facilities, except for the City's Municipal Airport System. All other references to the Transportation Division or the Deputy Manager of Public Works are deleted and replaced with references to the Engineering Division and the City Engineer, respectively.

SC-6 [RESERVED]

SC-7 CITY DELEGATION OF AUTHORITY

With reference to General Contract Condition 109, DEPUTY MANAGER and General Contract Condition 212, CITY’S CONTRACT ADMINISTRATION LINE OF AUTHORITY, the Manager hereby designates the City Engineer as the City official responsible for those certain actions and decisions designated as the responsibility of the Deputy Manager under the General Conditions and delegates to the City Engineer the authority necessary to undertake those responsibilities under this Contract. The City Engineer shall have supervisory responsibility over the Project Manager. Additionally, Contractor questions concerning the Plans and Technical Specifications shall be directed to:

Department of Transportation and Infrastructure:

Project Manager

Amy Strouthopoulos

Telephone

720.766.5140

SC-8 LIQUIDATED DAMAGES

Should the Contractor fail to complete all Work within the Contract Time allocated under the Contract Form at Paragraph 3, TERMS OF PERFORMANCE, the Contractor shall become liable to the City and County of Denver for liquidated damages, and not as a penalty, at the rate of **\$1,500.00** for each Day that the Contractor exceeds the time limits herein specified, all in accordance with provisions of General Contract Condition 602, LIQUIDATED DAMAGES; ADMINISTRATIVE COSTS; ACTUAL DAMAGES.

Representative hourly rates for the City administrative costs described in General Contract Condition 602.2 shall be as follows for this Project:

| | |
|-------------------------|----------------|
| Project Manager | \$69 per hour |
| Project Engineer | \$63 per hour |
| Inspector | \$49 per hour |
| Surveying, if necessary | \$100 per hour |

SC-9 SUBCONTRACTS

In accordance with General Contract Condition 501, SUBCONTRACTS, no limit shall apply to that percentage of the Work, which may be sublet providing that the subcontractors receive prior approval in accordance with General Contract Condition 502, SUBCONTRACTOR ACCEPTANCE.

SC-10 PAYMENTS TO CONTRACTORS

The application for payment shall be submitted through Textura® Corporations Construction Management Website. Contractor recognizes and agrees that it shall be required to use the Textura® Construction Payment Management System (“Textura”) for this Project to request payment from the City and to pay all first tier subcontractors and suppliers and further record payment to all certified subcontractors or suppliers that are listed for participation towards any assigned SMWDBE program goal. Contractor further agrees that, to the fullest extent possible within Textura, the City shall be entitled to all non-Confidential records, reports, data and other information related to the project that are available to Contractor through Textura, including, but not limited to, information related to Contractor and subcontractor billings. To that end, Contractor agrees it will activate any available settings within Textura necessary to grant the City access to such non-Confidential information related to the contract and the project. Applications for payment shall be based on the Contract Unit Prices or the approved Schedule of Values described in GC 903.1

In accordance with General Contract Condition 902, PAYMENT PROCEDURE, the party(ies) responsible for review of all Pay Applications shall be:

| <u>Agency/Firm</u> | <u>Name</u> | <u>Telephone</u> |
|---|--------------------|------------------|
| Department of Transportation and Infrastructure | Amy Strouthopoulos | 720.766.5140 |

In accordance with General Contract Condition 906, APPLICATIONS FOR PAYMENT, each Application submitted shall include the following:

1. The estimate of Work completed shall be based on the approved schedule of values or unit prices, as applicable, and the percent of the Work complete.
2. Each Application for Payment shall include each and every independent subcontractor's payroll information including pay dates and pay amounts.
3. The Contractor, and its subcontractors of all tiers who have performed work, shall also submit to the Auditor and other appropriate officials of the City prior to submitting the payment application, information required by General Contract Condition 1004, REPORTING WAGES PAID.
4. Starting with the second payment application, the payment applications shall be accompanied by a completed Contractors' Certification of Payment Form (CCP), listing all first tier subcontractors and suppliers and all certified subcontractors or suppliers that are listed for participation towards any assigned SMWDBE program goal. The final payment application must be accompanied by an executed Final Claim Release Form and Certificate of Contract Release Form from the Contractor.

* If subcontractor or supplier payments are disbursed via Textura® CPM, those systems generated Release and CCP forms are acceptable.

Title 20, 2003 Final Settlement, section .2, item F is modified to read as follows:

F. At time of request for final payment, Contractor shall submit a complete and final, unconditional waiver or release of any and all lien and claim rights for all labor, equipment, and material used or furnished to complete the Work in the form and format generated within the Textura CPM system. Contractor shall also return an executed Certificate of Contract Release (below), upon request from the City.

[REMAINDER OF PAGE INTENTIONALLY LEFT BLANK]



**City and County of Denver
Contractor's/Consultant's Certification of Payment (CCP)**

| | | | |
|---------------------------------|-------------------|--------------------------|------------------|
| Prime Contractor or Consultant: | | Phone: | Project Manager: |
| Pay Application #: | Pay Period: | Amount Requested: | |
| Contract #: | Project Name: | | |
| Current Completion Date: | Percent Complete: | Prepared By: | |
| Original Contract Amount: | | Current Contract Amount: | |

| Prime/Subcontractor/Supplier Name | Contracted to: | M/W/S/ DBE/ NON | A | B | C | D | E | F |
|-----------------------------------|--------------------|-----------------------|--------------------------|--|--|---|------------------|-----------------------|
| | | | Original Contract Amount | Current Contract Amount including Amendments | Requested Amount of this Pay Application | Amount Paid on the Previous Pay Application # | Net Paid To Date | Paid % Achieved (G/I) |
| General Contractor | City of Denver | MBE | | | | | | |
| Self Performed | n/a | | | | | | | |
| Subcontracted | n/a | | | | | | | |
| Sub1 - 1st Tier | General Contractor | | | | | | | |
| Sub2 - 1st Tier | General Contractor | | | | | | | |
| Self Performed | n/a | | | | | | | |
| Sub 1 - 2nd Tier | Sub 2 - 1st Tier | | | | | | | |
| Sub 3 - 1st Tier | General Contractor | | | | | | | |
| Self Performed | n/a | | | | | | | |
| Sub 2 - 2nd Tier | Sub 3 - 1st Tier | | | | | | | |
| Self Performed | n/a | | | | | | | |
| Sub 1 - 3rd Tier | Sub 2 - 2nd Tier | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| Totals | | | \$ - | \$ - | \$ - | \$ - | \$ - | 0% |

The undersigned certifies that the information contained in this document is true, accurate and that the payments shown have been made to all subcontractors and suppliers used on this project and listed herein. Please use an additional form, if more space is necessary.

| | |
|--------------------------|-------|
| Prepared By (Signature): | Date: |
|--------------------------|-------|

SC-11 CONTRACT FORMS

In accordance with the terms and conditions of the Contract Documents, the City requires the use of certain form documents in complying with or satisfying various obligations, notifications and conditions in contracting with the City or performing Work hereunder. These form documents are referenced by title throughout the Contract Documents for mandatory use as directed. The following are the forms that shall be utilized in accordance with the Contract Documents:

1. Performance and Payment Bond
2. Performance and Payment Bond Surety Authorization Letter (Sample)
3. Final Release and Certificate of Payment
4. Certificate of Contract Release, if requested by the City

The following are forms that will be issued by the City during construction:

1. Notice to Apparent Low Bidder (Sample)
2. Notice To Proceed (Sample)
3. Certificate of Contract Release (Sample)

SC-12 CONSTRUCTION INSPECTION BY THE CITY

General Condition 1701, CONSTRUCTION INSPECTION BY THE CITY, is modified as follows:

1701.1 Persons who are employees of the City or who are under contract to the City or the City as lessee will be assigned to inspect and test the Work. These persons may perform any tests and observe the Work to determine whether or not designs, materials used, manufacturing and construction processes and methods applied, and equipment installed satisfy the requirements of the drawings and specifications, accepted Shop Drawings, Product Data and Samples, and the General Contractor's warranties and guarantees. The General Contractor shall permit these inspectors unlimited access to the Work and provide means of safe access to the Work, which cost shall be included as a Cost of the Work without any increase to the Guaranteed Maximum Price. In addition, General Contractor shall provide whatever access and means of access are needed to off-site facilities used to store or manufacture materials and equipment to be incorporated into the Work and shall respond to any other reasonable request to further the inspector's ability to observe or complete any tests. Such inspections shall not relieve the General Contractor of any of its quality control responsibilities or any other obligations under the Contract. All inspections and all tests conducted by the City are for the convenience and benefit of the City. These inspections and tests do not constitute acceptance of the materials or Work tested or inspected, and the City may reject or accept any Work or materials at any time prior to the inspections pursuant to G.C. 2002, whether or not previous inspections or tests were conducted by the inspector or a City representative.

.2 Building Inspection will perform building code compliance inspections for structures designed for human occupancy. It is the General Contractor's responsibility to schedule and obtain these inspections. If a code compliance inspection results in identification of a condition which will be at variance to the Contract Documents, the General Contractor shall immediately notify the Project Manager and confirm such notification with formal correspondence no later than forty-eight (48) hours after the occurrence.

.3 When any unit of government or political subdivision, utility or railroad corporation is to pay a portion of the cost of the Work, its respective representatives shall have the right to inspect the Work. This inspection shall not make any unit of government or political subdivision, utility or railroad corporation a party to the Contract, and shall not interfere with the rights of either party.

SC-13 DISPOSAL OF NON-HAZARDOUS WASTE AT DADS

In accordance with the Landfill Agreement made between the City and Waste Management of Colorado, Inc., bidders will be required to haul dedicated loads (non-hazardous entire loads of waste) to the Denver-Arapahoe Disposal Site (“DADS”) for disposal. DADS is located at Highway 30 and Hampden Avenue in Arapahoe County, Colorado. The City will pay all fees associated with such disposal but the bidder shall be responsible for the costs of transporting the loads. Non-hazardous waste is defined as those substances and materials not defined or classified as hazardous by the Colorado Hazardous Waste Commission pursuant to C.R.S. §25-15-101(6), as amended from time to time, and includes construction debris, soil and asbestos. Bidders shall not use Gun Club Road between I-70 and Mississippi Avenue as a means of access to DADS.

SC-14 PROHIBITION ON USE OF CCA-TREATED WOOD PRODUCTS

The use of any wood products pressure-treated with chromated copper arsenate (CCA) is prohibited. Examples of CCA-treated wood products include wood used in play structures, decks, picnic tables, landscaping timbers, fencing, patios, walkways and boardwalks.

SC-15 WAIVER OF: PART 8 OF ARTICLE 20 OF TITLE 13, COLORADO REVISED STATUTES

The Contractor specifically waives all the provisions of Part 8 of Article 20 of Title 13, Colorado Revised Statutes regarding defects in the Work under this Construction Contract.

SC-16 ATTORNEY’S FEES

Colorado Revised Statute 38-26-107 requires that in the event any person or company files a verified statement of amounts due and unpaid in connection with a claim for labor and materials supplied on this project, the City shall withhold from payments to the Contractor sufficient funds to insure the payment of any such claims. Should the City and County of Denver be made a party to any lawsuit to enforce such unpaid claims or any lawsuit arising out of or relating to such withheld funds, the Contractor agrees to pay to the City its costs and a reasonable attorney’s fee which cost shall be included as a Cost of the Work.

Because the City Attorney Staff does not bill the City for legal services on an hourly basis, the Contractor agrees a reasonable fee shall be computed at the rate of one hundred dollars per hour of City Attorney time.

SC-17 INSURANCE

General Condition 1601 is hereby deleted in its entirety and replaced with the following:

(1) General Conditions: Contractor agrees to secure, at or before the time of execution of this Agreement, the following insurance covering all operations, goods or services provided pursuant to this Agreement. Contractor shall keep the required insurance coverage in force at all times during the term of the Agreement, or any extension thereof, during any warranty period, and for eight (8) years after termination of the Agreement. The required insurance shall be underwritten by an insurer licensed or authorized to do business in Colorado and rated by A.M. Best Company as “A-”VIII or better. Each policy shall contain a valid provision or endorsement requiring notification to the City in the event any of the required policies be canceled or non-renewed before the expiration date thereof. Such written notice shall be sent to the parties identified in the Notices section of this Agreement. Such notice shall reference the City contract number listed on the signature page of this Agreement. Said notice shall be sent thirty (30) days prior to such cancellation or non-renewal unless due to non-payment of premiums for which notice shall be sent ten (10) days prior. If such written notice is unavailable from the insurer, contractor shall provide written notice of cancellation, non-renewal and any reduction in coverage to the parties identified in the Notices section by certified mail, return receipt requested within three (3) business days of such notice by its insurer(s) and referencing the City’s contract number. If any policy is in excess of a deductible or self-insured retention, the City must be notified by the Contractor. Contractor shall be responsible for the payment of any deductible or self-insured retention. The insurance coverages specified in this Agreement are the minimum

requirements, and these requirements do not lessen or limit the liability of the Contractor. The Contractor shall maintain, at its own expense, any additional kinds or amounts of insurance that it may deem necessary to cover its obligations and liabilities under this Agreement.

(2) Proof of Insurance: Contractor shall provide a copy of this Agreement to its insurance agent or broker. Contractor may not commence services or work relating to the Agreement prior to placement of coverage. Contractor certifies that the certificate of insurance attached as part of the Contract Documents, preferably an ACORD certificate, complies with all insurance requirements of this Agreement. The City requests that the City's contract number be referenced on the Certificate. The City's acceptance of a certificate of insurance or other proof of insurance that does not comply with all insurance requirements set forth in this Agreement shall not act as a waiver of Contractor's breach of this Agreement or of any of the City's rights or remedies under this Agreement. The City's Risk Management Office may require additional proof of insurance, including but not limited to policies and endorsements.

(3) Additional Insureds: For Commercial General Liability, Auto Liability and Contractors Pollution Liability, Contractor and subcontractor's insurer(s) shall name the City and County of Denver, its elected and appointed officials, employees and volunteers as additional insured.

(4) Waiver of Subrogation: For all coverages, Contractor's insurer shall waive subrogation rights against the City.

(5) Subcontractors and Subconsultants: All subcontractors and subconsultants (including independent contractors, suppliers or other entities providing goods or services required by this Agreement) shall be subject to all of the requirements herein and shall procure and maintain the same coverages required of the Contractor. Contractor shall include all such subcontractors as additional insured under its policies (with the exception of Workers' Compensation) or shall ensure that all such subcontractors and subconsultants maintain the required coverages. Contractor agrees to provide proof of insurance for all such subcontractors and subconsultants upon request by the City.

(6) Workers' Compensation/Employer's Liability Insurance: Contractor shall maintain the coverage as required by statute for each work location and shall maintain Employer's Liability insurance with limits of \$100,000 per occurrence for each bodily injury claim, \$100,000 per occurrence for each bodily injury caused by disease claim, and \$500,000 aggregate for all bodily injuries caused by disease claims. Contractor expressly represents to the City, as a material representation upon which the City is relying in entering into this Agreement, that none of the Contractor's officers or employees who may be eligible under any statute or law to reject Workers' Compensation Insurance shall effect such rejection during any part of the term of this Agreement, and that any such rejections previously effected, have been revoked as of the date Contractor executes this Agreement.

(7) Commercial General Liability: Contractor shall maintain a Commercial General Liability insurance policy with limits of \$1,000,000 for each occurrence, \$1,000,000 for each personal and advertising injury claim, \$2,000,000 products and completed operations aggregate, and \$2,000,000 policy aggregate.

(8) Business Automobile Liability: Contractor shall maintain Business Automobile Liability with limits of \$1,000,000 combined single limit applicable to all owned, hired and non-owned vehicles used in performing services under this Agreement.

(9) Additional Provisions:

- (a) For Commercial General Liability, the policies must provide the following:
 - (i) That this Agreement is an Insured Contract under the policy;
 - (ii) Defense costs in excess of policy limits;

- (iii) A severability of interests or separation of insureds provision (no insured vs. insured exclusion); and
 - (iv) A provision that coverage is primary and non-contributory with other coverage or self-insurance maintained by the City.
- (b) For claims-made coverage:
- (i) The retroactive date must be on or before the contract date or the first date when any goods or services were provided to the City, whichever is earlier.
- (c) Contractor shall advise the City in the event any general aggregate or other aggregate limits are reduced below the required per occurrence limits. At their own expense, and where such general aggregate or other aggregate limits have been reduced below the required per occurrence limit, the Contractor will procure such per occurrence limits and furnish a new certificate of insurance showing such coverage is in force.

SC-18 GREENPRINT DENVER REQUIREMENTS

In accordance with the City and County of Denver Executive Order 123: Greenprint Denver Office and Sustainability Policy, as amended, Contractor shall adhere to sections of Executive Order 123 pertinent to the construction of the built environment. This includes but is not limited to: all construction and renovation of buildings shall follow instructions and memorandum for high performance buildings; horizontal projects shall include the use of fly ash concrete and recycled aggregate where possible; and, all projects shall recycle construction and demolition waste, and install materials that contain recycled content whenever possible using the U.S. Green Building Council Leadership in Energy and Environmental Design (LEED) as guidance. Non-hazardous solid waste that is eligible for reuse or recycling is not subject to the DADS disposal requirement defined in SC-13.

A completed “Greenprint Denver Closeout Form for Construction Projects” shall be delivered to the Project Manager as a submittal requirement of Final Acceptance.

<https://www.denvergov.org/content/denvergov/en/contract-administration/contractor-resources.html>

SC-19 RESERVED

SC-20 DEFENSE AND INDEMNIFICATION

Title 1602 is hereby deleted in its entirety and replaced with the following:

- (a) To the fullest extent permitted by law, the Contractor hereby agrees to defend, indemnify, reimburse and hold harmless City, its appointed and elected officials, agents and employees for, from and against all liabilities, claims, judgments, suits or demands for damages to persons or property arising out of, resulting from, or related to the work performed under this Agreement that are due to the negligence or fault of the Contractor or the Contractor’s agents, representatives, subcontractors, or suppliers (“Claims”). This indemnity shall be interpreted in the broadest possible manner consistent with the applicable law to indemnify the City.
- (b) Contractor’s duty to defend and indemnify City shall arise at the time written notice of the Claim is first provided to City regardless of whether suit has been filed and even if Contractor is not named as a Defendant.
- (c) Contractor will defend any and all Claims which may be brought or threatened against City and will pay on behalf of City any expenses incurred by reason of such Claims including, but not limited to, court costs and attorney fees incurred in defending and investigating such Claims or seeking to enforce this indemnity obligation. Such payments on behalf of City shall be in addition to any other legal remedies available to City and shall not be considered City’s exclusive remedy.

- (d) Insurance coverage requirements specified in this Agreement shall in no way lessen or limit the liability of the Contractor under the terms of this indemnification obligation. The Contractor shall obtain, at its own expense, any additional insurance that it deems necessary for the City's protection.
- (e) This defense and indemnification obligation shall survive the expiration or termination of this Agreement.

[REMAINDER OF PAGE INTENTIONALLY LEFT BLANK]

**CITY AND COUNTY OF DENVER
DEPARTMENT OF TRANSPORTATION AND INFRASTRUCTURE**

PERFORMANCE AND PAYMENT BOND

KNOW ALL MEN BY THESE PRESENTS, that we, the undersigned **VANCE BROTHERS, INC., 380 W 62nd Ave, Denver, CO 80216**, a corporation organized and existing under and by virtue of the laws of the State of **Colorado**, hereafter referred to as the "Contractor", and **Liberty Mutual Insurance Company Phone No. 610-832-8240**, a corporation organized and existing under and by virtue of the laws of the State of **Massachusetts**, and authorized to transact business in the State of Colorado, as Surety, are held and firmly bound unto the CITY AND COUNTY OF DENVER, a municipal corporation of the State of Colorado, hereinafter referred to as the "City", in the penal sum of **Four Million Four Hundred Thirteen Thousand Nine Hundred Sixty Dollars and No Cents (\$4,413,960.00)**, lawful money of the United States of America, for the payment of which sum, well and truly to be made, we bind ourselves and our heirs, executors, administrators, successors and assigns, jointly and severally, firmly by these presents;

THE CONDITION OF THE FOREGOING OBLIGATION IS SUCH THAT:

WHEREAS, the above bounden Contractor has entered into a written contract with the aforesaid City for furnishing all labor and tools, supplies, equipment, superintendence, materials and everything necessary for and required to do, perform and complete the construction of **Contract No. 202057115 - 2021 Citywide Chip Seal and Crack Seal**, Denver, Colorado, and has bound itself to complete the project within the time or times specified or pay liquidated damages, all as designated, defined and described in the said Contract and Conditions thereof, and in accordance with the Plans and Technical Specifications therefore, a copy of said Contract being made a part hereof;

NOW, THEREFORE, if the said Contractor shall and will, in all particulars well and truly and faithfully observe, perform and abide by each and every Covenant, Condition and part of said Contract, and the Conditions, Technical Specifications, Plans, and other Contract Documents thereto attached, or by reference made a part thereof and any alterations in and additions thereto, according to the true intent and meaning in such case, then this obligation shall be and become null and void; otherwise, it shall remain in full force and effect;

PROVIDED FURTHER, that if the said Contractor shall satisfy all claims and demands incurred by the Contractor in the performance of said Contract, and shall fully indemnify and save harmless the City from all damages, claims, demands, expense and charge of every kind (including claims of patent infringement) arising from any act, omission, or neglect of said Contractor, its agents, or employees with relation to said work; and shall fully reimburse and repay to the City all costs, damages, and expenses which it may incur in making good any default based upon the failure of the Contractor to fulfill its obligation to furnish maintenance, repairs or replacements for the full guarantee period provided in the Contract Documents, then this obligation shall be null and void; otherwise it shall remain in full force and effect;

PROVIDED FURTHER, that if said Contractor shall at all times promptly make payments of all amounts lawfully due to all persons supplying or furnishing it or its subcontractors with labor and materials, rental machinery, tools or equipment used or performed in the prosecution of work provided for in the above Contract and that if the Contractor will indemnify and save harmless the City for the extent of any and all payments in connection with the carrying out of such Contract, then this obligation shall be null and void; otherwise it shall remain in full force and effect;

PROVIDED FURTHER, that if the said Contractor fails to duly pay for any labor, materials, team hire, sustenance, provisions, provender, gasoline, lubricating oils, fuel oils, grease, coal, or any other supplies or materials used or consumed by said Contractor or its subcontractors in performance of the work contracted to be done, or fails to pay any person who supplies rental machinery, tools or equipment, all amounts due as the result of the use of such machinery, tools or equipment in the prosecution of the work, the Surety will pay the same in any amount not exceeding the amount of this obligation, together with interest as provided by law;

PROVIDED FURTHER, that the said Surety, for value received, hereby stipulates and agrees that no change, extension of time, alteration or addition to the terms of the Contract, or to contracts with others in connection with this project, or the work to be performed thereunder, or the Technical Specifications and Plans accompanying the same, shall in any way affect its obligation on this bond and it does hereby waive notice of any change, extension of time, alteration or addition to the terms of the Contract, or contracts, or to the work, or to the Technical Specifications and Plans.

IN WITNESS WHEREOF, said Contractor and said Surety have executed these presents as of this 31st day of March, 2021.

Vance Brothers, Inc.
360 West 62nd Avenue, Denver, CO 80326
Contractor

Attest:
Andrew Vance
Secretary Andrew W. Vance

By: Michael W. Vance
Vice President Michael W. Vance
Liberty Mutual Insurance Company
2200 Renaissance Boulevard, Ste. 400, King of Prussia, PA 19406-2755
Surety

By: Linda L. Nutt
Attorney-In-Fact Linda L. Nutt

(Accompany this bond with Attorney-in-Fact's authority from the Surety to execute bond, certified to include the date of the bond).

APPROVED AS TO FORM:
Attorney for the City and County of Denver

By: [Signature]
Assistant City Attorney

APPROVED FOR THE CITY AND COUNTY
DENVER

By: [Signature]
MAYOR

By: [Signature]
**EXECUTIVE DIRECTOR OF THE DEPARTMENT
OF TRANSPORTATION AND INFRASTRUCTURE**

This Power of Attorney limits the acts of those named herein, and they have no authority to bind the Company except in the manner and to the extent herein stated. Not valid for mortgage, note, loan, letter of credit, bank deposit, currency rate, interest rate or residual value guarantees. To confirm the validity of this Power of Attorney call 610-832-8240 between 9:00 am and 4:30 pm EST on any business day.



Liberty Mutual Insurance Company
The Ohio Casualty Insurance Company
West American Insurance Company

POWER OF ATTORNEY

KNOWN ALL PERSONS BY THESE PRESENTS: That The Ohio Casualty Insurance Company is a corporation duly organized under the laws of the State of New Hampshire, that Liberty Mutual Insurance Company is a corporation duly organized under the laws of the State of Massachusetts, and West American Insurance Company is a corporation duly organized under the laws of the State of Indiana (herein collectively called the "Companies"), pursuant to and by authority herein set forth, does hereby name, constitute and appoint Linda L. Nutt of the city of Kansas City, state of MO its true and lawful attorney-in-fact, with full power and authority hereby conferred to sign, execute and acknowledge the following surety bond:

Principal Name: Vance Brothers, Inc.

Obligee Name: City & County of Denver

Surety Bond Number: 674213002 Bond Amount: See Bond Form

IN WITNESS WHEREOF, this Power of Attorney has been subscribed by an authorized officer or official of the Companies and the corporate seals of the Companies have been affixed thereto this 12th day of December, 2018.



The Ohio Casualty Insurance Company
Liberty Mutual Insurance Company
West American Insurance Company
By: David M. Carey
David M. Carey, Assistant Secretary

STATE OF PENNSYLVANIA ss
COUNTY OF MONTGOMERY

On this 12th day of December, 2018, before me personally appeared David M. Carey, who acknowledged himself to be the Assistant Secretary of Liberty Mutual Insurance Company, The Ohio Casualty Company, and West American Insurance Company, and that he, as such, being authorized so to do, execute the foregoing instrument for the purposes therein contained by signing on behalf of the corporations by himself as a duly authorized officer.

IN WITNESS WHEREOF, I have hereunto subscribed my name and affixed my notarial seal at King of Prussia, Pennsylvania, on the day and year first above written.



COMMONWEALTH OF PENNSYLVANIA
Notarial Seal
Teresa Pastella, Notary Public
Upper Merion Twp., Montgomery County
My Commission Expires March 28, 2021
Member, Pennsylvania Association of Notaries

By: Teresa Pastella
Teresa Pastella, Notary Public

This Power of Attorney is made and executed pursuant to and by authority of the following By-laws and Authorizations of Liberty Mutual Insurance Company, The Ohio Casualty Insurance Company, and West American Insurance Company which resolutions are now in full force and effect reading as follows:

ARTICLE IV – OFFICERS – Section 12. Power of Attorney. Any officer or other official of the Corporation authorized for that purpose in writing by the Chairman or the President, and subject to such limitation as the Chairman or the President may prescribe, shall appoint such attorneys-in-fact, as may be necessary to act in behalf of the Corporation to make, execute, seal, acknowledge and deliver as surety any and all undertakings, bonds, recognizances and other surety obligations. Such attorneys-in-fact, subject to the limitations set forth in their respective powers of attorney, shall have full power to bind the Corporation by their signature and execution of any such instruments and to attach thereto the seal of the Corporation. When so executed, such instruments shall be as binding as if signed by the President and attested to by the Secretary. Any power or authority granted to any representative or attorney-in-fact under the provisions of this article may be revoked at any time by the Board, the Chairman, the President or by the officer or officers granting such power or authority.

ARTICLE XIII – Execution of Contracts – SECTION 5. Surety Bonds and Undertakings. Any officer of the Company authorized for that purpose in writing by the chairman or the president, and subject to such limitations as the chairman or the president may prescribe, shall appoint such attorneys-in-fact, as may be necessary to act in behalf of the Company to make, execute, seal, acknowledge and deliver as surety any and all undertakings, bonds, recognizances and other surety obligations. Such attorneys-in-fact subject to the limitations set forth in their respective powers of attorney, shall have full power to bind the Company by their signature and execution of any such instruments and to attach thereto the seal of the Company. When so executed such instruments shall be as binding as if signed by the president and attested by the secretary.

Certificate of Designation – The President of the Company, acting pursuant to the Bylaws of the Company, authorizes David M. Carey, Assistant Secretary to appoint such attorneys-in-fact as may be necessary to act on behalf of the Company to make, execute, seal, acknowledge and deliver as surety any and all undertakings, bonds, recognizances and other surety obligations.

Authorization – By unanimous consent of the Company's Board of Directors, the Company consents that facsimile or mechanically reproduced signature of any assistant secretary of the Company, wherever appearing upon a certified copy of any power of attorney issued by the Company in connection with surety bonds, shall be valid and binding upon the Company with the same force and effect as though manually affixed.

I, Renee C. Llewellyn, the undersigned, Assistant Secretary, of Liberty Mutual Insurance Company, The Ohio Casualty Insurance Company, and West American Insurance Company do hereby certify that this power of attorney executed by said Companies is in full force and effect and has not been revoked.

IN TESTIMONY WHEREOF, I have hereunto set my hand and affixed the seals of said Companies this _____ day of _____, 2021.



By: Renee C. Llewellyn
Renee C. Llewellyn, Assistant Secretary

March 11, 2021

Assistant City Attorney]
201 W. Colfax Ave. Dept. 1207
Denver, CO

RE: VANCE BROTHERS, INC.

Contract No: 202057115
Project Name: 2021 Citywide Chip Seal and Crack Seal
Amount: \$4,413,950.00
Bond Number: 674213002

Dear Assistant City Attorney,

The Performance and Payment Bonds covering the above captioned project were executed by this agency, through Liberty Mutual Insurance Company, on March 11, 2021.

We hereby authorize the City and County of Denver, the Department of Transportation and Infrastructure, to date all bonds and powers of attorney to coincide with the date of the contract.

If you should have any additional questions or concerns, please don't hesitate to give me a call at 816-843-4414.

Thank you.

Sincerely,

THOMAS MCGEE GROUP



Linda Nutt

Surety Account Manager

d: 816.843.4414 | o: 816.842.4800

lnutt@thomasmcgee.com



CERTIFICATE OF LIABILITY INSURANCE

DATE (MM/DD/YYYY)

3/10/2021

THIS CERTIFICATE IS ISSUED AS A MATTER OF INFORMATION ONLY AND CONFERS NO RIGHTS UPON THE CERTIFICATE HOLDER. THIS CERTIFICATE DOES NOT AFFIRMATIVELY OR NEGATIVELY AMEND, EXTEND OR ALTER THE COVERAGE AFFORDED BY THE POLICIES BELOW. THIS CERTIFICATE OF INSURANCE DOES NOT CONSTITUTE A CONTRACT BETWEEN THE ISSUING INSURER(S), AUTHORIZED REPRESENTATIVE OR PRODUCER, AND THE CERTIFICATE HOLDER.

IMPORTANT: If the certificate holder is an ADDITIONAL INSURED, the policy(ies) must be endorsed. If SUBROGATION IS WAIVED, subject to the terms and conditions of the policy, certain policies may require an endorsement. A statement on this certificate does not confer rights to the certificate holder in lieu of such endorsement(s).


| | | |
|--|---|------------------------------------|
| PRODUCER HUB International Mid-America 9200 Ward Parkway Suite 500 Kansas City MO 64114 | CONTACT NAME: Certificate Department PHONE (A/C. No. Ext): 816-708-4600 E-MAIL ADDRESS: HUB-KC.Certificates@HUBInternational.com | FAX (A/C. No): 816-203-4425 |
| | INSURER(S) AFFORDING COVERAGE | |
| INSURED Vance Brothers, Inc. 380 West 62nd Avenue Denver CO 80216 | INSURER A : The Phoenix Insurance Company NAIC # 25623 | |
| | INSURER B : Travelers Property Casualty Company of America 25674 | |
| | INSURER C : The Travelers Indemnity Company of America 25666 | |
| | INSURER D : Argonaut Insurance Company 19801 | |
| | INSURER E : | |
| | INSURER F : | |

COVERAGES **CERTIFICATE NUMBER:** 1342738239 **REVISION NUMBER:**

THIS IS TO CERTIFY THAT THE POLICIES OF INSURANCE LISTED BELOW HAVE BEEN ISSUED TO THE INSURED NAMED ABOVE FOR THE POLICY PERIOD INDICATED. NOTWITHSTANDING ANY REQUIREMENT, TERM OR CONDITION OF ANY CONTRACT OR OTHER DOCUMENT WITH RESPECT TO WHICH THIS CERTIFICATE MAY BE ISSUED OR MAY PERTAIN, THE INSURANCE AFFORDED BY THE POLICIES DESCRIBED HEREIN IS SUBJECT TO ALL THE TERMS, EXCLUSIONS AND CONDITIONS OF SUCH POLICIES. LIMITS SHOWN MAY HAVE BEEN REDUCED BY PAID CLAIMS.

| INSR LTR | TYPE OF INSURANCE | ADDL INSD | SUBR WVD | POLICY NUMBER | POLICY EFF (MM/DD/YYYY) | POLICY EXP (MM/DD/YYYY) | LIMITS |
|----------|---|-----------|----------|--------------------|-------------------------|-------------------------|---|
| A | <input checked="" type="checkbox"/> COMMERCIAL GENERAL LIABILITY <input type="checkbox"/> CLAIMS-MADE <input checked="" type="checkbox"/> OCCUR GEN'L AGGREGATE LIMIT APPLIES PER: <input type="checkbox"/> POLICY <input checked="" type="checkbox"/> PRO-JECT <input type="checkbox"/> LOC <input type="checkbox"/> OTHER: | Y | | DTC09212947PHX21 | 1/1/2021 | 1/1/2022 | EACH OCCURRENCE \$ 1,000,000 DAMAGE TO RENTED PREMISES (Ea occurrence) \$ 1,000,000 MED EXP (Any one person) \$ 15,000 PERSONAL & ADV INJURY \$ 1,000,000 GENERAL AGGREGATE \$ 2,000,000 PRODUCTS - COMP/OP AGG \$ 2,000,000 \$ |
| C | <input checked="" type="checkbox"/> AUTOMOBILE LIABILITY <input checked="" type="checkbox"/> ANY AUTO <input type="checkbox"/> ALL OWNED AUTOS <input type="checkbox"/> SCHEDULED AUTOS <input checked="" type="checkbox"/> HIRED AUTOS <input checked="" type="checkbox"/> NON-OWNED AUTOS <input checked="" type="checkbox"/> MCS 90 | Y | | DT8109M352747TIA21 | 1/1/2021 | 1/1/2022 | COMBINED SINGLE LIMIT (Ea accident) \$ 1000000 BODILY INJURY (Per person) \$ BODILY INJURY (Per accident) \$ PROPERTY DAMAGE (Per accident) \$ \$ |
| B | <input checked="" type="checkbox"/> UMBRELLA LIAB <input checked="" type="checkbox"/> OCCUR <input type="checkbox"/> EXCESS LIAB <input type="checkbox"/> CLAIMS-MADE <input type="checkbox"/> DED <input checked="" type="checkbox"/> RETENTION \$ 10,000 | Y | | CUP9M4229022126 | 1/1/2021 | 1/1/2022 | EACH OCCURRENCE \$ 10,000,000 AGGREGATE \$ 10,000,000 \$ |
| D | <input checked="" type="checkbox"/> WORKERS COMPENSATION AND EMPLOYERS' LIABILITY ANY PROPRIETOR/PARTNER/EXECUTIVE OFFICER/MEMBER EXCLUDED? (Mandatory in NH) If yes, describe under DESCRIPTION OF OPERATIONS below | Y/N | N/A | WC92870828551 | 1/1/2021 | 1/1/2022 | <input checked="" type="checkbox"/> PER STATUTE <input type="checkbox"/> OTH-ER E.L. EACH ACCIDENT \$ 1,000,000 E.L. DISEASE - EA EMPLOYEE \$ 1,000,000 E.L. DISEASE - POLICY LIMIT \$ 1,000,000 |

DESCRIPTION OF OPERATIONS / LOCATIONS / VEHICLES (ACORD 101, Additional Remarks Schedule, may be attached if more space is required)
 Re: 202057115 - 2021 Citywide Chip Seal and Crack Seal; The City and County of Denver, its Elected and Appointed Officials, Employees and Volunteers are Additional Insured as respects the General, Auto and Umbrella Liability policies.

| | |
|---|---|
| CERTIFICATE HOLDER Department of Transportation & Infrastructure – Contract Administration 201 W Colfax Ave, Dept 614 Denver CO 80202 | CANCELLATION SHOULD ANY OF THE ABOVE DESCRIBED POLICIES BE CANCELLED BEFORE THE EXPIRATION DATE THEREOF, NOTICE WILL BE DELIVERED IN ACCORDANCE WITH THE POLICY PROVISIONS. AUTHORIZED REPRESENTATIVE  |
|---|---|

© 1988-2014 ACORD CORPORATION. All rights reserved.



NOTICE TO APPARENT LOW BIDDER

Name
Address
City, State Zip

The EXECUTIVE DIRECTOR OF THE DEPARTMENT OF TRANSPORTATION AND INFRASTRUCTURE has considered the Bids submitted on **January 21, 2021**, for work to be done and materials to be furnished in and for:

CONTRACT 202057115 - 2021 Citywide Chip Seal and Crack Seal

as set forth in detail in the Contract Documents for the City and County of Denver, Colorado. It appears that your Bid is fair, equitable, and to the best interest of the City and County; therefore, said Bid is hereby accepted at the bid price contained herein, subject to the approval and execution of the Contract Documents by the City in accordance with the Charter of the City and County of Denver, and to your furnishing the items specified below. The award is based on the total bid items: **(# bid items (# through #))** the total estimated cost thereof being: **(Contract Written Amount) (\$_____)**.

In accordance with the requirements set forth in the Contract Documents, you are required to furnish the following documents:

- a. Insurance Certificates: General Liability and Automotive Liability, Workman's Compensation and Employer Liability; and,
- b. Payment and Performance Bond along with One original Power of Attorney relative to Performance and/or Payment Bond.

All construction Contracts made and entered into by the City and County of Denver are subject to Affirmative Action and Equal Opportunity Rules and Regulations, as adopted by the Manager of the Department of Transportation and Infrastructure, and each contract requiring payment by the City of one-half million dollars (\$500,000.00) or more shall first be approved by the City Council acting by ordinance and in accordance with Section 3.2.6 of the Charter of the City and County of Denver.

Prior to issuance of Notice to Proceed, all DSBO requirements must be completed. Additional information may be obtained by contacting the Director of DSBO at (720-913-1714).

NOTICE TO APPARENT LOW BIDDER

CONTRACT NO. 202057115

Page 2

The Bid Security submitted with your Bid, will be returned upon execution of the Contract and furnishing of the Performance Bond. In the event you should fail to execute the Contract and to furnish the performance Bond within the time limit specified, said Bid Security will be retained by the City and County of Denver as liquidated damages, and not as a penalty for the delay and extra work caused thereby.

Dated at Denver, Colorado this _____ day of _____ 20__.

CITY AND COUNTY OF DENVER

By _____
Executive Director of the Department of Transportation and Infrastructure

SAMPLE

City and County of Denver Department of Transportation & Infrastructure

201 West Colfax Avenue, Dept 608 | Denver, CO 80202

www.denvergov.org/doti

311 | POCKETGOV.COM | DENVERGOV.ORG | DENVER 8 TV



**NOTICE TO PROCEED
(SAMPLE)**

Current Date

Name
Company
Street
City/State/Zip

CONTRACT NO. 202057115 - 2021 Citywide Chip Seal and Crack Seal

In accordance with General Contract Condition 302 of the Standard Specifications for Construction, General Contract Conditions, 2011 Edition, you are hereby authorized and directed to proceed on _____ with the work of constructing contract number 202057115, as set forth in detail in the contract documents for the City and County of Denver.

With a contract time of 120 calendar days, the project must be complete on or before _____.

If you have not already done so, you must submit your construction schedule, in accordance with General Contract Condition 306.2.B, to the Project Manager within 10 days. Additionally, you must submit your tax-exempt certificate, and copies of your subcontractors' certificates, in accordance with General Contract Condition 323.5, to the Project Manager as soon as possible. Failure to submit these certificates will delay processing of payment applications.

Sincerely,

By: _____
Lesley B. Thomas
City Engineer

cc:

City and County of Denver Department of Transportation & Infrastructure
201 West Colfax Avenue, Dept 608 | Denver, CO 80202
www.denvergov.org/doti

311 | POCKETGOV.COM | DENVERGOV.ORG | DENVER 8 TV



Certificate of Contract Release
202057115 - 2021 Citywide Chip Seal and Crack Seal

Current Date
Name
Street Address
City, State, Zip

Upon receipt of the below stated amount from the City and County of Denver, as full and final payment of the cost of the improvements provided for in the foregoing contract, _____ dollars and _____ cents (\$ _____), in cash, being the remainder of the full amount accruing to the undersigned by virtue of said contract; said cash also covering and including full payment for the cost of all work, extra work and material furnished by the undersigned in the construction of said improvements, and all incidentals thereto, and the undersigned hereby releases said City and County of Denver from any and all claims or demands whatsoever, regardless of how denominated, growing out of said contract.

The Undersigned further certifies that each of the undersigned's subcontractors and suppliers that incurred or caused to be incurred, on their behalf, costs, charges or expenses in connection with the undersigned's Work effort on the above referenced Project have been duly paid in full. The undersigned further agrees to defend, indemnify and save and hold harmless the City, its officers, employees, agents and assigns and the above-referenced Contractor from and against all costs, losses, damages, causes of action, judgments under the subcontract and expenses arising out of or in connection with any claim or claims against the City or the Contractor which arise out of the Undersigned's performance of the Work effort and which may be asserted by the Undersigned or any of its suppliers or subcontractors of any tier or any of their representatives, officers, agents, or employees.

And these presents are to certify that all persons performing work upon or furnishing materials for said improvements under the foregoing contract have been paid in full and this payment to be made as described herein is the last or final payment.

Contractor's Signature

Date Signed

If there are any questions, please contact me by telephone at (###) ###-####. Please return this document to me via email at pw.procurement@denvergov.org.

Sincerely,

Contract Administration

City and County of Denver Department of Transportation & Infrastructure
201 West Colfax Avenue, Dept 608 | Denver, CO 80202
www.denvergov.org/doti

311 | POCKETGOV.COM | DENVERGOV.ORG | DENVER 8 TV

CITY AND COUNTY OF DENVER

STATE OF COLORADO



DENVER
THE MILE HIGH CITY

**DEPARTMENT OF TRANSPORTATION &
INFRASTRUCTURE**

Prevailing Wage Rates

Contract Number: 202057115

2021 Citywide Chip Seal and Crack Seal

December 16, 2020



TO: All Users of the City and County of Denver Prevailing Wage Schedules
FROM: Ryland Feno, Classification & Compensation Technician II
DATE: January 06, 2020
SUBJECT: Latest Change to Prevailing Wage Schedules

Please be advised prevailing wage rates for some building, heavy, highway, and residential construction trades have not been updated by the United States Department of Labor (DOL) since March 1, 2002. The Career Service Board, in their meeting held on April 21, 2011, approved the use of the attached supplemental wage rates until prevailing wage rates for these classifications of work are again published by the United States Department of Labor in accordance with the Davis-Bacon Act.

The effective date for this publication will be **Friday, January 03, 2020** and applies to the City and County of Denver for **HIGHWAY CONSTRUCTION PROJECTS** in accordance with the Denver Revised Municipal Code, Section 20-76(c).

General Wage Decision No. CO20200009
Superseded General Decision No. CO20190009
Modification No. 0
Publication Date: 01/03/2020
(6 pages)

Unless otherwise specified in this document, apprentices shall be permitted only if they are employed pursuant to and individually registered in a bona fide apprenticeship program registered with the U.S. Department of Labor (DOL). The employer and the individual apprentice must be registered in a program which has received prior approval by the DOL. Any employer who employs an apprentice and is found to be in violation of this provision shall be required to pay said apprentice the full journeyman scale.

Attachments as listed above.

***Career Service Board approved to adjust all Davis Bacon classifications under \$13.00 to comply with the city's minimum wage. The effective date is August 15, 2019. See page 7 for reference.**

Office of Human Resources
201 W. Colfax Ave. Dept. 412 | Denver, CO 80202
p: 720.913.5751 | f: 720.913.5720
www.denvergov.org/humanresources

TRAFFIC SIGNALIZATION:

Traffic Signal Installation

| | | |
|-------------|----------|------------|
| Zone 1..... | \$ 26.42 | 4.75%+8.68 |
| Zone 2..... | \$ 29.42 | 4.75%+8.68 |

TRAFFIC SIGNAL INSTALLER ZONE DEFINITIONS

Zone 1 shall be a 35 mile radius, measured from the following addresses in each of the following cities:

- Colorado Springs - Nevada & Bijou
- Denver - Ellsworth Avenue & Broadway
- Ft. Collins - Prospect & College
- Grand Junction - 12th & North Avenue
- Pueblo - I-25 & Highway 50

All work outside of these areas shall be paid Zone 2 rates.

 ENGI0009-008 05/01/2018

| | Rates | Fringes |
|---|----------|---------|
| POWER EQUIPMENT OPERATOR: | | |
| (3)-Hydraulic Backhoe (Wheel Mounted, under 3/4 yds), Hydraulic Backhoe (Backhoe/Loader combination), Drill Rig Caisson (smaller than Watson 2500 and similar), Loader (up to and including 6 cu. yd.)..... | \$ 28.25 | 10.70 |
| (3)-Loader (under 6 cu. yd.) Denver County..... | \$ 28.25 | 10.70 |
| (3)-Motor Grader (blade- rough) Douglas County..... | \$ 28.25 | 10.70 |
| (4)-Crane (50 tons and under), Scraper (single bowl, under 40 cu. yd)..... | \$ 28.40 | 10.70 |
| (4)-Loader (over 6 cu. yd) Denver County..... | \$ 28.40 | 10.70 |
| (5)-Drill Rig Caisson (Watson 2500 similar or larger), Crane (51-90 tons), Scraper (40 cu.yd and over),..... | \$ 28.57 | 10.70 |
| (5)-Motor Grader (blade- finish) Douglas County..... | \$ 28.57 | 10.70 |
| (6)-Crane (91-140 tons)..... | \$ 29.55 | 10.70 |

SUCO2011-004 09/15/2011

| | Rates | Fringes |
|--|----------|---------|
| CARPENTER (Excludes Form Work)... | \$ 19.27 | 5.08 |
| CEMENT MASON/CONCRETE FINISHER | | |
| Denver..... | \$ 20.18 | 5.75 |
| Douglas..... | \$ 18.75 | 3.00 |
| ELECTRICIAN (Excludes Traffic Signal Installation)..... | \$ 35.13 | 6.83 |
| FENCE ERECTOR (Excludes Link/Cyclone Fence Erection)..... | \$ 13.02 | 3.20 |
| GUARDRAIL INSTALLER..... | \$ 12.89 | 3.20 |
| HIGHWAY/PARKING LOT STRIPING:Painter | | |
| Denver..... | \$ 12.62 | 3.21 |
| Douglas..... | \$ 13.89 | 3.21 |
| IRONWORKER, REINFORCING (Excludes Guardrail Installation)..... | \$ 16.69 | 5.45 |
| IRONWORKER, STRUCTURAL (Includes Link/Cyclone Fence Erection, Excludes Guardrail Installation)..... | \$ 18.22 | 6.01 |
| LABORER | | |
| Asphalt Raker..... | \$ 16.29 | 4.25 |
| Asphalt Shoveler..... | \$ 21.21 | 4.25 |
| Asphalt Spreader..... | \$ 18.58 | 4.65 |
| Common or General | | |
| Denver..... | \$ 16.76 | 6.77 |
| Douglas..... | \$ 16.29 | 4.25 |
| Concrete Saw (Hand Held).... | \$ 16.29 | 6.14 |
| Landscape and Irrigation.... | \$ 12.26 | 3.16 |
| Mason Tender- Cement/Concrete | | |
| Denver..... | \$ 16.96 | 4.04 |
| Douglas..... | \$ 16.29 | 4.25 |
| Pipelayer | | |
| Denver..... | \$ 13.55 | 2.41 |
| Douglas..... | \$ 16.30 | 2.18 |
| Traffic Control (Flagger)... | \$ 9.55 | 3.05 |
| Traffic Control (Sets Up/Moves Barrels, Cones, | | |

| | | |
|---|----------|------|
| Install Signs, Arrow Boards and Place Stationary Flags) (Excludes Flaggers)..... | \$ 12.43 | 3.22 |
| PAINTER (Spray Only)..... | \$ 16.99 | 2.87 |
| POWER EQUIPMENT OPERATOR: | | |
| Asphalt Laydown | | |
| Denver..... | \$ 22.67 | 8.72 |
| Douglas..... | \$ 23.67 | 8.47 |
| Asphalt Paver | | |
| Denver..... | \$ 24.97 | 6.13 |
| Douglas..... | \$ 25.44 | 3.50 |
| Asphalt Roller | | |
| Denver..... | \$ 23.13 | 7.55 |
| Douglas..... | \$ 23.63 | 6.43 |
| Asphalt Spreader..... | \$ 22.67 | 8.72 |
| Backhoe/Trackhoe | | |
| Douglas..... | \$ 23.82 | 6.00 |
| Bobcat/Skid Loader..... | \$ 15.37 | 4.28 |
| Boom..... | \$ 22.67 | 8.72 |
| Broom/Sweeper | | |
| Denver..... | \$ 22.47 | 8.72 |
| Douglas..... | \$ 22.96 | 8.22 |
| Bulldozer..... | \$ 26.90 | 5.59 |
| Concrete Pump..... | \$ 21.60 | 5.21 |
| Drill | | |
| Denver..... | \$ 20.48 | 4.71 |
| Douglas..... | \$ 20.71 | 2.66 |
| Forklift..... | \$ 15.91 | 4.68 |
| Grader/Blade | | |
| Denver..... | \$ 22.67 | 8.72 |
| Guardrail/Post Driver..... | \$ 16.07 | 4.41 |
| Loader (Front End) | | |
| Douglas..... | \$ 21.67 | 8.22 |
| Mechanic | | |
| Denver..... | \$ 22.89 | 8.72 |
| Douglas..... | \$ 23.88 | 8.22 |
| Oiler | | |
| Denver..... | \$ 23.73 | 8.41 |
| Douglas..... | \$ 24.90 | 7.67 |
| Roller/Compactor (Dirt and Grade Compaction) | | |
| Denver..... | \$ 20.30 | 5.51 |
| Douglas..... | \$ 22.78 | 4.86 |
| Rotomill..... | \$ 16.22 | 4.41 |
| Screed | | |
| Denver..... | \$ 22.67 | 8.38 |
| Douglas..... | \$ 29.99 | 1.40 |
| Tractor..... | \$ 13.13 | 2.95 |

TRAFFIC SIGNALIZATION:

Groundsman

| | | |
|--------------|----------|------|
| Denver..... | \$ 17.90 | 3.41 |
| Douglas..... | \$ 18.67 | 7.17 |

TRUCK DRIVER

Distributor

| | | |
|--------------|----------|------|
| Denver..... | \$ 17.81 | 5.82 |
| Douglas..... | \$ 16.98 | 5.27 |

Dump Truck

| | | |
|--------------|----------|------|
| Denver..... | \$ 15.27 | 5.27 |
| Douglas..... | \$ 16.39 | 5.27 |

Lowboy Truck.....

| | |
|----------|------|
| \$ 17.25 | 5.27 |
|----------|------|

Mechanic.....

| | |
|----------|------|
| \$ 26.48 | 3.50 |
|----------|------|

Multi-Purpose Specialty &

Hoisting Truck

| | | |
|--------------|----------|------|
| Denver..... | \$ 17.49 | 3.17 |
| Douglas..... | \$ 20.05 | 2.88 |

Pickup and Pilot Car

| | | |
|--------------|----------|------|
| Denver..... | \$ 14.24 | 3.77 |
| Douglas..... | \$ 16.43 | 3.68 |

Semi/Trailer Truck.....

| | |
|----------|------|
| \$ 18.39 | 4.13 |
|----------|------|

Truck Mounted Attenuator....

| | |
|----------|------|
| \$ 12.43 | 3.22 |
|----------|------|

Water Truck

| | | |
|--------------|----------|------|
| Denver..... | \$ 26.27 | 5.27 |
| Douglas..... | \$ 19.46 | 2.58 |

WELDERS - Receive rate prescribed for craft performing operation to which welding is incidental.

**Office of Human Resources
Supplemental Rtes
(Specific to the Denver Projects)
Revised 08/21/2019)**

| Classification | | Base | Fringe |
|---|----------------------------------|-------------|---------------|
| Guard Rail Installer | | \$13.00 | \$3.20 |
| Highway Parking Lot Striping: Painter | | \$13.00 | \$3.21 |
| Ironworker (Ornamental) | | \$26.05 | \$12.00 |
| Laborer | Removal of Asbestos | \$21.03 | \$8.55 |
| Laborer (Landscape & Irrigation) | | \$13.00 | \$3.16 |
| Laborer: Traffic Control (Flagger) | | \$13.00 | \$3.05 |
| Laborer: Stationary Flags(excludes Flaggers) | | \$13.00 | \$3.22 |
| Line Construction | Lineman, Gas Fitter/Welder | \$36.88 | \$9.55 |
| | Line Eq Operator/Line Truck Crew | \$25.74 | \$8.09 |
| Millwright | | \$28.00 | \$10.00 |
| Pipefitter | | \$30.45 | \$12.85 |
| Plumber | | \$30.19 | \$13.55 |
| Power Equipment Operator (Tunnels Above and Below Ground, shafts and raises): | Group 1 | \$25.12 | \$10.81 |
| | Group 2 | \$25.47 | \$10.85 |
| | Group 3 | \$25.57 | \$10.86 |
| | Group 4 | \$25.82 | \$10.88 |
| | Group 5 | \$25.97 | \$10.90 |
| | Group 6 | \$26.12 | \$10.91 |
| | Group 7 | \$26.37 | \$10.94 |
| Power Equipment Operator | Group 1 | \$22.97 | \$10.60 |
| | Group 2 | \$23.32 | \$10.63 |
| | Group 3 | \$23.67 | \$10.67 |
| | Group 4 | \$23.82 | \$10.68 |
| | Group 5 | \$23.97 | \$10.70 |
| | Group 6 | \$24.12 | \$10.71 |
| | Group 7 | \$24.88 | \$10.79 |
| Truck Driver | Group 1 | \$18.42 | \$10.00 |
| | Group 2 | \$19.14 | \$10.07 |
| | Group 3 | \$19.48 | \$10.11 |
| | Group 4 | \$20.01 | \$10.16 |
| | Group 5 | \$20.66 | \$10.23 |
| | Group 6 | \$21.46 | \$10.31 |
| Truck Driver: Truck Mounted Attenuator | | \$13.00 | \$3.22 |

Go to <http://www.denvergov.org/Auditor> to view the Prevailing Wage Clarification Document for a list of complete classifications used.

CITY AND COUNTY OF DENVER

STATE OF COLORADO



DENVER
THE MILE HIGH CITY

**DEPARTMENT OF TRANSPORTATION &
INFRASTRUCTURE**

Addenda

Contract Number: 202057115

2021 Citywide Chip Seal and Crack Seal

December 16, 2020

CITY AND COUNTY OF DENVER
DEPARTMENT OF TRANSPORTATION AND INFRASTRUCTURE

CONTRACT NO. 202057115
PROJECT NAME: 2021 CITYWIDE CHIP SEAL AND CRACK SEAL

ADDENDUM NO. 1 TO CONTRACT DOCUMENTS
DATE OF ADDENDUM: JANUARY 8, 2021

Bidders are hereby instructed that the drawings, specifications, and other contract documents are modified, corrected, supplemented and/or superseded for the above-mentioned project as hereinafter described in the following attachments:


ADDITIONAL DOCUMENTS

Please see attached maps, 2021 Draft Work Program.

QUESTIONS/ANSWERS

- Q1. Can we please get some copies of the chip/cape seal 2021 project maps for us to evaluate?
A1. Please see attached provided maps.

This **ADDENDUM** shall be attached to, become a part of, and be returned with the Bid Proposal.



Lesley B. Thomas, City Engineer

January 8, 2021

Date

The undersigned bidder acknowledges receipt of this Addendum. The Proposal submitted herewith is in accordance with the stipulations set forth herein.




Heath Russo, Project Mgr. Contractor

1/8/2021

Date

ADDENDUM NO. 1


2021 Draft Work Program




Legend
2021 Draft Work Program
CCD_Treatment

- Chip Seal
- GO Bond
- HPR
- Mill and Overlay


Baker




East Colfax - Carryover from 2020




Mar Lee




Platt Park




Southmoor Park



Villa Park - Carryover from 2020



Wellshire



CITY AND COUNTY OF DENVER

STATE OF COLORADO



DENVER
THE MILE HIGH CITY

**DEPARTMENT OF TRANSPORTATION &
INFRASTRUCTURE**

Technical Specifications

Contract Number: 202057115

2021 Citywide Chip Seal and Crack Seal

December 16, 2020

**CITY AND COUNTY OF DENVER
DEPARTMENT OF PUBLIC WORKS
Engineering Division**

CONTRACT NO. TBD

2021 Citywide Chip Seal and Crack Seal Program

INDEX TO TECHNICAL SPECIFICATIONS

| <u>Item</u> | <u>Description</u> | <u>Page</u> |
|--------------------------------|---|-------------|
| REVISION OF SECTION 408 | CRACK SEALANT AND HOT POUR MASTIC.. | TS-1 |
| REVISION OF SECTION 409 | CAPE SEAL | TS-3 |
| REVISION OF SECTION 626 | MOBILIZATION | TS-9 |
| REVISION OF SECTION 627 | PAVEMENT MARKING..... | TS-10 |
| REVISION OF SECTIONS 627 & 708 | PAVEMENT MARKING WITH WATERBORNE PAINT..... | TS-11 |
| REVISION OF SECTIONS 627 & 713 | THERMOPLASTIC PAVEMENT MARKING.. | TS-14 |
| REVISION OF SECTIONS 627 & 713 | PREFORMED THERMOPLASTIC PAVEMENT MARKING | TS-14 |
| REVISION OF SECTION 630 | CONSTRUCTION ZONE TRAFFIC CONTROL..... | TS-16 |
| REVISION OF SECTION 702 | BITUMINOUS MATERIALS..... | TS-20 |

Appendix

A. Annotated Revisions Since Last Publication

**REVISION OF SECTION 408
CRACK SEALANT AND HOT POUR MASTIC**

Section 408 of the Standard Specifications is hereby revised for this project as follows:

DESCRIPTION

Subsection **408.01** shall be revised to the following:

This work consists of furnishing and placing an approved hot poured joint and crack sealant and a hot pour mastic material in properly prepared cracks in asphalt pavements. Cracks with a width greater than $\frac{1}{8}$ inch and less than 1 inch are to be filled with crack sealant material. Cracks greater than 1 inch are to be filled with hot pour mastic material. Crack sealing and mastic shall precede cape seal operations in locations specified by the project manager. Additional crack seal work shall be completed at locations to be specified by the project manager following the completion of capeseal operations. All work to be completed shall be directed by the Project Manager.

MATERIALS

Subsection **408.02** shall be revised to the following:

Materials for hot poured joint and crack sealant shall meet the requirements of subsection 702.06.

Using a mixture of different manufacturers' brands or different types of sealant is prohibited.

Material specifications for hot poured mastic shall be provided to project manager for approval prior to commencing work.

CONSTRUCTION REQUIREMENTS

Subsection **408.03** shall be revised to add the following:

Traffic Controls: Place appropriate traffic controls in accordance with part 6, Temporary Controls, of the FHWA Manual on Uniform Traffic Control Devices for Streets and Highways (MUTCD) to protect the work site for the duration of the repairs.

Crackseal and mastic material is only to be applied to clean, sound, dry surfaces. All areas must be clean from dust, dirt, grease, debris, loose materials and any other matter that will inhibit the bonding of the repair compound. Do not apply on wet or frosted surfaces. All areas to be repaired shall be blown with clean, dry, oil free compressed air at 90 psi (620 kpa) minimum. If compressed air does not sufficiently remove all debris or dust coatings, additional cleaning procedures such as sweeping with a stiff or wire bristle broom, sandblasting or routing are recommended.

The minimum pavement temperature for installation of mastic is 40° F (4° C).

Mastic shall be heated in a thermostatically controlled mastic mixer that utilizes oil as a heat transfer medium and has a full sweep horizontal agitator capable of gently lifting the material from the bottom of the reservoir and turning the material over and over. The agitation shall be capable of mixing and suspending materials, filled with aggregates having a specific gravity as

high as 3.0. The heated repair mastic material at the recommended application temperature shall be dispensed onto the properly prepared repair area.

Immediately following application to the pavement surface, mastic shall be leveled and smoothed to the desired level using a straight metal squeegee. If necessary for deep installations, to limit settling and to produce a level finished surface, mastic shall be applied in layers with a cooling and solidifying time period between applications. Minimum installed thickness is 3/8 in (1 cm). The finished installation should be applied smooth and level with the pavement surface.

For installations deeper than 2.5 in (6.3 cm), product should be installed in layers not exceeding 2.5 in thick (6.3 cm) with cooling to 200°F (93°C) maximum before applying the next layer. Installations over 2 in (5cm) deep can be bulked by adding up to 25% by volume of an approved, clean, dry 3/4 inch aggregate in layers for increased stability and quicker cooling.

After application, time must be given for the product to cool before opening the area to traffic. Cooling time will vary depending on the size of the application and ambient temperature. Generally allow approximately 30 to 60 minutes of cooling for each 1 in (2.5 cm) of material depth.

METHOD OF MEASUREMENT

Subsection **408.04** shall be revised to add the following

Hot poured joint and crack sealant will be measured by the ton of material used. Hot poured mastic will be measured by the pound of material used. The project manager may require the weighing of equipment and/or materials for determination of actual quantities of material used. Measurement will be made by weigh tickets before and after placement of each truck load to acquire a net weight of material placed. This net weight will be measured and paid by the weight of material required to seal cracks, complete in place, as accepted by the Project Manager.

BASIS OF PAYMENT

Subsection **408.05** shall be revised to the following:

The accepted quantities for crack seal shall be paid for at the contract unit price per ton.
The accepted quantities for mastic shall be paid for at the contract unit price per pound.

Payment will be made under:

| <u>PAY ITEM</u> | <u>PAY UNIT</u> |
|------------------------|------------------------|
| Crack Seal | TON |
| Mastic | LB |

All materials, equipment, associated traffic control, and costs incidental to the preparation of the surface and the application of the hot poured joint and crack sealant and mastic will not be paid for separately, but shall be included in the work.

**REVISION OF SECTION 409
CAPE SEAL**

Section 409 of the Standard Specifications is hereby revised for this project as follows:

Delete Section 409 and replace with the following:

409.1 CAPE SEAL SPECIFICATIONS

409.1.1 DESCRIPTION

The Contractor shall furnish all labor, equipment, material, supplies, signage, traffic control, and other incidentals necessary to provide an application of polymerized Chip Seal followed by a polymerized Slurry Seal to an existing roadway surface. This two-step process is called Cape Seal.

409.1.2 MATERIALS

Bituminous Materials: Material specifications for Bituminous Materials are contained in Section 702. Section 702.1 provides specifications for the Polymer Modified Emulsion for the Chip Seal. Section 702.2 provides specifications for the Cationic Quick Setting Emulsified Asphalt for the Slurry Seal.

Aggregate: The cover coat and Slurry aggregate shall be washed, hard, durable, clean rock and free from coatings or deleterious material. All of the aggregate shall be crushed gray granite with 100% fractured faces. The aggregate shall have maximum loss of 20% when tested with the LA Abrasion procedure as defined by AASHTO T96 using grade C or D. The maximum amount of flat and elongated aggregate with a ratio of 3:1 shall not exceed 12% as determined by ASTM D4791. Only one source of aggregate shall be used and shall conform to the following gradations.

Gradation Table - Cover Coat Aggregate (percent passing)

| Sieve Size | 3/8" Chip | 1/4" Chip |
|------------|-----------|-----------|
| 5/8" | 100 | 100 |
| 1/2" | 100 | 100 |
| 3/8" | 95-100 | 100 |
| 1/4" | 0-35 | 95-100 |
| No. 8 | 0-3 | 0-3 |
| No. 200 | 0-1.5 | 0-1.5 |

Gradation Table – Slurry Aggregate (percent passing)

| Sieve Size / (Tolerance) | Type I % Passing | Type II % Passing |
|--------------------------|------------------|-------------------|
| No. 4 (+/- 5%) | 100 | 90-100 |
| No. 8 (+/- 5%) | 90-100 | 65-90 |
| No. 16 (+/- 5%) | 65-90 | 45-70 |
| No. 30 (+/- 5%) | 40-65 | 30-50 |
| No. 50 (+/-4%) | 25-42 | 18-36 |
| No. 100 (+/-3%) | 15-30 | 10-24 |
| No. 200 (+/- 2%) | 10-20 | 5-15 |

Cape Seal Material Application Table

| Material | 3/8" Cape Seal | 1/4" Cape Seal |
|----------------------|--------------------|--------------------|
| CRS-2P Chip Seal | 0.32 – 0.40 Gal/SY | 0.28 – 0.34 Gal/SY |
| Cover Coat Aggregate | 22 lbs/SY Minimum | 20 lbs/SY Minimum |
| Slurry Mixture | 20 lbs/SY Minimum | 18 lbs/SY Minimum |

The specific size of aggregate used shall be determined using factors such as surface temperature, traffic volume, existing road condition, and time of year. The Contractor may alter the application rate at any time during the course of the construction upon approval by the Project Manager.

Water: All water used in making the Slurry shall be potable. The effect of moisture content on the specific weight of the aggregate, and the moisture content of the aggregate being used, shall be taken into account in calibrating the machine to deliver asphalt in the correct proportion.

Mixture Design: Before work begins the Contractor shall submit a mixture design for the Slurry Seal, covering the specified materials to be used on this project. This design shall be prepared by the emulsion supplier with a laboratory qualified in Slurry Seal mixture design and testing. Once the materials are selected, no substitution will be permitted unless first tested and approved by the laboratory preparing the mixture design and the City project manager.

409.1.3 CONSTRUCTION REQUIREMENTS

Equipment: The size and condition of all equipment shall be approved prior to construction. Should equipment be unsatisfactory for whatever cause, the Contractor shall remove and replace the equipment without delay or cost. The equipment shall conform to the following minimum requirements.

Bituminous Distributor: A minimum of two like distributors shall be used on this project. The distributors shall be self-powered and capable of providing a uniform application rate of emulsion varying from .05-1.00 gallons per square yard over a variable width up to twenty feet in a single pass. The uniformity of the distributors shall not vary by more the two-hundredths gallons per square yard. The distributors shall be equipped with a variable power unit for the pump and full circulation spray bars, which are adjustable laterally and vertically. The nozzle angle and bar height shall be set to provide one hundred percent of double coverage in a single pass. Where multiple passes will be required to complete the full width, the four inches adjacent to the second pass may be left with fifty percent coverage so that the next pass will complete the full application rate specified. Distributors shall be self-powered and include a computerized application controls, a tachometer, pressure gauges, accurate volume devices, calibrated tank, and a thermometer for measuring temperatures of the emulsion in the tank.

Aggregate Spreader: The aggregate spreader shall be self-propelled and supported by at least four tires on two axles capable of providing a uniform application rate of aggregate from five to fifty pounds per square yard over a variable width up to twenty feet in a single pass. The uniformity of this machine shall not vary by more than one pound per square yard. The aggregate spreader shall be equipped with the means of applying the cover coat material to the surface with computerized application controls so that the required amount of material will be deposited uniformly over the full width of the bituminous material. A computer rate controlled aggregate spreader shall be required.

Rollers: A minimum of two self-propelled pneumatic tired rollers shall be used on the project unless otherwise requested by the Project Manager. The rubber tired rollers shall have a gross load adjustable to apply 200 – 250 pounds per inch of rolling width. Tire pressure shall be specified for the pneumatic tire rollers and shall not vary more than plus or minus 5.0 psi. The smooth drum roller shall be a single drum roller with a loaded rate of five tons. Depending on the speed of the Chip Seal operation and the width of coverage, additional rollers may be required. At no time shall the rollers travel more than five miles per hour.

A coverage shall be the number of passes required to cover the entire surface from side to side. Each pass shall overlap the previous pass by approximately one-half (1/2) the width of the front wheel or roll. The first rolling of the aggregate shall be completed before the emulsion “breaks”. The second rolling shall be performed as soon as possible after the first rolling. The third rolling shall pay special attention to areas that are not in the main travel

areas (shoulders, parking areas, etc.). Additional rolling may be required in these areas as directed by the Engineer and will be considered incidental to the Work. All rolling shall be done at low speed (not to exceed 5 mph).

Mixing Slurry Machine: The Slurry course shall be mixed in a self-propelled mixing machine equipped with a continuous flow pug mill capable of accurately delivering and automatically proportioning the aggregate, emulsified asphalt, water and admixtures to a double shafted, multi-blade pugmill mixer capable of minimum speeds of 200 revolutions per minute.

A minimum of two mixing machines, of 12 cubic yards or larger shall be utilized on the project. The Slurry course retention time in the pugmill shall be less than three seconds. The mixing machine shall have sufficient storage capacity of aggregate, emulsified asphalt, and water to maintain an adequate supply to the proportioning controls.

The mixing machine shall be equipped with hydraulic controls for proportioning the material by volume to the mixture. Each material control device shall be calibrated, properly marked, preset. The mixing machine shall be equipped with a water pressure system and nozzle type spray bars to provide water spray immediately ahead of the spreader box. The mixing machine shall be equipped with an approved fines feeder that provides a uniform, positive, accurately metered, pre-determined amount of a mineral filler at the same time and location that the aggregate is fed.

The Slurry mixture shall be uniformly spread by means of a controlled spreader box capable of spreading a traffic lane width and shall have strips of flexible rubber belting or similar material on each side of the box. The rear flexible strike-off blade shall make close contact with the pavement and shall be capable of being adjusted to the various crown shapes so as to apply a uniform layer of material. Slurry mixture, to be spread in areas inaccessible to the controlled spreader box, may be spread by other approved methods.

Each mixing unit to be used in performance of the Slurry work shall be calibrated prior to construction at a minimum of once per year. Calibration documentation covering the exact materials to be used may be acceptable, provided they were made during the calendar year. The documentation shall include an individual calibration of each material at various settings, which can be related to the machine's metering devices. No machine will be allowed to work on the project until the calibration has been completed and accepted.

Sweepers: A minimum of two vacuum designed sweepers having only negative air pressure at the road surface capable of removing excess aggregate and debris material shall be used on this project. The body hoppers of the vacuum sweepers shall be a minimum capacity of ten cubic yards, and the negative air pressure at the intake shall be rated at forty six inches of negative water pressure. Sweepers shall meet applicable U.S. Environmental Protection Agency Standards. No mechanical pick-up brooms will be allowed on the project.

409.1.4 EXECUTION OF THE WORK

Surface Preparation: The Contractor shall be responsible for all measures necessary to provide a thoroughly clean and dry pavement surface including vegetation removal, and sweeping prior to the Chip Seal application. The Contractor shall observe the condition of the pavement prior to bidding to determine the work necessary to provide a clean, dry pavement for construction and shall include the work necessary in the bid. Immediately prior to applying the Chip Seal, the surface shall be cleared of all loose material, oil spots, vegetation and other objectionable material. Manholes, valve boxes, drop inlets and other service entrances shall be protected from the Chip Seal by a suitable method. The Project Manager shall approve the surface preparation prior to surfacing.

Application of Bituminous Material (Chip Seal): The application of the emulsion shall be performed by means of a pressure distributor in a manner to achieve a uniform and continuous spread over the asphalt surface. The temperature of the emulsion shall be a minimum of 160°F. The quantity of emulsion per square yard shall be as specified herein and agreed upon with the project manager. The distributor shall be moving forward at proper application speed at the time the spray bar is opened. If at any time a nozzle becomes clogged or not spraying a proper pattern, the operation shall be immediately halted until repairs are made. Repairs shall be made immediately after deficiencies are noted and prior to the aggregate spreader at all times during construction. The width of the spread shall be no greater than the width of the aggregate spreader except where additional passes are required the emulsion shall be four inches beyond the aggregate spread at fifty percent application rate. At no time shall the emulsion be allowed to break, chill, set up, harden, or otherwise impair the aggregate retention before the aggregate has been properly applied and rolled

Application of Cover Coat Aggregate (Chip Seal): The aggregate shall be applied immediately following the emulsion application by the approved aggregate spreader. The quantity of cover coat aggregate per square yard shall be specified herein and agreed upon with the Project Manager. The Contractor, prior to start of work, shall calibrate the aggregate spreader to achieve the design application rate of the cover coat aggregate. Spreading shall be accomplished in such a manner that the tires of the trucks and aggregate spreader never contact the newly applied bituminous material. The width of the aggregate spreader shall be equal to the width of the emulsion spread, except where additional passes are required. Areas, which are deficient in aggregate, shall be covered immediately with additional material.

Rolling (Chip Seal): Initial rolling shall begin immediately after the application of cover coat aggregate. Rollers shall work in tandem and complete a minimum of three passes with a sufficient overlap. Should the rolling operation be delayed, the aggregate and emulsion spreading shall be halted until the operation regains proper sequencing and timing. The maximum speed of the rolling operations shall be five miles per hour.

Sweeping (Chip Seal): Within 24 hours of Slurry application, excess aggregate shall be swept and removed from the roadway and adjacent areas (including gutters, sidewalks, driveway and alley aprons) with the specified sweepers.

Application of Material (Slurry): Within 5 working days of the Chip Seal application the Slurry course will be applied. The materials and installation of slurry seal shall be price reduced for failure to install within 5 working days of the Chip Seal application.

| | > 5 days < 10 days | ≥ 10 days and < 15 days after | ≥ 15 days and < 20 days after | ≥ 20 days |
|-------------------|--------------------|-------------------------------|-------------------------------|-----------|
| % Price Reduction | 10% | 20% | 35% | 50% |

The surface shall be fogged with water directly preceding the spreader. The Slurry mixtures shall be of the desired consistency, based on the submitted mixture design, as it leaves the mixer with additional approved additive if required. A sufficient amount of Slurry shall be carried in all parts of the spreader at all times so that complete coverage is obtained.

No lumping, balling, or unmixed aggregates shall be permitted. No segregation of the emulsion and aggregate fines from the coarse aggregate will be permitted. No excessive breaking of the emulsion will be allowed in the spreader box. Rippling of the finished pavement is undesirable and shall be minimized.

No excessive build-up or unsightly appearance shall be permitted on longitudinal or transverse joints. The use of burlap drags or other type drags shall be used so that joints will be straight and have a neat appearance. Squeegees shall be used to spread Slurry in areas not accessible to the Slurry mixer. Care shall be exercised as to leave a good appearance. Care shall be taken to insure straight lines along curbs, shoulders and joints. Lines at intersections will be kept straight to provide a good appearance.

Slurry treated areas shall be allowed to cure until such time as traffic will not damage the finished product. Contractor will be responsible for monitoring roadways treated to insure sufficient cure time is allowed before allowing traffic over the treated areas.

Manholes, Valves and Inlets: Manholes, valve boxes, and inlets shall be covered and or protected with an approved material during the operation and shall be removed immediately after the street has been Cape Sealed. The Contractor is responsible for locating all exposed manholes, valve boxes, and inlets prior to construction.

Weather Limitations: The Chip Seal shall not be applied when the pavement is moist, or when the weather is or is predicted to be detrimental. Detrimental weather is defined as rain showers, cool temperatures, moist pavements, threat of rain showers, or other environmental factors which could affect the performance of the Chip Seal construction. If either the pavement or air temperature is below 55°F (10°C) and falling, the weather is considered detrimental and Chip Seal operations will cease immediately. When both pavement and air temperatures are above 50°F (7°C) and rising, temperature conditions are acceptable for Chip Seal operations. If the project manager, in his/her sole discretion, determines that the weather is predicted to be detrimental then all Chip seal operations must cease until the weather conditions improve and the project manager approves continuing the work.

The Slurry Seal shall not be applied if either the pavement or air temperature is below 50°F (10°C) and falling, but may be applied when both pavement and air temperatures are above 45°F (7°C) and rising. No Slurry Seal shall be applied when air temperatures will be below freezing within 24 hours. The mixture shall not be applied when weather conditions prolong opening to traffic beyond a reasonable time. If the project manager, in his/her sole discretion, determines that the weather is or is predicted to be detrimental then all Slurry seal operations must cease until the weather conditions improve and the project manager approves continuing the work.

Traffic Control: A traffic control plan approved by Project Manager will be required before any work commences. Temporary raised pavement markers will be installed as needed, at a minimum of 40' spacing. The cost of signage, markers, pavement marking, and traffic control necessary to complete this project shall NOT be included in the unit price of the Cape Seal, as these items are to be bid separately.

Notification: The Contractor shall distribute an approved information flyer to all residents and businesses adjacent to the project at least one week prior to the anticipated start of construction. A local telephone number will be provided on the flyer and manned 24/7 until the contract is completed. Date specific no-Parking tow-away signs must be in place a minimum of 24-hours in advance of the construction. Should work not occur on the specified day, a new notification will be distributed and date specific no-parking tow-away signs will be posted.

The contractor shall submit a daily e-mail update to the project manager listing the current status of all outstanding work and anticipated time-frame for remaining work.

The cost of notification shall be included in the unit price of the Cape Seal.

Method of Measurement & Payment: The Cape Seal shall be measured and paid for by the square yard sealed and accepted by the owner. Payment shall be full compensation for the

Cape Seal work completed in accordance with the above specifications.

PAY ITEM
Cape Seal (CRS-2P)

PAY UNIT
S.Y.

**REVISION OF SECTION 626
MOBILIZATION**

Section 626 of the Standard Specifications is hereby revised for this project as follows:

Initial mobilization shall not be measured and paid for separately but shall be included in the price of the work. Remobilization is defined as work stoppages in excess of 48 hours; (excluding weekends and holidays) as designated by the Project Manager for the convenience of the City, and shall be measured and paid for separately. Mobilization and Remobilization shall include all labor, materials, and equipment for the distribution of public information flyers and related traffic control preparation for the work.

PAY ITEM
Remobilization

PAY UNIT
EA

**REVISION OF SECTIONS 627
PAVEMENT MARKING**

Section **627** of the Standard Specifications is hereby revised for this project as follows:

Subsection **627.03 (c)** is revised as follows:

Roadways constructed under traffic.

All multi-lane roadways, arterial roadways, and major collectors must be striped at the end of the day with full compliance pavement markings. Paint may be used for temporary markings.

All other roadways must be tabbed at minimum at the end of each day with a minimum of 8” tabs for lane lines and centerline markings.

Layouts for striping shall match existing conditions and roadway striping must be confirmed with Traffic Engineering Services prior to installation of final striping. Existing conditions shall be determined by an on-site inspection.

Final striping must be installed within 5 days from completion of the paving.

Final striping shall be completed with the following materials:

- Cross walks, stop lines and word symbols shall be completed with preformed thermoplastic pavement marking.
- Lane markings shall be completed with extruded thermoplastic pavement markings.
- Preference is to complete edge lines and center lines with extruded thermoplastic pavement markings. However, edge lines and centerlines may use epoxy with the approval of the Project Manager and Traffic Engineering Services.

Subsection 627.13 is revised as follows:

The materials and installation of pavement markings shall be price reduced for failure to install within 10 days upon receipt of written request from Traffic Engineering Services or the Engineer/Project Manager or upon the task order completion deadline.

| | > 10 days and < 30 days after | ≥ 30 days and < 60 days after | ≥ 60 days and < 90 days after | ≥ 90 days |
|-------------------|-------------------------------|-------------------------------|-------------------------------|-----------|
| % Price Reduction | 20 % | 50 % | 70 % | 85 % |

Delete the third paragraph of 627.13 and replace with the following:

Sandblasting will not be measured and paid for separately but shall be included in the work.

**REVISION OF SECTIONS 627 and 708
PAVEMENT MARKING WITH WATERBORNE PAINT**

Sections 627 and 708 of the Standard Specifications are hereby revised for this project as follows:

Delete subsection 627.04 and replace with the following:

627.04 Pavement Marking with Waterborne Base Paint. Striping shall be applied when the air and pavement temperatures are no less than 52 °F for waterborne paint. The pavement surface shall be dry and clean. Surface cleaning shall be required when there is deicing material on the road. Weather conditions shall be conducive to satisfactory results.

The Contractor shall utilize equipment that meets the following requirements, as approved:

- (1) Equipment shall permit traffic to pass safely within the limits of the roadway surface and shoulder while operating.
- (2) Equipment shall be designed for placement of both solid and broken line stripes with a reasonably clean-edged stripe of the width and location as shown on the contract.
- (3) Equipment shall have a glass bead dispenser directly behind, synchronized with the paint applicator. Each applicator shall have individual control and automatic skip control that will paint a strip with a gap as shown in the contract.
- (4) The equipment may be equipped with a heat exchanger to heat the paint to reduce drying time.
- (5) The operation shall include a trailing vehicle equipped with a flashing arrow board.

The Contractor shall prevent traffic from crossing a wet stripe. Stripes which have been marred or picked up by traffic before they have dried shall be repaired at the Contractor's expense. Removal of paint from vehicles that crossed wet paint shall be at the Contractor's expense.

The water-based paint and stripes shall fall within the following minimum and maximum ranges:

| | DESCRIPTION | MINIMUM | MAXIMUM |
|-----------|--------------------------------------|------------------------------------|---------------------|
| Alignment | Lateral Deviation | N/A | 2.0 inch per 200 ft |
| Paint | Coverage rate per gallon of paint | 100 sq. ft | 110 sq. ft |
| | Thickness | 20 mil | N/A |
| | Width of painted lines | 4 inch | N/A |
| | Width Variance | N/A | 1/4 inch |
| | Water-Based Paint | Dry time to no tracking conditions | N/A |
| Beads | Application rate per gallon of paint | 5 lbs 3 oz | 6 lbs 3 oz |

Subsection 627.13 shall include the following:

PAY ITEM
Pavement Marking Paint (Waterborne)

PAY UNIT
Gallon

Delete subsection 708.01 and replace with the following:

708.01 General. This specification covers ready-mix paints and coatings. Paints and coatings shall be manufactured eight weeks or less prior to delivery to the project. Each paint container shall be labeled with the name and address of the manufacturer, trade name or trademark, type of paint, number of gallons, batch number, and date of manufacture.

Paints shall be free of foreign material that is capable of clogging screens, valves, pumps, and other parts of the application equipment. Paint shall not contain the following:

- (1) Benzene
- (2) Chlorinated solvents
- (3) Ethylene glycol ethers
- (4) Ethylene glycol acetates
- (5) Lead
- (6) Mercury
- (7) Chromium
- (8) Cadmium
- (9) Petroleum products

The Contractor shall obtain certification in writing from the manufacturer showing that the product is free of the materials described above and that it meets or exceeds the requirements of 29 CFR 1910.1200.

Paints shall not form a surface skin within 48 hours in three-quarter filled, tightly closed containers. Paint and coating pigments shall be lead free, and shall not thicken, become granular, or curdle in their containers.

Delete subsection 708.05 and replace with the following:

708.05 Pavement Marking Materials. Pavement marking materials shall be selected from the Department's Approved Products List (APL). Prior to start of work, a Certified Test Report (CTR) for all pavement marking materials shall be submitted in accordance with subsection 106.13.

For white paint, the color after drying shall be a flat-white, free from tint, and shall provide the maximum amount of opacity and visibility under both daylight and artificial light. For yellow paint, the Federal Standard 595B shall be used to designate colors and the ASTM E308 shall be used to quantitatively define colors. After drying, the yellow paint shall visually match Federal Standard 595B color chip number 33538, and shall be within 6 percent of central color, PR-1 Chart, where $x = 0.5007$ and $y = 0.4555$ (The four pairs of chromaticity coordinates determine the acceptable color in terms of the CIE 1931 Standard Colorimetric System measured with Standard Illuminant D65.)

- (a) *Acrylic Waterborne Paint.* Acrylic waterborne paint shall be a lead-free, 100 percent Acrylic resin polymer waterborne product. The finished product shall maintain its consistency during application at temperatures compatible with conventional equipment.

Waterborne paint shall meet all of the following requirements:

Performance Requirements: The paint shall be water resistant and shall show no softening, blistering or loss in gloss.

ACRYLIC WATERBORNE PAINT

| Property | Minimum | Maximum | Test Method |
|--|--|-------------------------|---|
| Nonvolatile portion of vehicle (white and yellow), % | 42.5 | | |
| Pigment Composition | | | |
| (white and yellow), % by weight | 58.0 | 62.0 | ASTM D 4451 ASTM D 3723 |
| White Paint | | | |
| Titanium Dioxide | | 10.0%; 1.0 lb/gal | ASTM D 476, Type III |
| Calcium Carbonate, % | | 92.0 | ASTM D 1199, Type GC-II |
| Yellow Paint | | | |
| Titanium Dioxide | | 5.0%; 0.2 lb/gal | ASTM D 476, Type III |
| Calcium Carbonate | | 93.0 | ASTM D 1199, Type GC-II |
| Organic Yellow Pigments, % | 5.0 | | |
| Yellow Iron Oxide | | 0.063%; 0.025 lb/gal | ASTM D 768 |
| Vehicle Composition , 100% acrylic polymers, (white and yellow), % | | 43.0 | FTMS 141C - Method 4031 or Method 4053.1 |
| Properties of the Finished Paint | | | |
| Total Non-volatiles, (solids) % by weight | | | |
| White Paint, % | 77.0 | | FTMS 141C - Method 4053.1, |
| Yellow Paint, % | 76.0 | | ASTM D 2369, or ASTM D 4758 |
| Density, lbs/gal ¹ | | | |
| White and Yellow Paint | 14.0 | | ASTM D 1475 using U.S. Standard weight per gallon cup as defined in U.S. Military Standard 4566A |
| Consistency (Viscosity) White and Yellow, Krebs- Stormer Units | 85 | 95 | ASTM D 562 |
| Freeze Thaw Stability | Shall complete 5 or more test cycles successfully | | ASTM D 2243 |
| | 3 | | ASTM D 1210 |
| Hydrogen ion content: pH | 9.6 | | ASTM E 70 |
| Directional Reflectance: [15 mil Wet Film] | | | ASTM E 1347 |
| White, dried | 85 | | |
| Yellow, dried | 50 | | |
| Dry Opacity (Contrast Ratio): [15 mil Wet Film] | | | ASTM D 2805 |
| White Paint | 0.95 | | |
| Yellow Paint | 0.88 | | |

¹Density shall not vary more than 0.3 lbs/gal between batches

**REVISION OF SECTIONS 627 and 713
THERMOPLASTIC PAVEMENT MARKING
(Extruded Thermoplastic Pavement Marking for Lane Markings, Edge Lines and Center Lines)**

Specifications for Extruded Thermoplastic Pavement Marking as specified in Sections 627.06 and 713.12 are specified without revision for lane markings and edge lines.

**REVISION OF SECTIONS 627 and 713
PREFORMED THERMOPLASTIC PAVEMENT MARKING
(for Cross walks, Stop lines and Word Symbols)**

Sections 627 and 708 of the Standard Specifications are hereby revised for this project as follows:

SECTION 627.09 Preformed Thermoplastic Pavement Marking. The markings shall consist of a resilient white or yellow thermoplastic product with glass beads uniformly distributed throughout the entire cross sectional area. Legends and symbols shall be capable of being affixed to bituminous pavements by heating.

The markings shall conform to pavement contours, breaks and faults through the action of traffic at normal pavement temperatures. The material shall have resealing characteristics with the capability of fusing with itself and previously applied thermoplastic markings under normal use.

The preformed thermoplastic markings shall be packaged in a protective plastic film with cardboard stiffeners where necessary to prevent damage in transit. The carton in which the material is packed shall be clearly labeled for ease of identification.

- (a) *Application.* Application temperature shall be as recommended by the manufacturer. The pavement and air temperature shall be as recommended by the manufacturer at the time of application. The material shall be applied using a heating method recommended by the manufacturer. The contractor shall provide the Engineer a copy of the manufacturer's installation recommendations prior to beginning work. The pavement shall be clean dry and free from debris. The preformed thermoplastic markings may be installed on top of existing thermoplastic markings after all loose material has been removed. The preformed thermoplastic markings shall not be installed on top of existing preformed plastic pavement markings without first removing the existing markings to a depth that insures removal of the adhesive backing of the preformed plastic. It shall not be installed on top of pavement marking paint without first removing paint.
- (b) *Equipment.* The Contractor shall use a heating method specifically recommended by the manufacturer for the installation of preformed thermoplastic markings.

SECTION 713.14 Preformed Thermoplastic Material

- (a) *General.* Preformed thermoplastic markings shall be composed of aggregates, pigments, binders and Glass beads, and shall conform to AASHTO designation M 249 with the exception of the relevant differences due to the fact that the material is supplied in a preformed state. The material shall be either alkyd or hydrocarbon based. Only preformed thermoplastic pavement markings material listed on the Departments approved products list may be used.
- (b) *Physical Requirements.*

1. Graded Glass Beads. The material shall contain a minimum of 30 percent graded glass beads by weight. The beads shall be clear and transparent. Twenty percent or less shall consist of irregular, fused spheroids, or silica. The refractive index shall be at least 1.50.
2. Pigments. White – Sufficient titanium dioxide pigment shall be used to insure a color similar to Federal Highway White, Color Number 17886, conforming to Federal Standard 595. Yellow – Sufficient yellow pigment shall be used to insure a color similar to Federal Highway Yellow, Color Number 13655, conforming to Federal Standard 595. The yellow pigment shall be organic and contain no lead chromate.
3. Skid Resistance. The surface of the preformed thermoplastic markings shall provide a minimum resistance value of 45 BPN when tested according to ASTM E 303.
4. Thickness. The material shall be supplied at a minimum thickness of 90 mils.
5. Environmental Resistance. The preformed thermoplastic material shall be resistant to deterioration due to exposure to sunlight, water, oil, gasoline, salt and adverse weather conditions.
6. Application. The top surface material must have regularly-spaced indents which provide a visual cue during application that the material has reached a molten state indicating satisfactory adhesion and proper bead embedment has been achieved. Installation must be a no preheated of surface material.

Subsection 627.13 shall include the following:

Payment shall be made under:

| <u>PAY ITEM</u> | <u>PAY UNIT</u> |
|---|-----------------|
| Pavement Marking Paint (Waterborne) | Gallon |
| Thermoplastic Pavement Marking (Lane Markings) | Square Foot |
| Epoxy Pavement Marking (Lane Marking Alternative) | Gallon |
| Preformed Thermoplastic Pavement Marking (Word – Symbol) | Square Foot |
| Preformed Thermoplastic Pavement Marking (X-Walk, Stop Line) | Square Foot |

**REVISION OF SECTION 630
CONSTRUCTION ZONE TRAFFIC CONTROL**

Section 630 of the Standard Specifications is hereby revised as follows:

Subsection 630.01 shall be modified to read:

As required by, in descending order of precedence, the specifications, Traffic Barricade Manual published by the City and County of Denver, the Standard Specifications, as augmented by the Colorado Department of Transportation M and/or S standards, and the manual on Uniform Traffic Control Devices for Streets and Highways.

The Contractor shall submit, in writing, the proposed Method of Handling Traffic (MHT) for review and approval of the Project Engineer. The MHT shall be developed according to this section and the construction plans.

Subsection 630.02 through 630.07 shall be as provided in the City and County of Denver Traffic Barricade manual, latest edition. Modifications to said manual are:

Paragraph III shall include:

Traffic Control. Traffic control through the construction area is the responsibility of the Contractor. Before starting construction the Contractor shall submit, in writing, the proposed Method of Handling Traffic (MHT) for the initial phase of construction. When a different MHT is required for a subsequent construction phase, it must be submitted two weeks prior to starting that phase. All proposed methods of handling traffic shall be approved, in writing, by the Engineer. No phase of construction shall start until an acceptable MHT has been received and approved by the Engineer. The proposed methods shall include, as a minimum, the following:

A detailed diagram which shows the location of all sign placements, including advance construction signs (if not previously approved) and speed limit signs; method, length and time duration for lane closures; and location of flag persons.

Certain traffic control devices may be used for more than one operation or phase.

Approval of the proposed MHT does not relieve the Contractor of liability specifically assigned to him under the contract. The Contractor shall erect and maintain warning lights, signs, barricades, and sufficient safeguards around all excavations, embankments, and obstructions.

The contractor shall notify the project manager by Thursday at 3:00 P.M. which streets they intend to work on the following week. This notification shall be made for all phases of construction.

VI.B.3 therein shall include:

Non-metallic drums or tubular devices may be substituted for vertical panel channelizing devices.

VI.F shall include:

The Contractor shall, at the preconstruction conference, designate one of his employees, other than the Superintendent, to be responsible for traffic control management. This responsibility shall include management of the Contractor's signing and all other details covered by the

Specifications which contribute to the convenience, safety, and orderly movement of traffic and to the comfort of the traveling public. The designated employee shall have the Certification of the Traffic Control Supervisor as a Worksite Traffic Supervisor by the American Traffic Safety Services Association (ATSSA) in lieu of completion of the CDOT minimum training requirements.

Traffic control management shall be maintained on a 24-hour per day basis. The Contractor shall make arrangements so that the Traffic Control Supervisor or his approved representative shall be available on every working day, "on call" at all times and available upon the Engineer's request at other than normal working hours. The Traffic Control Supervisor shall have an up-to-date copy of part VI of the MUTCD, pertaining to traffic controls for street and highway construction, as well as the City and County Traffic Barricade manual, available at all times.

VI.F.2 The third item shall read:

The flagger's STOP/SLOW sign paddle shall be 18 inches with letters six inches high.

Subsection 630.08 shall include the following:

Equipment

The Contractor shall not have construction equipment or materials in the lanes open to traffic any time, unless approved by the Project Engineer.

The Contractor and subcontractors shall equip their construction vehicles with flashing amber lights. Flashing amber lights on vehicles and equipment shall be visible from all directions.

All personal / employee vehicle and construction equipment parking is prohibited when it conflicts with safety, access, or the flow of traffic.

Devices:

The Contractor shall install construction traffic control devices in locations where they do not block or impede other existing traffic control devices, or sidewalks for pedestrians, disabled persons, or bicyclists.

Steel drum channelizing devices shall not be used for traffic control.

Subsection 630.09, second paragraph is hereby deleted and replaced with the following:

When a different MHT is required for a subsequent construction phase, it must be submitted at least two weeks prior to starting that phase. All proposed methods of handling traffic shall be approved, in writing, by the Project Engineer following approval of the Traffic Engineering Services Department.

Approval of the proposed MHT does not relieve the Contractor of liability specifically assigned to him under the contract. The Contractor shall erect and maintain warning lights, signs, barricades, and sufficient safeguards around all excavations, embankments, and obstructions.

The contractor shall notify the Project Engineer by Thursday at 3:00 P.M. which streets they intend to work on the following week. This notification shall be made for all phases of construction.

Subsection 630.09 (4) shall be revised to include the following:

Access to driveways shall be maintained at all times during construction. The Contractor shall coordinate driveway work with the property owner. Appropriate signage shall be provided alerting all motorists leaving driveways that enter a work zone as to which direction the through lane is traveling and what access restrictions exist, if any.

Subsection 630.09 (9) shall be added as follows:

General Work Restrictions

The Contractor shall perform all the work on the roadway between the hours of 8:30 A.M. and 3:30 P.M. or as approved by the Project Engineer. Weekend and nighttime work shall be allowed with the prior approval of the Project Engineer.

Work shall not be permitted that directly or indirectly interferes with the flow of traffic between the hours of 5:30 AM and 8:30 AM Monday through Friday; between the hours of 3:00 PM to 6:30 PM Monday through Thursday; and after 2:00 PM on Fridays unless otherwise authorized by the Project Engineer.

Work that interferes with traffic 1] on any day of a 3 or 4 day holiday weekend; or 2] after 12:00 noon on the day preceding such holiday weekend, shall only be permitted following review of a Contractor submitted request and approval by the Project Engineer and the City of Denver Traffic Engineering Services Department:

The Contractor shall coordinate all of the work on the roadway during any special event with the City and County of Denver.

Two-way traffic shall be maintained on all two-way streets, via flagging if necessary for closures of less than one day unless authorized by the Project Engineer and the Traffic Engineering Services Department. One lane, one-way traffic shall be maintained at all times on one-way streets outside of the Central Business District and two lanes, one-way traffic shall be maintained at all times within the Central Business District.

Contractor shall obtain all required access and construction permits from the City & County of Denver prior to initiating work along City right of way.

The Contractor shall maintain access to all roadways, side streets, walkways, alleyways, driveways, and hike/bike paths at all times unless otherwise approved by the Project Engineer. The sole exception to this requirement is that the City will permit full closures of access to all alleyways, walkways, driveways, and hike/ bike paths DIRECTLY ADJACENT to an active work Phase for a maximum period of one (1) week. Should the Contractor wish to exercise this exception, a request for same shall be submitted to the Project Engineer for review and approval including proposed method for Public notice per Section 632. If access restrictions are approved by the Project Engineer, the Contractor shall coordinate with all tenants affected by alley and/or access closures two weeks prior to closure.

All proposed lane closures shall be subject to the approval of the Project Engineer and Traffic Engineering Services Department. Requests for such lane closures shall be submitted with a Method of Handling Traffic at least 24 hours in advance of the time the lane closure is to be implemented. Lane closures will not be allowed to remain unless utilized in continuum for the duration of each working period. Contractor shall make all efforts to fashion the lane closure proposal to close no more than one lane at a given time.

Prior to any removal or pavement marking operations directly adjacent to parking, temporary NO PARKING ANYTIME, TOW AWAY ZONES, with the date and time of the proposed

work must be posted a minimum of 24 hours in advance of the work. For locations where parking meters are located adjacent to the proposed work zone all impacted parking meters must be red bagged prior to commencement of work.

The Contractor shall be responsible to determine the meter numbers and dates for all proposed work at these locations and will need to provide this information with the street occupancy permit request for the work. This request should be submitted at least 5 days in advance of the proposed start of work. Parking may only be restricted on one side of the street at a time and the length of the restriction should not create a significant impact to the local residents or businesses in the area.

All lane closures require an arrow board to be installed.

Subsections 630.10 and 630.11 of the Standard Specifications shall apply except as otherwise provided herein.

Subsection 630.14 is hereby deleted and replaced with the following:

The Contractor shall furnish all personnel and materials necessary to perform the Construction Zone Traffic Control as required and these quantities shall not be measured.

Temporary pavement markings for traffic control shall not be measured and paid for separately, but shall be included in the work.

Payment for traffic control shall be as follows:

| <u>PAY ITEM</u> | <u>PAY UNIT</u> |
|----------------------------------|-----------------|
| Traffic Control Arterial* | LS/DAY |
| Traffic Control Local/Collector* | LS/DAY |

*The designation of which roads are arterials and which roads are local/collector shall be determined using the classification found on the City's GIS system.

The amount paid per day shall not exceed one unit of Traffic Control for an Arterial and/or one unit of traffic control for Local/Collector.

Subsection 630.15 is hereby deleted and replaced with the following:

Payment for Construction Zone Traffic Control shall include all devices; a Traffic Control Supervisor, Variable Message Signs as specified, arrow boards, detours, addition and/or adjustments to traffic signal heads as needed to support phased construction traffic control, temporary pavement markings, and all other personnel and resources necessary to complete the work. Payment shall be made based on the number of calendar days Construction Zone Traffic Control is in place. A calendar day shall be a minimum of 6 hours unless approved by the Project Engineer.

When the contract bid schedule includes Traffic Control pay items as a lump sum per day: A day shall be defined as the time from 12:00 midnight to 12:00 midnight. Traffic Control devices shall not be measured but will be paid for on a lump sum basis.

**REVISION OF SECTION 702
BITUMINOUS MATERIALS**

Section 702 of the Standard Specifications is hereby revised for this project as follows:

ASPHALT CEMENT

Subsection 702.02 shall be deleted and replaced with the following:

702.1 Polymer Modified Emulsion (Chip Seal): Polymer modified asphalt emulsion (CRS-2P) shall conform to the requirements listed below. The asphalt binder shall be polymer modified before emulsification and shall contain at least 3 percent polymer by weight of asphalt binder. The emulsion shall be pumpable and suitable for application through a distributor truck. The emulsified asphalt shall conform to the following requirements:

CRS-2P

| Test on Emulsion | Minimum | Maximum | Test Method |
|---|----------|---------|-------------|
| Viscosity, Saybolt Furol, 50°C , sec, (a) | 50 | 450 | AASHTO T 59 |
| Storage Stability Test, 24-h,%(a) | | 1 | AASHTO T 59 |
| Demulsibility, 35 ML, 0.8% dioctyl sodium Sulfosuccinate, % | 40 | | AASHTO T 59 |
| Particle Charge Test | Positive | | AASHTO T 59 |
| Sieve Test, %(a) | | 0.1 | AASHTO T 59 |
| Oil Distillate, by Volume of Emulsion, % | | 3 | AASHTO T 59 |
| Residue, % | 65 | | AASHTO T 59 |
| Test on Residue (Colorado DOT CP-L 2212*) (b) | | | |
| Penetration, 25 °C, 100g , 5s, dmm | 70 | 150 | AASHTO T 49 |
| Solubility in Trichloroethylene, % (b) | 97.5 | | AASHTO T 44 |
| Toughness, in-lb | 90 | | CP-L2210* |
| Tenacity, in-lb | 60 | | CP-L2210* |

(a) This test requirement on representative samples is waived if successful application of the material has been achieved in the field.

(b) If the solubility of the residue is less than 97.5%, the base asphalt binder for the emulsion shall be tested. The solubility of the base asphalt binder shall be greater than 99 percent.

* CP-L 2210, CP-L 2211, and CP-L 2212 are Colorado DOT test procedures.

702.2 Cationic Quick Setting Emulsified Asphalt (Slurry Seal): CQS-1hL shall be an emulsified mixture of *straight-run vacuum tower bottoms asphalt*, synthetic SBR polymer dispersion, emulsifiers and water. The emulsion shall contain a minimum of one percent (1.0%) styrene butadiene rubber (SBR) solids by weight of asphalt cement. The SBR polymer dispersion shall be co-milled during the emulsification process such that a bicontinuous polymer-asphalt network is formed upon curing of the finished emulsion. The emulsion shall be pumpable and suitable for use in a Slurry Seal machine. The emulsion, standing undisturbed for 48 hours will show milky white on top as evidence that the emulsion contains SBR polymer dispersion. The emulsified asphalt shall conform to the following requirements:

| Test on Emulsion | Minimum | Maximum | Test Method |
|--|----------------|----------------|--------------------|
| Viscosity, Say bolt Furol, 77 °F,s | 20 | 100 | ASTM D244 |
| Storage Stability Test, 24-h,%(a) | | 1 | ASTM D6930 |
| Particle Charge Test | Positive | | ASTM D244 |
| Sieve Test, %(a) | | 0.1 | ASTM D6933 |
| Distillation: (b) | | | |
| Residue, % | 60 | | ASTM D6997 |
| Polymer: | | | |
| Polymer content, % polymer solids based on asphalt solids | 1.0 | | Supplier Cert. |
| Polymer Type: | SBR Latex | | Supplier Cert. |
| Test on Residue from 325 °F hot plate evaporation test (Colorado DOT CP_L2212*) b | | | |
| Penetration, 77 °F, 100g,5s | 40 | 90 | ASTM D5 |
| Ductility, 77 °F, 5 cm/min,cm | 40 | | ASTM D113 |
| Solubility in Trichloroethylene, % | 97.5 | | ASTM D2042 |
| Elastic Recover, 77 °F, 10cm,1h,% | 40 | | ASTM D5976 |

a) This test requirement on representative samples is waived if successful application of the material has been achieved in the field.

b) Distillation to 260°C (T-59 §11 to 15) shall be the reference method for percent residue.

Residue by hot plate evaporation at 163°C (CP-L2212 modified to a maximum temperature of 325°F) shall be the reference method to obtain material for tests on residue. Residue from distillation shall not be used for tests on residue due to polymer degradation at 260°C. Colorado DOT Procedure CP-L 2212* modified to a 163°C maximum temperature may be used for acceptance testing of percent residue.

c) If the solubility of the residue is less than 97.5%, the base asphalt binder for the emulsion shall be tested. The solubility of the base asphalt binder shall be greater than 99 percent.

* CP-L 2210, CP-L 2211, and CP-L 2212 are Colorado DOT test procedures.

702.3 Emulsified Asphalt Material (Micro Surfacing) – The emulsion for Micro Surfacing shall be Emulsified Asphalt (CQS-1P) conforming to CDOT Table 702-12. The modified emulsion shall contain a minimum of 3% polymer, SBR latex, or natural latex by weight.

| Test on Emulsion | Minimum | Maximum | AASHTO |
|---|----------------|----------------|---------------|
| Viscosity, Say bolt Furol, 25 °C (77 °F),s | 15 | 100 | T-59 |
| Storage Stability Test, 24-h,% | -- | 1 | T-59 |
| Particle Charge Test | Positive | | |
| Sieve Test, %(a) | | 0.1 | T-59 |
| Distillation: | | | |
| Oil distillate, by volume, % | -- | 0.5 | T-59 |
| Residue, % | 62* | -- | T-59 |
| Test on Residue Distillation: | | | |
| Penetration, 25 °C (77 °F), 100g (0.22 lbs) ,5s | 40 | 90 | T-49 |
| Ductility, 25 °C (77 °F), 50 mm (2")/sec | 50 | -- | T-51 |
| Solubility in Trichloroethylene, % | 97 | -- | T-44 |
| Softening Point, Ring-and-Ball, °C (°F) | 57.2 (135) | -- | T-53 |

*The standard distillation procedure shall be modified as follows:

The temperature on the lower thermometer shall be brought slowly to 350 °F +/- 20 °F and maintained at this point for 20 minutes. The total distillation shall be completed in 60+/- 5 minutes from the first application of heat.

A. Annotated Revisions Since Last Publication

409.1.2 Gradation requirement for cover coat aggregate updated to match ISSA standards except for the #200 sieve. The percent passing the #200 sieve will remain the same with an acceptable range of 0 – 1.5.

409 and 702 Bid Alternate Item for CRS-2R emulsion deleted.

CITY AND COUNTY OF DENVER

STATE OF COLORADO



DENVER
THE MILE HIGH CITY

**DEPARTMENT OF TRANSPORTATION &
INFRASTRUCTURE**

Utilities Clearance Record Form

Contract Number: 202057115

2021 Citywide Chip Seal and Crack Seal

December 16, 2020

| | | | |
|---|--|--------------|-------------------|
| CITY AND COUNTY OF DENVER | | | |
| CAPITAL PROJECT UTILITIES CLEARANCE RECORD | | | |
| Project Name: | 2021 Citywide Chip Seal and Crack Seal | Contract No: | 202057115 |
| Project Location: | Citywide | AD date: | December 16, 2020 |
| Project Manager: | Amy Strouthopoulos | Est. NTP: | |
| Supervising Engineer: | Brian Roecker | Const. date: | |

A. Project Utilities Determination

- 1- All checked Yes/No utilities indicated in Part-B have been identified within the project limits and coordinated with the utility owners.
 2- All utility clearance action requirements indicated in Part-C will be obtained before project advertisement.
 3- Note to Project Manager: If activity is applicable, show completed date and initial. Any utility impact resulting in a change to the plans and specifications after the date of signature must be approved by the PWERA-Utilities.

B. Utilities Involvement

| Yes | No | Utilities Involved | Utilities Reviewed | Relocations Requested | Utility Clearance | Clearance Completed | |
|--------------------------|-------------------------------------|--------------------------------------|--------------------------|--------------------------|--------------------------|---------------------|----------|
| | | | | | | Date | Initials |
| <input type="checkbox"/> | <input checked="" type="checkbox"/> | 360 Network | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | 12/3/2020 | AS |
| <input type="checkbox"/> | <input checked="" type="checkbox"/> | Above Net Communications | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | 12/3/2020 | AS |
| <input type="checkbox"/> | <input checked="" type="checkbox"/> | Adesta Group Communications | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | 12/3/2020 | AS |
| <input type="checkbox"/> | <input checked="" type="checkbox"/> | AT&T | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | 12/3/2020 | AS |
| <input type="checkbox"/> | <input checked="" type="checkbox"/> | Comcast Cable | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | 12/3/2020 | AS |
| <input type="checkbox"/> | <input checked="" type="checkbox"/> | Conoco Phillips | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | 12/3/2020 | AS |
| <input type="checkbox"/> | <input checked="" type="checkbox"/> | Danella.com | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | 12/3/2020 | AS |
| <input type="checkbox"/> | <input checked="" type="checkbox"/> | Denver Water | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | 12/3/2020 | AS |
| <input type="checkbox"/> | <input checked="" type="checkbox"/> | Level 3 Communications | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | 12/3/2020 | AS |
| <input type="checkbox"/> | <input checked="" type="checkbox"/> | McLeod USA (Paetec) | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | 12/3/2020 | AS |
| <input type="checkbox"/> | <input checked="" type="checkbox"/> | Metro Wastewater | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | 12/3/2020 | AS |
| <input type="checkbox"/> | <input checked="" type="checkbox"/> | Nustar Energy | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | 12/3/2020 | AS |
| <input type="checkbox"/> | <input checked="" type="checkbox"/> | Qwest Communications | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | 12/3/2020 | AS |
| <input type="checkbox"/> | <input checked="" type="checkbox"/> | Rocky Mountain Pipeline | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | 12/3/2020 | AS |
| <input type="checkbox"/> | <input checked="" type="checkbox"/> | Sprint (Nextel) | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | 12/3/2020 | AS |
| <input type="checkbox"/> | <input checked="" type="checkbox"/> | Time Warner (TW) Telecom | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | 12/3/2020 | AS |
| <input type="checkbox"/> | <input checked="" type="checkbox"/> | Verizon (MCI) | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | 12/3/2020 | AS |
| <input type="checkbox"/> | <input checked="" type="checkbox"/> | XO Communications | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | 12/3/2020 | AS |
| <input type="checkbox"/> | <input checked="" type="checkbox"/> | Xcel Energy - Electric, Distribution | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | 12/3/2020 | AS |
| <input type="checkbox"/> | <input checked="" type="checkbox"/> | Xcel Energy - Electric, Transmission | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | 12/3/2020 | AS |
| <input type="checkbox"/> | <input checked="" type="checkbox"/> | Xcel Energy - Gas | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | 12/3/2020 | AS |
| <input type="checkbox"/> | <input checked="" type="checkbox"/> | Xcel Energy - Steam | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | 12/3/2020 | AS |
| <input type="checkbox"/> | <input checked="" type="checkbox"/> | Railroad, Name | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | 12/3/2020 | AS |
| <input type="checkbox"/> | <input checked="" type="checkbox"/> | Railroad, Name | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | 12/3/2020 | AS |
| <input type="checkbox"/> | <input checked="" type="checkbox"/> | Irrigation company, Name | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | 12/3/2020 | AS |
| <input type="checkbox"/> | <input checked="" type="checkbox"/> | Irrigation company, Name | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | 12/3/2020 | AS |
| <input type="checkbox"/> | <input checked="" type="checkbox"/> | Other, Name | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | 12/3/2020 | AS |
| <input type="checkbox"/> | <input checked="" type="checkbox"/> | Other, Name | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | 12/3/2020 | AS |

C. Additional Requirements

| Yes | No | Activity | Utilities Involved | Date | Initials |
|-------------------------------------|-------------------------------------|--|--------------------|-----------|----------|
| <input checked="" type="checkbox"/> | <input type="checkbox"/> | Existing utility easements identified? | Name | 12/3/2020 | AS |
| <input type="checkbox"/> | <input checked="" type="checkbox"/> | Existing utility easements available? | Name | 12/3/2020 | AS |
| <input type="checkbox"/> | <input checked="" type="checkbox"/> | Railroad Agreement? | Name | 12/3/2020 | AS |
| <input type="checkbox"/> | <input checked="" type="checkbox"/> | Irrigation company agreement? | Name | 12/3/2020 | AS |

D. Comments

Citywide chip seal and crack seal. Surface utility locates only.

E. Project Utility Certification

To the maximum extent practicable prior to the bid advertisement of this project, as a project manager, I am verifying that all the utility conflicts with the indicated above utilities have been coordinated and resolved with the utility owners. All identified mitigations up to this point are included in the final set of plans and specifications for advertisement and construction.

Project Manager Name: Amy Strouthopoulos, **Date:** 12/3/2020.