

CITY AND COUNTY OF DENVER

STATE OF COLORADO



**DENVER**  
THE MILE HIGH CITY

DEPARTMENT OF PUBLIC WORKS

Contract Documents

Contract Number: 201845779



2018 Citywide Bond Concrete Repair

November 16, 2018



## NOTICE OF APPARENT LOW BIDDER

Keene Concrete, Inc.  
30263 WCR 8  
Keenesburg, CO 80643

The EXECUTIVE DIRECTOR OF PUBLIC WORKS has considered the Bids submitted on **December 20, 2018**, for work to be done and materials to be furnished in and for:

### CONTRACT NO: 201845779 2018 Citywide Bond Concrete Repair

as set forth in detail in the Contract Documents for the City and County of Denver, Colorado. It appears that your Bid is fair, equitable, and to the best interest of the City and County; therefore, said Bid is hereby accepted at the bid price contained herein, subject to the approval and execution of the Contract Documents by the City in accordance with the Charter of the City and County of Denver, and to your furnishing the items specified below. The award is based on the total bid items: **(202-00019 through 630-00003, Fifty Eight (58) total bid items, the total estimated cost thereof being: Two Million Four Hundred Sixty Eight Thousand Nine Hundred and Fifty Dollars and Zero Cents (\$2,468,950.00).**

It will be necessary for you to appear forthwith at the office of the Department of Public Works, Contract Administration, 201 W. Colfax Ave., Dept 614, Denver, Colorado 80202, to receive the said Contract Documents, execute the same and return them to the Department of Public Works, Contract Administration within the time limit set forth in the Bid Package Documents.

In accordance with the requirements set forth in the Contract Documents, you are required to furnish the following documents:

- a. Insurance Certificates: General Liability and Automotive Liability, Workman's Compensation and Employer Liability;
- b. Payment and Performance Bond along with One original Power of Attorney relative to Performance and/or Payment Bond; and,

All construction Contracts made and entered into by the City and County of Denver are subject to Affirmative Action and Equal Opportunity Rules and Regulations, as adopted by the Manager of Public Works, and each contract requiring payment by the City of one-half million dollars (\$500,000.00) or more shall first be approved by the City Council acting by ordinance and in accordance with Section 3.2.6 of the Charter of the City and County of Denver.

Prior to issuance of Notice to Proceed, all Equal Opportunity requirements must be completed. Additional information may be obtained by contacting the Director of Contract Compliance at (720-913-1700).

Denver Public Works/Office of the Executive Director  
201 West Colfax Avenue, Dept 608 | Denver, CO 80202  
[www.denvergov.org/dpw](http://www.denvergov.org/dpw)  
p. 720.865.8630 | f. 720.865.8795



**NOTICE OF APPARENT LOW BIDDER**

CONTRACT NO. 201845779

Page 2

The Bid Security submitted with your Bid, will be returned upon execution of the Contract and furnishing of the Performance Bond. In the event you should fail to execute the Contract and to furnish the performance Bond within the time limit specified, said Bid Security will be retained by the City and County of Denver as liquidated damages, and not as a penalty for the delay and extra work caused thereby.

Dated at Denver, Colorado this 18<sup>th</sup> day of January 2019.

CITY AND COUNTY OF DENVER

By

*EC*

Eulois Cleckley

Executive Director of Public Works

cc: Kristen Moore (CAO), Treasury (taxauditadmin@denvergov.org), DSBO Inbox (dsbo@denvergov.org), PM, Prevailing Wage (prevailingwage@denvergov.org), File

Denver Public Works/Office of the Executive Director  
201 West Colfax Avenue, Dept 608 | Denver, CO 80202

[www.denvergov.org/dpw](http://www.denvergov.org/dpw)

p. 720.865.8630 | f. 720.865.8795

**CITY AND COUNTY OF DENVER**

**STATE OF COLORADO**



**DENVER**  
THE MILE HIGH CITY

**DEPARTMENT OF PUBLIC WORKS**

**Bid Form Package**

**Contract Number: 201845779**



**2018 Citywide Bond Concrete Repair**

**November 16, 2018**

**CITY AND COUNTY OF DENVER  
DEPARTMENT OF PUBLIC WORKS**

**TABLE OF CONTENTS  
FOR  
BID FORM AND SUBMITTAL PACKAGE**

Table of Contents	BF-1
Bidder's Checklist	BF-2 through BF-3
Bid Form and Submittal Package Acknowledgment Form	BF-4 through BF-5
Bid Form	BF-6 through BF-8
List of Proposed Minority/Woman Business Enterprise(s)	BF-9 through BF-12
Commitment to Minority/Woman Business Enterprise Participation	BF-13
Minority/Woman Business Enterprise Letter(s) of Intent & Checklist	BF-14 through BF-15
Joint Venture Affidavit	BF-16
Joint Venture Eligibility Form	BF-17 through BF-19
Bid Bond	BF-20
Diversity and Inclusiveness in City Solicitations Form	BF-21 through BF-24



*This Checklist is provided solely for the assistance of the bidders, and need not be returned by Bidders with your BID FORM PACKAGE.*

**BIDDER'S CHECKLIST**

These forms comprise the Bid Form and Submittal Package. Designated forms must be completed and turned in at the time of Bid Opening. Bidders should refer to the Contract Documents, particularly the Instructions to Bidders, accompanying this package, in completing these forms.

FORM/ PAGE NO.	COMMENTS	COMPLETE
BF-4 – BF-5	a.) Legal name, address, Acknowledgment signature and attestation (if required.)	<input checked="" type="checkbox"/>
BF-6+	a.) Fill in individual bid item dollars and totals in Numerical figures only b.) Complete all blanks c.) Legal name required	<input checked="" type="checkbox"/> <input checked="" type="checkbox"/>
BF-7	a.) Write out bid total or bid totals in words and figures in the blank form space(s) provided b.) Calculate Textura® Construction Payment Management System Fee from chart on pg. BF-3 and write fee in the space provided	<input checked="" type="checkbox"/>
BF-8	a.) List all subcontractors who are performing work on this project	<input checked="" type="checkbox"/>
BF-9 – BF-10	a.) Fully complete List of Proposed Minority /Woman Business Enterprise Bidders, Subcontractors, Suppliers, Manufacturers, or Brokers – check appropriate boxes.	<input checked="" type="checkbox"/>
BF-11	a.) Complete all blanks b.) If Addenda have been issued, complete bottom section.	<input checked="" type="checkbox"/> <input checked="" type="checkbox"/>
BF-12	a.) Complete appropriate sections - signature(s) required. b.) If corporation, then corporate seal required.	<input checked="" type="checkbox"/> <input checked="" type="checkbox"/>
BF-13	a.) Fully complete Commitment to Participation	<input checked="" type="checkbox"/>
BF-16	a.) If applicable, fully complete Joint Venture Affidavit (Submit 10 days prior to Bid Opening date)	<input type="checkbox"/>
BF-17 – BF-19	a.) If applicable, fully complete Joint Venture Eligibility Form (Submit 10 days prior to Bid Opening date)	<input type="checkbox"/>
BF-20	a.) Fill in all Bid Bond blanks b.) Signatures required c.) Corporate Seal if required d.) Dated e.) Attach Surety Agents Power of Attorney or Certified or cashier's check made out to the Manager of Revenue referencing Bidder's Company and Contract Number.	<input checked="" type="checkbox"/> <input checked="" type="checkbox"/> <input checked="" type="checkbox"/> <input checked="" type="checkbox"/> <input checked="" type="checkbox"/>
BF-21- BF-24	a.) Each bidder, as a condition of responsiveness to this solicitation, shall <u>complete and return</u> the "Diversity and Inclusiveness in City Solicitations Information Request Form" with their Bid.	<input checked="" type="checkbox"/>

**Textura® Construction Payment Management System (“Textura”)**

Bidder recognizes and agrees that it shall be required to use the Textura® Construction Payment Management System (“Textura”) for this Project to request payment from the City and to pay subcontractors. All certified subcontractors or suppliers who are listed for participation towards any assigned program goal must be paid via Textura. All fees associated with Textura are to be paid by the bidder for billings for work performed. Bidders are required, when preparing a bid, to enter the price of Textura on the line provided for the service. The fee is all inclusive of all subcontractor, project and subscription fees associated with Textura. The bidder will calculate the fee based on their total bid (not including any alternates, if applicable) and the table below, and then include it on the line item provided in the bid form labeled “Textura® Construction Payment Management System Fee”. This expense becomes part of the contract and billable to the City. All costs including, but not limited to, costs associated with training, entering data, and/or utilizing Textura other than the Textura Construction Payment Management System Fee are overhead and shall not be reimbursed by the City. Bidder will be responsible for any tax on the Textura fee. As with other taxes, the City will not reimburse bidder for this cost and therefore this cost should be included in bidder’s bid. Textura will invoice the awarded bidder directly.

Project Value	Project Fee (GC + Sub Usage)
\$100,000 – 249,999.99	\$780
\$250,000 - \$499,999.99	\$1,625
\$500,000 - \$999,999.99	\$3,250
\$1,000,000 - \$2,999,999.99	\$5,850
\$3,000,000 - \$4,999,999.99	\$9,100
\$5,000,000 - \$9,999,999.99	\$12,220
\$10,000,000 - \$19,999,999.99	\$20,345
\$20,000,000 - \$49,999,999.99	\$32,500
\$50,000,000 - \$99,999,999.99	\$48,750
\$100,000,000 - \$199,999,999.99	\$69,095
\$200,000,000 - \$299,999,999.99	\$85,345
\$300,000,000 - \$399,999,999.99	\$109,720
\$400,000,000 - \$499,999,999.99	\$142,220
\$500,000,000 - \$999,999,999.99	\$162,500
\$1,000,000,000 - \$1,999,999,999.99	\$345,345
\$2,000,000,000 - \$4,999,999,999.99	\$650,000
\$5,000,000,000 - \$9,999,999,999.99	\$1,015,625
\$10,000,000,000 or greater	\$1,503,125

For more information:

<http://www.denvergov.org/content/denvergov/en/contract-administration/bidding-process.html>

**CITY AND COUNTY OF DENVER  
DEPARTMENT OF PUBLIC WORKS**

**BID FORM AND SUBMITTAL PACKAGE ACKNOWLEDGMENT**

**CONTRACT NO. 201845779**

**2018 Citywide Bond Concrete Repair**

**BIDDER:**

Keene Concrete, Inc.  
(Legal Name per Colorado Secretary of State)

**ADDRESS:**

30263 WCR 8  
Keenesburg CO 80643  
\_\_\_\_\_  
\_\_\_\_\_

The undersigned bidder states that the undersigned bidder has received and had an opportunity to fully and thoroughly examine a complete set of the Contract Documents for **Contract No. 201845779, 2018 Citywide Bond Concrete Repair**, made available to the undersigned bidder pursuant to Notice of Invitation for Bids dated November 16, 2018.

The undersigned bidder acknowledges that a complete and final set of the Contract Documents for the referenced Project, the components of which are identified below, are bound and maintained as the record set of Contract Documents by the Contract Administration Division of the Department of Public Works and that this Record Set is available for examination by the undersigned bidder.

The undersigned bidder, having thoroughly examined each of the components identified below and contained in Contract Documents, HEREBY SUBMITS THIS BID FORM AND SUBMITTAL PACKAGE, fully understanding that the Contract Documents, as defined in Paragraph 1 of the contract, including this executed Bid Form and Submittal Package, constitute all of the terms, conditions and requirements upon which this submission is based and further understanding that, by submission of this Bid Form and Submittal Package, the City shall rely on the representations and commitments of the undersigned bidder contained herein.

The following completed documents comprising this Bid Form and Submittal Package will be included with and, by this reference, are expressly incorporated into the Contract Documents specified at Paragraph 1 of the Contract:

- Bid Form and Submittal Package Acknowledgment Form
- Bid Form
- List of Proposed Minority/Woman Owned Business Enterprise(s)
- Commitment to Minority/Woman Owned Business Enterprise Participation
- Minority/Woman Owned Business Enterprise(s) of Intent
- Joint Venture Affidavit (if applicable)
- Joint Venture Eligibility Form (if applicable)
- Bid Bond
- Certificate of Insurance



The following designated documents constitute that portion of the Contract Documents made available by the Notice of Invitation for Bids, but not included in the Bid Form and Submittal Package:

- Notice of Invitation for Bids
- Instructions to Bidders
- Addenda (as applicable)
- Equal Employment Opportunity Provisions (Appendix A and Appendix F)
- Contract Form
- General Contract Conditions
- Special Contract Conditions
- Performance and Payment Bond
- Notice to Apparent Low Bidder
- Notice to Proceed
- Contractor's Certification of Payment Form
- Final/Partial Lien Release Form
- Final Receipt
- Change Orders (as applicable)
- Federal Requirements (as applicable)
- Prevailing Wage Rate Schedule(s)
- Technical Specifications
- Contract Drawings
- Accepted Shop Drawings

The undersigned bidder expressly assumes responsibility for the complete contents of these designated documents as bound together with the Bid Form and Submittal Package submitted herewith and designated the Contract Documents.

IN WITNESS WHEREOF, the undersigned bidder has signed personally or by duly authorized officer or agent and duly attested.

**BIDDER:** Keene Concrete, Inc.

**Name:** Chris C Bailey

**By:** Chris C Bailey

**Title:** President

**ATTEST:**

**By:** Gail Darnell  
Gail Darnell Sec/Treas

[SEAL]



**CITY AND COUNTY OF DENVER  
DEPARTMENT OF PUBLIC WORKS**

**BID FORM**

**CONTRACT NO. 201845779  
2018 Citywide Bond Concrete Repair**

**BIDDER** Keene Concrete, Inc.  
(Legal Name per Colorado Secretary of State)

**TO:** The Manager of Public Works  
City and County of Denver  
c/o Contract Administration  
201 West Colfax, Dept. 614  
Denver, Colorado 80202

The Undersigned Bidder, having examined the plans, technical specifications, and remainder of the proposed Contract Documents as designated and enumerated in the General and Special Contract Conditions and any and all addenda thereto; having investigated the location of and conditions affecting the proposed Work; and being acquainted with and fully understanding the extent and character of the Work covered by this bid, and all factors and conditions affecting or which may be affected by Work, HEREBY SUBMITS THIS BID, pursuant to an advertisement of a Notice of Invitation for Bids as published on **November 16, 2018**, to furnish all required materials, tools, appliances, equipment and plant; to perform all necessary labor and to undertake and complete: **Contract No. 201845779, 2018 Citywide Bond Concrete Repair**, in Denver, Colorado, in full accordance with and conformity to the Plans, Technical Specifications, and Contract Documents hereto attached or by reference made a part hereof, at and for the following price(s) set forth on this Bid Form.

The following documents, which taken as a whole constitute the Contract Documents for this Project, and which are incorporated herein, by reference, were made available to the Bidder as provided in the Advertisement of Notice of Invitation for Bids, were received by the bidder, and form the basis for this bid:

- Advertisement of Notice of Invitation for Bids*
- Instructions to Bidders*
- Commitment to M/WBE Participation*
- Article III, Divisions 1 and 3 of Chapter 28, D.R.M.C.*
- Bid Bond*
- Addenda (as applicable)*
- Equal Employment Opportunity Provisions (Appendix A and Appendix F)*
- Bid Form*
- Contract Form*
- General Contract Conditions*
- Special Contract Conditions*
- Performance and Payment Bond*
- Notice to Apparent Low Bidder*
- Notice to Proceed*
- Contractor's Certification of Payment Form*
- Final/Partial Lien Release Form*
- Final Receipt*
- Change Orders (as applicable)*
- Federal Requirements (as applicable)*
- Prevailing Wage Rate Schedule(s)*
- Technical Specifications*
- Contract Drawing*
- Accepted Shop Drawings*
- Certificate of Insurance*

Item No.	Description and Price	Estimated Quantity	Estimated Cost
202-00019	<b>REMOVAL OF INLET</b> at the unit price of \$ <u>300.<sup>00</sup></u> per EACH.	10 EA	\$ <u>30,000.<sup>00</sup></u>
202-00033	<b>REMOVAL OF SIPHON</b> at the unit price of \$ <u>500.<sup>00</sup></u> per EACH.	10 EA	\$ <u>5,000.<sup>00</sup></u>
202-00200	<b>REMOVAL OF SIDEWALK</b> at the unit price of \$ <u>11.<sup>00</sup></u> per SQUARE YARD.	3,750 SY	\$ <u>41,250.<sup>00</sup></u>
202-00201	<b>REMOVAL OF CURBHEAD</b> at the unit price of \$ <u>6.<sup>00</sup></u> per LINEAR FOOT.	2,000 LF	\$ <u>12,000.<sup>00</sup></u>
202-00203	<b>REMOVAL OF CURB AND GUTTER</b> at the unit price of \$ <u>6.<sup>00</sup></u> per LINEAR FOOT.	5,500 LF	\$ <u>33,000.<sup>00</sup></u>
202-00204	<b>REMOVAL OF COMBINATION CURB, GUTTER AND WALK</b> at the unit price of \$ <u>8.<sup>00</sup></u> per LINEAR FOOT.	4,000 LF	\$ <u>32,000.<sup>00</sup></u>
202-00208	<b>REMOVAL AND RESET FLAGSTONE (INCLUDES SALVAGE AND STORAGE)</b> at the unit price of \$ <u>30.<sup>00</sup></u> per SQUARE YARD.	500 SY	\$ <u>15,000.<sup>00</sup></u>
202-00210	<b>REMOVAL OF CONCRETE PAVEMENT</b> at the unit price of \$ <u>13.<sup>00</sup></u> per SQUARE YARD.	2,500 SY	\$ <u>32,500.<sup>00</sup></u>
202-00220	<b>REMOVAL OF ASPHALT MAT</b> at the unit price of \$ <u>4.<sup>00</sup></u> per SQUARE YARD.	7,500 SY	\$ <u>30,000.<sup>00</sup></u>

Item No.	Description and Price	Estimated Quantity	Estimated Cost
202-01000	REMOVAL OF FENCE at the unit price of \$ <u>10.<sup>00</sup></u> per LINEAR FOOT.	500 LF	\$ <u>5,000.<sup>00</sup></u>
202-05021	TRIP HAZARD SAWING (>5 LOCATIONS 1 MONTH COMPLETION) at the unit price of \$ <u>30.<sup>00</sup></u> per INCH-FEET.	100 IN-FT	\$ <u>3,000.<sup>00</sup></u>
202-05020	TRIP HAZARD SAWING (<= 5 LOCATIONS 1 WEEK COMPLETION) at the unit price of \$ <u>33.<sup>00</sup></u> per INCH-FEET.	100 IN-FT	\$ <u>3,300.<sup>00</sup></u>
203-00200	UNCLASSIFIED EXCAVATION at the unit price of \$ <u>25.<sup>00</sup></u> per CUBIC YARD.	2,500 CY	\$ <u>62,500.<sup>00</sup></u>
203-02330	3-MAN LABOR CREW at the unit price of \$ <u>50.<sup>00</sup></u> per HOUR.	300 HR	\$ <u>15,000.<sup>00</sup></u>
206-00065	STRUCTURE BACK FILL (FLOW FILL) at the unit price of \$ <u>110.<sup>00</sup></u> per CUBIC YARD.	150 CY	\$ <u>16,500.<sup>00</sup></u>
208-00050	STORM DRAINAGE INLET PROTECTION at the unit price of \$ <u>50.<sup>00</sup></u> per EACH.	750 EA	\$ <u>37,500.<sup>00</sup></u>
210-00810	RESET GROUND SIGN at the unit price of \$ <u>50.<sup>00</sup></u> per EACH.	250 EA	\$ <u>12,500.<sup>00</sup></u>
210-04010	ADJUST MANHOLE/METER/VALVE/PU LLBOX at the unit price of \$ <u>50.<sup>00</sup></u> per EACH.	60 EA	\$ <u>3,000.<sup>00</sup></u>
210-04011	ADJUST INLET FRAME AND ADJUSTABLE CURBHEAD at the unit price of \$ <u>50.<sup>00</sup></u> per EACH.	60 EA	\$ <u>3,000.<sup>00</sup></u>

Item No.	Description and Price	Estimated Quantity	Estimated Cost
210-04020	<b>RESET INLET GRATE, FRAME, AND ADJUSTABLE CURB BOX (NEW CASTING)</b> at the unit price of \$ <u>1100.<sup>00</sup></u> per EACH.	100 EA	\$ <u>110,000.<sup>00</sup></u>
212-00050	<b>SODDING</b> at the unit price of \$ <u>2.<sup>00</sup></u> per SQUARE FOOT.	500 SF	\$ <u>1000.<sup>00</sup></u>
212-01200	<b>RESTORE LANDSCAPING</b> at the unit price of \$ <u>5.<sup>00</sup></u> per SQUARE FOOT.	2,500 SF	\$ <u>12,500.<sup>00</sup></u>
212-01201	<b>AMENDED TOP SOIL OR LANDSCAPE PLANTER'S SOIL MIX</b> at the unit price of \$ <u>50.<sup>00</sup></u> per CUBIC YARD.	250 CY	\$ <u>12,500.<sup>00</sup></u>
304-06000	<b>AGGREGATE BASE COURSE</b> at the unit price of \$ <u>25.<sup>00</sup></u> per TON.	1,000 TON	\$ <u>25,000.<sup>00</sup></u>
403-00720	<b>HBP PATCH/OVERLAY</b> at the unit price of \$ <u>110.<sup>00</sup></u> per TON.	2,000 TON	\$ <u>220,000.<sup>00</sup></u>
412-00000	<b>24-HOUR HIGH EARLY STRENGTH CONCRETE</b> at the unit price of \$ <u>40.<sup>00</sup></u> per CUBIC YARD.	2,400 CY	\$ <u>96,000.<sup>00</sup></u>
412-00001	<b>ADD PIGMENT TO CONCRETE</b> at the unit price of \$ <u>50.<sup>00</sup></u> per CUBIC YARD.	100 CY	\$ <u>5,000.<sup>00</sup></u>
412-00100	<b>GEO TECH MATERIAL TESTING CONCRETE</b> at the unit price of \$ <u>550.<sup>00</sup></u> per EACH.	50 EA	\$ <u>27,500.<sup>00</sup></u>

Item No.	Description and Price	Estimated Quantity	Estimated Cost
412-00400	<b>4" CONCRETE PAVEMENT</b> at the unit price of \$ <u>40.<sup>00</sup></u> per SQUARE YARD.	150 SY	\$ <u>6,000.<sup>00</sup></u>
412-00600	<b>6" CONCRETE PAVEMENT</b> at the unit price of \$ <u>48.<sup>00</sup></u> per SQUARE YARD.	2,500 SY	\$ <u>120,000.<sup>00</sup></u>
412-00800	<b>8" CONCRETE PAVEMENT</b> at the unit price of \$ <u>60.<sup>00</sup></u> per SQUARE YARD.	500 SY	\$ <u>30,000.<sup>00</sup></u>
412-01000	<b>10" CONCRETE PAVEMENT</b> at the unit price of \$ <u>78.<sup>00</sup></u> per SQUARE YARD.	200 SY	\$ <u>15,600.<sup>00</sup></u>
412-01200	<b>12" CONCRETE PAVEMENT</b> at the unit price of \$ <u>88.<sup>00</sup></u> per SQUARE YARD.	200 SY	\$ <u>17,600.<sup>00</sup></u>
413-00100	<b>CONCRETE PATCHING (STRUCTURAL SURFACE REPAIR &lt;2" DEPTH)</b> at the unit price of \$ <u>50.<sup>00</sup></u> per SQUARE FEET-INCH.	200 SF-IN	\$ <u>10,000.<sup>00</sup></u>
601-00100	<b>PAVESTONE STACKED PRE- CAST WALL BLOCK</b> at the unit price of \$ <u>30.<sup>00</sup></u> per SQUARE FOOT.	500 SF	\$ <u>15,000.<sup>00</sup></u>
601-00400	<b>REINFORCED VARIABLE HEIGHT CONCRETE RETAINING WALL</b> at the unit price of \$ <u>30.<sup>00</sup></u> per SQUARE FOOT.	1,500 SF	\$ <u>45,000.<sup>00</sup></u>
601-06150	<b>CONCRETE PATCHING (STRUCTURAL CURB REPAIR)</b> at the unit price of \$ <u>12.<sup>00</sup></u> per LINEAR FOOT.	500 LF	\$ <u>6,000.<sup>00</sup></u>

Item No.	Description and Price	Estimated Quantity	Estimated Cost
603-01150	<b>15" REINFORCED CONCRETE PIPE (RCP)</b> at the unit price of \$ <u>80.<sup>00</sup></u> per LINEAR FOOT.	50 LF	\$ <u>4,000.<sup>00</sup></u>
603-01180	<b>18" REINFORCED CONCRETE PIPE (RCP)</b> at the unit price of \$ <u>80.<sup>00</sup></u> per LINEAR FOOT.	50 LF	\$ <u>4,000.<sup>00</sup></u>
604-14050	<b>NUMBER 14 INLET (L=6')</b> at the unit price of \$ <u>3,500.<sup>00</sup></u> per EACH.	10 EA	\$ <u>35,000.<sup>00</sup></u>
604-16050	<b>SINGLE NUMBER 16 INLET</b> at the unit price of \$ <u>3,000.<sup>00</sup></u> per EACH.	10 EA	\$ <u>30,000.<sup>00</sup></u>
608-00000	<b>CONCRETE SIDEWALK</b> at the unit price of \$ <u>40.<sup>00</sup></u> per SQUARE YARD.	2,500 SY	\$ <u>100,000.<sup>00</sup></u>
608-00010	<b>CONCRETE CURB RAMP</b> at the unit price of \$ <u>79.<sup>00</sup></u> per SQUARE YARD.	8,500 SY	\$ <u>671,500.<sup>00</sup></u>
608-00018	<b>TRUNCATED DOMES (SPECIAL CAST IRON) MATERIAL ONLY</b> at the unit price of \$ <u>45.<sup>00</sup></u> per SQUARE FOOT.	500 SF	\$ <u>22,500.<sup>00</sup></u>
609-20000	<b>CONCRETE GUTTER OVERLAY</b> at the unit price of \$ <u>8.<sup>00</sup></u> per LINEAR FOOT.	3,000 LF	\$ <u>24,000.<sup>00</sup></u>
609-21020	<b>CURB &amp; GUTTER TYPE II, SECTION 2B</b> at the unit price of \$ <u>18.<sup>00</sup></u> per LINEAR FOOT.	5,500 LF	\$ <u>99,000.<sup>00</sup></u>

Item No.	Description and Price	Estimated Quantity	Estimated Cost
609-21023	<b>CURB &amp; GUTTER TYPE IIB (9") CURBHEAD</b> at the unit price of \$ <u>20.<sup>00</sup></u> per LINEAR FOOT.	300 LF	\$ <u>6,000.<sup>00</sup></u>
609-22021	<b>COMBINATION CURB, GUTTER &amp; SIDEWALK (2'-8")</b> at the unit price of \$ <u>33.<sup>00</sup></u> per LINEAR FOOT.	3,500 LF	\$ <u>115,500.<sup>00</sup></u>
609-22025	<b>COMBINATION CURB, GUTTER &amp; SIDEWALK (3'-11")</b> at the unit price of \$ <u>39.<sup>00</sup></u> per LINEAR FOOT.	400 LF	\$ <u>15,600.<sup>00</sup></u>
610-00026	<b>MEDIAN COVER MATERIAL (6" PATTERNED COLORED CONCRETE)</b> at the unit price of \$ <u>150.<sup>00</sup></u> per SQUARE YARD.	100 SY	\$ <u>15,000.<sup>00</sup></u>
613-07000	<b>RESET PULL BOX</b> at the unit price of \$ <u>400.<sup>00</sup></u> per EACH.	50 EA	\$ <u>20,000.<sup>00</sup></u>
614-72875	<b>LOOP DETECTOR WIRE</b> at the unit price of \$ <u>25.<sup>00</sup></u> per LINEAR FOOT.	50 LF	\$ <u>1,250.<sup>00</sup></u>
623-00204	<b>SPRINKLER SYSTEM/ADJUST SPRINKLER HEAD</b> at the unit price of \$ <u>30.<sup>00</sup></u> per EACH.	500 EA	\$ <u>15,000.<sup>00</sup></u>
623-00205	<b>SPRINKLER SYSTEM/NEW SPRINKLER HEAD</b> at the unit price of \$ <u>50.<sup>00</sup></u> per EACH.	500 EA	\$ <u>25,000.<sup>00</sup></u>
623-00505	<b>SPRINKLER SYSTEM/IRRIGATION RECONSTRUCTION</b> at the unit price of \$ <u>6.<sup>00</sup></u> per LINEAR FOOT.	7,500 LF	\$ <u>45,000.<sup>00</sup></u>



Item No.	Description and Price	Estimated Quantity	Estimated Cost
630-00000	<b>TRAFFIC CONTROL - ARTERIAL/COLLECTOR</b> at the unit price of \$ <u>700.<sup>00</sup></u> per DAY.	50 DAY	\$ <u>35,000.<sup>00</sup></u>
630-00002	<b>TRAFFIC CONTROL - LOCAL</b> at the unit price of \$ <u>380.<sup>00</sup></u> per DAY.	100 DAY	\$ <u>38,000.<sup>00</sup></u>
630-00003	<b>TRAFFIC CONTROL - UNIFORMED TRAFFIC CONTROL</b> at the unit price of \$ <u>100.<sup>00</sup></u> per HOUR.	20 HR	\$ <u>2,000.<sup>00</sup></u>

**Bid Items Total Amount [58 bid items (202-00019 through 630-0003)]**

\$ 2,463,100.<sup>00</sup>

**Textura ® Fee from table on Page BF-3 (based on Bid Items Total Amount)**

\$ 5,850.<sup>00</sup>

**Bid Items Total Amount plus Textura® Fee equals Total Bid Amount**

\$ 2,468,950.<sup>00</sup>

**Total Bid Amount:**

TWO MILLION FOUR HUNDRED SIXTY EIGHT THOUSAND -  
NINE HUNDRED FIFTY & 00/100

Dollars (\$ 2,468,950.<sup>00</sup>)

If the Manager mails a written Notice of Apparent Low Bidder, addressed to the Bidder's business address stated on this Bid Form, the Undersigned Bidder shall, in accordance with the Contract Documents, be ready to, and shall, within five (5) days after the date of the Notice: (i) execute the attached form of Contract in conformity with this bid; (ii) furnish the required proofs of insurance; and (iii) furnish the required bond or bonds in the sum of the full amount of this bid, executed by a surety company acceptable to the Manager.

The Ohio Casualty Ins. Co., a corporation of the State of NH, is hereby offered as Surety on said bond. If such surety is not approved by the Manager, another and satisfactory surety company shall be furnished.

Enclosed with this bid is a bid guarantee, as defined in the attached Instructions to Bidders, in the amount of 5% of total bid. The Undersigned Bidder agrees that the entire amount of this bid guarantee is to be paid to and become the property of the City as liquidated damages, and not as a penalty, if: (i) the bid is considered to be the best by the City; (ii) the City notifies the Undersigned Bidder that it is the Apparent Low Bidder; and (iii) the Undersigned Bidder fails to execute the Contract in the form prescribed or to furnish the required bond and proofs of insurance, within five (5) days after the date of such notification.

The following persons, firms or corporations are interested with the Undersigned Bidder in this bid: N/A

Name: \_\_\_\_\_ Name: \_\_\_\_\_

Address: \_\_\_\_\_ Address: \_\_\_\_\_

If there are no such persons, firms, or corporations, please so state in the following space:

None

The Undersigned Bidder proposes to subcontract the following Work in accordance with General Contract Conditions, Title 5, SUBCONTRACTS, and represents that, to the greatest degree practical, all subcontractors known at the time of bid submittal have been identified.

Item of Work	Percent (%) of Total Work	Proposed Subcontractor and Address
LANDSCAPING AND/OR REMOVALS	1.782%	ZENITRAM LLC 15990 HEDGEWAY DRIVE PARKER COLORADO 80134
ASPHALT	18.226%	LOYA CONSTRUCTION INC PO BOX 211555 DENVER COLORADO 80221

(Copy this page if additional room is required.)



**DENVER**  
OFFICE OF ECONOMIC  
DEVELOPMENT

**List of Proposed  
MWBE  
Bidders, Subcontractors,  
Suppliers (Manufacturers) or  
Brokers**

Office of Economic Development  
Division of Small Business Opportunity  
Compliance Unit  
201 W. Colfax Ave. Dept. 907  
Denver, CO 80202  
Phone: 720-913-1999  
[DSBO@denvergov.org](mailto:DSBO@denvergov.org)

City & County of Denver Contract No.: 201845779

The undersigned Bidder proposes to utilize all listed firms. The following MWBE(s) firms listed are CURRENTLY certified by the City and County of Denver. Only the level of MWBE participation listed at the bid opening will count toward satisfaction of the project goal. Only bona fide commissions may be counted for Brokers. MWBE prime bidders must detail their bid information below. Please copy and attach this page to list additional MWBE.

**Prime Bidder**

Business Name: <u>KEENE CONCRETE INC</u>		
Address: <u>3026 WICK B KEENE BURL CO 80643</u>		Contact Person: <u>TYLER VANDERPOOL</u>
Type of Service: <u>CONCRETE CONSTRUCTION</u>	Dollar Amount: \$: <u>197,950.<sup>00</sup></u>	Percent of Project: <u>79.991%</u>

**Certified MWBE Prime Bidder**

Business Name:		
Address:		Contact Person:
Type of Service:	Dollar Amount: \$:	Percent of Project:

**Subcontractors, Suppliers Manufacturers or Brokers (check one box)**

<input checked="" type="checkbox"/> Subcontractor (v)	<input type="checkbox"/> Supplier (v)	<input type="checkbox"/> Manufacturer (v)	<input type="checkbox"/> Broker (v)
---	---------------------------------------	---	-------------------------------------

Business Name: <u>ZENITRAM LLC</u>		
Address: <u>15990 HEDGECOCK DR PARKER CO 80134</u>		Type of Service: <u>LANDSCAPING/REMOVALS</u>
Contact Person: <u>CODY MARTINEZ</u>	Dollar Amount: \$: <u>44,000.<sup>00</sup></u>	Percent of Project: <u>1.782%</u>

<input checked="" type="checkbox"/> Subcontractor (v)	<input type="checkbox"/> Supplier (v)	<input type="checkbox"/> Manufacturer (v)	<input type="checkbox"/> Broker (v)
---	---------------------------------------	---	-------------------------------------

Business Name: <u>LOYA CONSTRUCTION INC</u>		
Address: <u>PO BOX 211555 DENVER CO 80221</u>		Type of Service: <u>ASPHALT</u>
Contact Person: <u>YESENIA LOYA</u>	Dollar Amount: \$: <u>450,000.<sup>00</sup></u>	Percent of Project: <u>18.226%</u>

<input type="checkbox"/> Subcontractor (v)	<input type="checkbox"/> Supplier (v)	<input type="checkbox"/> Manufacturer (v)	<input type="checkbox"/> Broker (v)
--	---------------------------------------	---	-------------------------------------

Business Name:		
Address:		Type of Service:
Contact Person:	Dollar Amount: \$:	Percent of Project:

Rev 031816JE

Subcontractors, Suppliers Manufacturers or Brokers (check one box)				
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Business Name:				
Address:			Type of Service:	
Contact Person:			Dollar Amount: \$:	Percent of Project:
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Business Name:				
Address:			Type of Service:	
Contact Person:			Dollar Amount: \$:	Percent of Project:
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Business Name:				
Address:			Type of Service:	
Contact Person:			Dollar Amount: \$:	Percent of Project:
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Business Name:				
Address:			Type of Service:	
Contact Person:			Dollar Amount: \$:	Percent of Project:
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Business Name:				
Address:			Type of Service:	
Contact Person:			Dollar Amount: \$:	Percent of Project:
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Business Name:				
Address:			Type of Service:	
Contact Person:			Dollar Amount: \$:	Percent of Project:
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

Rev 031816JE

The undersigned Bidder hereby certifies that the aforementioned subcontractors and suppliers have full knowledge that their names have been offered as subcontractors and suppliers for the work, and the Bidder further certifies that the dollar amount of work to be performed by the aforementioned M/WBE(s) was furnished to the Bidder prior to the bid opening. The undersigned Bidder agrees that after the bid opening, it shall submit to the City an executed and completed W/MBE "Letter of Intent" in three working days (3) on each of its M/WBE subcontractors. The "Letter of Intent" form is contained in the Contract Documents.

The undersigned Bidder acknowledges the right of the City to reject any or all bids submitted, to waive informalities in bids and to re-advertise this Project for bids.

The undersigned certifies that it has carefully checked all works and figures and all statements made in these Bid Forms.

This bid is submitted upon the declaration that neither, I (we), nor, to the best of my (our) knowledge, none of the members of my (our) firm or company have either directly or indirectly entered into any agreement, participated in any collusion or otherwise taken any action in restraint of free competitive bidding in connection with this bid.

Business Address of Bidder: 30263 WCR 8  
City, State, Zip Code: Keenesburg CO 80643  
Telephone Number of Bidder: 303-227-1901 Fax No. 303-227-1904  
Social Security or Federal Employer ID Number of Bidder: 84-1549666

Name and location of the last work of this kind herein contemplated upon which the Bidder was engaged:  
2018 Citywide ADA Ramp & Concrete Repair Ph.1B - various locations throughout Denver

For information relative thereto, please refer to:

Name: Andy Ford  
Title: Project Manager  
Address: 2000 W 3rd Ave Denver CO 80223

The undersigned acknowledges receipt, understanding, and full consideration of the following addenda to the Contract Documents:

Addenda Number 1 Date 12/13/18  
Addenda Number \_\_\_\_\_ Date \_\_\_\_\_  
Addenda Number \_\_\_\_\_ Date \_\_\_\_\_

Dated this 20th day of December, 2018.

**CITY AND COUNTY OF DENVER  
DEPARTMENT OF PUBLIC WORKS  
Engineering Division**

**CONTRACT NO. 201845779  
PROJECT NAME: 2018 Citywide Bond Concrete Repair**

**ADDENDUM NO. 1 TO CONTRACT DOCUMENTS**

Bidders are hereby instructed that the drawings, specifications, and other contract documents are modified, corrected, supplemented and/or superseded for the above mentioned project as hereinafter described in the following attachments:

**Question and Answers**


- 1. The HBP Patch/Overlay and we looked through the bid docs and did not find a mix design. Do you have one other than "City and County of Denver approved mix".*

No specific mix design is specified. CDOT approved mix designs for patching will be accepted.


- 2. In the pre-bid it says the City will do the concrete testing but there is a line item on the bid schedule for material testing. Please confirm who is to pay for testing.*

The line item for testing will be used to pay for the concrete testing required of the Contractor (air, slump, strength), typically once a week unless concrete does not meet specifications or High Early Concrete is used and further testing is required. The City also has a third party tester on call to verify results. This is paid by the City with a separate contract, not the testing line item.

This ADDENDUM shall be attached to, become a part of, and be returned with the Bid Proposal.

  
Lesley B. Thomas  
City Engineer  
12.13.18  
Date

The undersigned bidder acknowledges receipt of this Addendum. The Proposal submitted herewith is in accordance with the stipulations set forth herein.

  
Contractor

ADDENDUM NO. 1

DATE: 12/14/18

**Signature of Bidder:**

If an Individual: \_\_\_\_\_ doing business  
as \_\_\_\_\_.

If a Partnership: \_\_\_\_\_  
by: \_\_\_\_\_ General Partner.

If a Corporation: Keene Concrete, Inc.  
a Colorado Corporation,  
by: Chris C Bailey, its President.  
CHRIS C BAILEY

Attest:  
Gail Darnell  
Secretary Gail Darnell (Corporate Seal)



**If a Joint Venture, signature of all Joint Venture participants.**

Firm: \_\_\_\_\_

Corporation ( ), Partnership ( ) or ( ) Limited Liability Company

By: \_\_\_\_\_ (If a Corporation)  
Attest: \_\_\_\_\_  
Title: \_\_\_\_\_ Secretary (Corporate Seal)

Firm: \_\_\_\_\_

Corporation ( ), Partnership ( ) or ( ) Limited Liability Company

By: \_\_\_\_\_ (If a Corporation)  
Attest: \_\_\_\_\_  
Title: \_\_\_\_\_ Secretary (Corporate Seal)

Firm: \_\_\_\_\_

Corporation ( ), Partnership ( ) or ( ) Limited Liability Company

By: \_\_\_\_\_ (If a Corporation)  
Attest: \_\_\_\_\_  
Title: \_\_\_\_\_ Secretary (Corporate Seal)





**DENVER**  
OFFICE OF ECONOMIC  
DEVELOPMENT

Office of Economic Development  
Division of Small Business Opportunity  
Compliance Unit  
201 W. Colfax Ave. Dept. 907  
Denver, CO 80202  
Phone: 720-913-1999  
[DSBO@denvergov.org](mailto:DSBO@denvergov.org)

## COMMITMENT TO MWBE PARTICIPATION

**The undersigned has satisfied the MWBE participant requirements in the following manner (Please check the appropriate box):**

The Bidder/Proposer is committed to the minimum 20 % **MWBE** utilization on the project, and will submit Letters of Intent (LOI) for each subcontractor/subconsultant listed in the Bid Forms as follows:  
**Hard Bids: Three (3)** business days after the bid opening.  
**Request for Proposals/Qualifications:** With the proposal when due.  
**Compliance Plans:** With each task/work order

The Bidder/Proposer is unable to meet the project goal of \_\_\_\_\_% **MWBE**, but is committed to a minimum of \_\_\_\_\_% **MWBE** utilization on the project. The Bidder/Proposer understands that they must submit a detailed statement of their good faith effort under sealed bid procedures, as a matter of responsiveness, or with initial proposals, under contract negotiation procedures; or no later than **three (3)** days after bid opening as a matter of responsibility as in accordance with DRMC Section 28-62 and 28-67 of Ordinance 85 to the Division of Small Business Opportunity.

The Bidder/Proposer is a certified **MWBE** in good standing with the City and is committed to self-perform a minimum of \_\_\_\_\_% of the work on the contract.

Bidder/Proposer (Name of Firm): Keene Concrete, Inc

Firm's Representative (Please print): Chris C Bailey

Signature (Firm's Representative): Chris C Bailey

Title: President

Address: 30263 WCR 8

City: Keenesburg

State: CO

Zip: 80643

Phone: 303-227-1901

Fax: 303-227-1904

Email: tylerv@keeneconcrete.com

**A copy of the MWBE Certification letter must be attached to each Letter of Intent (LOI).**



**DENVER**  
OFFICE OF ECONOMIC  
DEVELOPMENT

Office of Economic Development  
Division of Small Business Opportunity  
Compliance Unit  
101 West Colfax Ave., Ste 850  
Denver, CO 80202  
Phone: 720-913-1714

**LETTER OF INTENT (LOI)**  
**INSTRUCTIONS FOR COMPLETION & SUBMISSION:**

- All lines must be completed or marked N/A for Not Applicable
- Certification Letter must be submitted with LOI
- Submit the attached completed checklist with this letter
- Email to [dsbo@denvergov.org](mailto:dsbo@denvergov.org)
- FOR RFPs and RFQs: LOIs should be included with Submittal

**Contract No.:** 201845779 **Project Name:** 2018 CITYWIDE BOND CONCRETE REPAIR

**A. The Following Section Is To Be Completed by the Bidder/Consultant**  
**This Letter of Intent Must be Signed by the Bidder/Consultant and M/WBE, SBE, EBE or DBE**

**Name of Bidder/Consultant:** KEENE CONCRETE INC **Self-Performing:**  Yes  No **Phone:** 303-227-1901  
**Contact Person:** TYLER VANDERPOOL **Email:** TYLER@KEENECONCRETE.COM **Fax:** 303-227-1904  
**Address:** 30263 WCR B **City:** KEENESBURG **State:** CO **Zip:** 80643

**B. The Following Section is To Be Completed by the M/WBE, SBE, EBE or DBE, at any Tier**  
**This Letter of Intent Must be Signed by the M/WBE, SBE, EBE or DBE and Bidder/Consultant**

**Name of Certified Firm:** ZENITRAM LLC **Phone:** 303-386-2674  
**Contact Person:** CODY MARTINEZ **Email:** CODY@ZENITRAMLLC.COM **Fax:**  
**Address:** 15990 HEDGEMAN DR **City:** PARKER **State:** CO **Zip:** 80134

**Please check the designation which applies to the certified firm.**

M/WBE (✓)	<input checked="" type="checkbox"/>	SBE (✓)	<input type="checkbox"/>	EBE (✓)	<input type="checkbox"/>	DBE (✓)	<input type="checkbox"/>
-----------	-------------------------------------	---------	--------------------------	---------	--------------------------	---------	--------------------------

**Indirect Utilization:** If this M/WBE, SBE, EBE or DBE is not a direct first tier subcontractor/subconsultant, supplier or broker to the Bidder/Consultant, please indicate the name of the subcontractor/subconsultant, supplier or broker which is utilizing the participation of this firm:

**A Copy of the M/WBE, SBE, EBE or DBE Letter of Certification must be Attached**

Identify the scope of the work to be performed or supply item that will be provided by the M/WBE/SBE/DBE. **On unit price bids only, identify which bid line items the M/WBE/SBE/EBE/DBEs scope of work or supply corresponds to.**

LANDSCAPING AND REMOVALS

**Subcontractor/Subconsultant (✓)**  **Supplier (✓)**  **Broker (✓)**

**Bidder** intends to utilize the aforementioned M/WBE, SBE, EBE or DBE for the Work/Supply described above. The cost of the work and percentage of the total subcontractor M/WBE, SBE, EBE or DBE bid amount is:

\$ 44,000.00 1.782%

**Consultant** intends to utilize the aforementioned M/WBE, SBE, EBE or DBE for the Work/Supply described above. The percentage of the work of the total subconsultant M/WBE, SBE, EBE or DBE will perform is: %

If the fee amount of the work to be performed is requested, the fee amount, is: \$

**Bidder/Consultant's Signature:** Tyler Vanderpool **Date:** 12/20/2018

**Title:** CONTROLLER

**M/WBE, SBE, EBE or DBE or Self-Performing Firm's Signature:** *[Signature]* **Date:** 12-20-2018

**Title:** Owner

If the above named Bidder/Consultant is not determined to be the successful Bidder/Consultant, this Letter of Intent shall be null and void.



**Office of Economic Development**  
Division of Small Business Opportunity

201 W. Colfax Avenue, #907  
Denver, CO Zip 80202  
p: 720.913.1999  
f: 720.913.1809  
[www.denvergov.org/dsbo](http://www.denvergov.org/dsbo)

Denver International Airport  
Airport Office Building, Suite 7810  
8500 Pena Boulevard  
Denver, CO Zip 80249  
p: 303.342.2180  
f: 303.342.2190  
[www.Dydenver.com](http://www.Dydenver.com)

July 25, 2018

Cody Martinez  
Zenitram, LLC  
15990 Hedgeway Drive  
Parker, CO 80134

Dear Cody Martinez:

**SUBJECT: Minority/Women Business Enterprise (M/WBE) Certification, Pursuant to Article III of Chapter 28, Div. 3 of the D.R.M.C. Construction, Reconstruction, Remodeling and Professional Design, Construction Services and Concessions**

The City and County of Denver's Division of Small Business Opportunity (DSBO) has approved Zenitram, LLC for certification as a **Minority/Women Business Enterprise (M/WBE)**. Zenitram, LLC will be listed in the City and County of Denver's Minority/Women Business Enterprise (M/WBE) Certification Directory. Your firm is certified with the following certification dates:

**July 25, 2018 to July 24, 2019**

Listed below is each NAICS code for which Zenitram, LLC is certified. Please verify your NAICS codes as this letter showing the following codes is required for bidding on City projects:

**NAICS CODES:**

DENVER 237310: ASPHALT PAVING (I.E., HIGHWAY, ROAD, STREET, PUBLIC SIDEWALK)  
DENVER 237310: CONCRETE PAVING (I.E., HIGHWAY, ROAD, STREET, PUBLIC SIDEWALK)  
DENVER 237310: CURBS AND STREET GUTTERS, HIGHWAY, ROAD AND STREET, CONSTRUCTION  
DENVER 238110: CONCRETE FINISHING  
DENVER 238110: CONCRETE REPAIR  
DENVER 238110: FOOTING AND FOUNDATION CONCRETE CONTRACTORS  
DENVER 238120: STAIRWAY, PRECAST CONCRETE, INSTALLATION  
DENVER 238910: CONCRETE BREAKING AND CUTTING FOR DEMOLITION

Concrete Contractor / Handicap Ramps

This Certification is intended to be used only for participation in city funded projects, and/or certain privately funded projects on city-owned property for contracts with construction, reconstruction, remodeling and professional design and construction services.

Your business enterprise is required to maintain an accurate mailing address, email address and telephone number information with DSBO. If any changes occur in the firm's legal structure, ownership, management, control, or work performed, you must notify DSBO immediately. Failure to report any of these changes may result in removal of your business enterprise from the Certification Directory and possible revocation of certification of your business enterprise as an M/WBE.

Please be aware that your M/WBE Certification is valid for a period of one (1) year, and must be renewed annually. It is your responsibility to request and submit a renewal application and all of the documents required within the renewal application in order for your renewal to be processed. Your application and accompanying documents should be sent electronically to our office at least thirty (30) days prior to the expiration date of your M/WBE Certification.

You may visit [www.work4denver.com](http://www.work4denver.com) to view upcoming Construction/Professional Service bidding opportunities, or [www.denvergov.org/purchasing](http://www.denvergov.org/purchasing) for upcoming Goods & Services bid opportunities. This letter must be attached to your Letter of Intent (LOI) for bidding opportunities in which you may be utilized for goal participation.



**DENVER**  
OFFICE OF ECONOMIC  
DEVELOPMENT

Office of Economic Development  
Division of Small Business Opportunity  
Compliance Unit  
101 West Colfax Ave., Ste 850  
Denver, CO 80202  
Phone: 720-913-1714

**LETTER OF INTENT (LOI)**  
**INSTRUCTIONS FOR COMPLETION & SUBMISSION:**

- All lines must be completed or marked N/A for Not Applicable
- Certification Letter must be submitted with LOI
- Submit the attached completed checklist with this letter
- Email to [dsbo@denvergov.org](mailto:dsbo@denvergov.org),
- **FOR RFPs and RFQs: LOIs should be included with Submittal**

**Contract No.:** 201845779 **Project Name:** 2018 CITYWIDE BOND CONCRETE REPAIR

**A. The Following Section Is To Be Completed by the Bidder/Consultant**  
**This Letter of Intent Must be Signed by the Bidder/Consultant and M/WBE, SBE, EBE or DBE**

**Name of Bidder/Consultant:** KEENE CONCRETE INC **Self-Performing:**  Yes  No **Phone:** 303-227-1901  
**Contact Person:** TYLER VANDERPOOL **Email:** TYLER@KEENECONCRETE.COM **Fax:** 303-227-1904  
**Address:** 30263 WCR 8 **City:** KEENESBURG **State:** CO **Zip:** 80643

**B. The Following Section is To Be Completed by the M/WBE, SBE, EBE or DBE, at any Tier**  
**This Letter of Intent Must be Signed by the M/WBE, SBE, EBE or DBE and Bidder/Consultant**

**Name of Certified Firm:** LOYA CONSTRUCTION INC **Phone:** 720-254-3702  
**Contact Person:** YESENIA LOYA **Email:** LOYA@CONSTRUCTIONCOYAHOO.COM **Fax:**  
**Address:** PO BOX 211555 **City:** DENVER **State:** CO **Zip:** 80221

**Please check the designation which applies to the certified firm.**

M/WBE (✓)	<input checked="" type="checkbox"/>	SBE (✓)	<input type="checkbox"/>	EBE (✓)	<input type="checkbox"/>	DBE (✓)	<input type="checkbox"/>
-----------	-------------------------------------	---------	--------------------------	---------	--------------------------	---------	--------------------------

**Indirect Utilization:** If this M/WBE, SBE, EBE or DBE is not a direct first tier subcontractor/subconsultant, supplier or broker to the Bidder/ Consultant, please indicate the name of the subcontractor/subconsultant, supplier or broker which is utilizing the participation of this firm:

**A Copy of the M/WBE, SBE, EBE or DBE Letter of Certification must be Attached**

Identify the scope of the work to be performed or supply item that will be provided by the M/WBE/SBE/DBE. **On unit price bids only, identify which bid line items the M/WBE/SBE/EBE/DBEs scope of work or supply corresponds to.**

ASPHALT

**Subcontractor/Subconsultant (✓)**  **Supplier (✓)**  **Broker (✓)**

**Bidder** intends to utilize the aforementioned M/WBE, SBE, EBE or DBE for the Work/Supply described above. The cost of the work and percentage of the total subcontractor M/WBE, SBE, EBE or DBE bid amount is:

\$ 450,000.00 18.226%

**Consultant** intends to utilize the aforementioned M/WBE, SBE, EBE or DBE for the Work/Supply described above. The percentage of the work of the total sub consultant M/WBE, SBE, EBE or DBE will perform is:

If the fee amount of the work to be performed is requested, the fee amount, is: \$

**Bidder/Consultant's Signature:** Tyler Vanderpool **Date:** 12/20/2018

**Title:** CONTROLLER

**M/WBE, SBE, EBE or DBE or Self-Performing Firm's Signature:** [Signature] **Date:** 12/20/2018

**Title:** President

If the above named Bidder/Consultant is not determined to be the successful Bidder/Consultant, this Letter of Intent shall be null and void.



201 W. Colfax Avenue, #907  
Denver, CO Zip 80202  
p: 720.913.1999  
f: 720.913.1809  
www.denvergov.org/dsbo

Denver International Airport  
Airport Office Building, Suite 7810  
8500 Pena Boulevard  
Denver, CO Zip 80249  
p: 303.342.2180  
f: 303.342.2190  
www.Dydenver.com

March 14, 2018

Yesenia Loya  
Loya Construction, Inc. DBA N/A  
PO Box 211555  
Denver, CO 80221

Dear Yesenia Loya:

**SUBJECT: Minority/Women Business Enterprise (M/WBE) Certification, Pursuant to Article III of Chapter 28, Div. 3 of the D.R.M.C. Construction, Reconstruction, Remodeling and Professional Design, Construction Services and Concessions**

The City and County of Denver's Division of Small Business Opportunity (DSBO) has approved Loya Construction, Inc. DBA N/A for certification as a **Minority/Women Business Enterprise (M/WBE)**. Loya Construction, Inc. DBA N/A will be listed in the City and County of Denver's Minority/Women Business Enterprise (M/WBE) Certification Directory. Your firm is certified with the following certification dates:

**March 14, 2018 to March 13, 2019**

Listed below is each NAICS code for which Loya Construction, Inc. DBA N/A is certified. Please verify your NAICS codes as this letter showing the following codes is required for bidding on City projects:

**NAICS CODES:**

DENVER 237310: ASPHALT PAVING (I.E., HIGHWAY, ROAD, STREET, PUBLIC SIDEWALK)  
DENVER 237310: CURBS AND STREET GUTTERS, HIGHWAY, ROAD AND STREET, CONSTRUCTION  
DENVER 238390: WATERPROOFING CONTRACTORS  
DENVER 484220: GRAVEL HAULING, LOCAL  
DENVER 484220: SAND HAULING, LOCAL  
DENVER 484220: TOP-SOIL HAULING, LOCAL

Concrete flatwork & curb & gutter; ground maintenance-snow removal; paving-asphalt & concrete; asphalt cement & emulsified asphalt; concrete flatwork; paving/cold bituminous; paving/hot bituminous; tandem trucking; tractor trailer; special trailers; dirt(haul);aggregate (haul);asphalt haul);rip rap(haul);construction debris

This Certification is intended to be used only for participation in city funded projects, and/or certain privately funded projects on city-owned property for contracts with construction, reconstruction, remodeling and professional design and construction services.

Your business enterprise is required to maintain an accurate mailing address, email address and telephone number information with DSBO. If any changes occur in the firm's legal structure, ownership, management, control, or work performed, you must notify DSBO immediately. Failure to report any of these changes may result in removal of your business enterprise from the Certification Directory and possible revocation of certification of your business enterprise as an M/WBE.

Please be aware that your M/WBE **Certification is valid for a period of one (1) year, and must be renewed annually.** It is your responsibility to request and submit a renewal application and all of the documents required within the renewal application in order for your renewal to be processed. Your application and accompanying documents should be sent electronically to our office at least thirty (30) days prior to the expiration date of your M/WBE Certification.

You may visit [www.work4denver.com](http://www.work4denver.com) to view upcoming Construction/Professional Service bidding opportunities, or [www.denvergov.org/purchasing](http://www.denvergov.org/purchasing) for upcoming Goods & Services bid opportunities. This letter must be attached to your Letter of Intent (LOI) for bidding opportunities in which you may be utilized for goal participation.

## Letter of Intent (LOI) Checklist

*All lines must be completed or marked N/A for Not Applicable*

*Submit the attached completed checklist with this letter.*

<b>Completed ✓</b>	
<input type="checkbox"/>	Project Number & Project Name
<input type="checkbox"/>	Section A: Name of Bidder/Consultant, Contact Person, Address, City, State, Zip, Phone, Email
<input type="checkbox"/>	Section B: Name of Certified Firm, Contact Person, Address, City, State, Zip, Phone, Email
<input type="checkbox"/>	Designation checked for MBE/WBE, SBE, EBE or DBE
<input type="checkbox"/>	Indirect Utilization: Name of subcontractor/subconsultant, supplier or broker is indicated if using the participation of a 2 <sup>nd</sup> tier subcontractor/subconsultant, supplier or broker.
<input type="checkbox"/>	Scope of work performed or item supplied by M/WBE, SBE, EBE or DBE
<input type="checkbox"/>	Line items performed, if line-item bid.
<input type="checkbox"/>	Copy of M/WBE, SBE, EBE or DBE Letter of Certification Attached
<input type="checkbox"/>	Designation checked for Subcontractor/Subconsultant, Supplier or Broker
	<b>If project is a hard bid...</b>
<input type="checkbox"/>	Bidder has indicated dollar amount for value of work going to Subcontractor/ Subconsultant, Supplier or Broker
<input type="checkbox"/>	Bidder has indicated percentage for value of work going to Subcontractor/ Subconsultant, Supplier or Broker
	<b>If project is an RFP/RFQ...</b>
<input type="checkbox"/>	Consultant has indicated percentage for value of work going to Subcontractor/ Subconsultant, Supplier or Broker Name & contact name for MWBE.
<input type="checkbox"/>	Fee amount if fee amount of work to be performed is requested.
<input type="checkbox"/>	Bidder/Consultant's Signature, Title & Date
<input type="checkbox"/>	M/WBE, SBE, EBE or DBE Firm's Signature, Title and Date

<b>Select One ✓</b>	<b>SUBMITTED VIA...</b> For Construction Hard Bids ONLY, Bidders are strongly urged to deliver the LOI via one of the methods below. (The preferred method is to scan/email completed forms to email address below. Delivery to any other point cannot be guaranteed timely delivery.)
<input type="checkbox"/>	Email to <a href="mailto:DSBO@denvergov.org">DSBO@denvergov.org</a>

**The complete and accurate information that is required for the Letter of Intent is based on the following sections of the Ordinance 85: Section 28-63 and Section 28-68. Failure to complete this information on the Letter of Intent (LOI) may automatically deem a bid or proposal non-responsive.**



**Joint Venture Affidavit**

The Undersigned swears that the foregoing statements are correct and include all material information necessary to identify and explain the terms and operation of our joint venture and the intended participation by each joint venturer in the undertaking. Further, the Undersigned covenant and agree to provide the City current, complete, and accurate information regarding actual joint venture work and the payment thereof and any proposed changes in any of the joint venture arrangements and to permit the audit and examination of the books, records, and files of the joint venture, by authorized representatives of the City or Federal funding agency, if applicable. Any material misrepresentation will be grounds for terminating any contract which may be awarded and for initiating action under Federal or State laws concerning false statements.

Name of Firm: \_\_\_\_\_

Print Name: \_\_\_\_\_

Title \_\_\_\_\_

Signature: \_\_\_\_\_

Date: \_\_\_\_\_

**Notary Public**

County of \_\_\_\_\_

State of \_\_\_\_\_

My Commission Expires: \_\_\_\_\_

Subscribed and sworn before me this

\_\_\_\_\_ day of \_\_\_\_\_, 20\_\_\_\_\_

Notary Seal

Notary Signature: \_\_\_\_\_

Notary Commission #: \_\_\_\_\_

Address: \_\_\_\_\_

Name of Firm: \_\_\_\_\_

Print Name: \_\_\_\_\_

Title \_\_\_\_\_

Signature: \_\_\_\_\_

Date: \_\_\_\_\_

**Notary Public**

County of \_\_\_\_\_

State of \_\_\_\_\_

My Commission Expires: \_\_\_\_\_

Subscribed and sworn before me this

\_\_\_\_\_ day of \_\_\_\_\_, 20\_\_\_\_\_

Notary Seal

Notary Signature: \_\_\_\_\_

Notary Commission #: \_\_\_\_\_

Address: \_\_\_\_\_



**JOINT VENTURE  
ELIGIBILITY FORM**

Joint Venture means an association of two (2) or more business enterprises to constitute a single business enterprise to perform a City construction or professional design and construction services contract for which purpose they combine their property, capital, efforts, skills and knowledge, and in which each joint venturer is responsible for a distinct, clearly defined portion of the work of the contract, performs a commercially useful function, and whose share in the capital contribution, control, management responsibilities, risks and profits of the joint venture are equal to its ownership interest. Joint ventures must have an agreement in writing specifying the terms and conditions of the relationships between the joint venturers and their relationship and responsibility to the contract.

The Division of Small Business Opportunity (DSBO) requires the following information be provided from participants of a prospective joint venture, to assist DSBO in evaluating the proposed joint venture. This Joint Venture Eligibility form and the Joint Venture Affidavit apply if SBEs, EBEs, MBEs, WBEs or DBEs participate in this joint venture.

Please return this form, the Joint Venture Affidavit, and a copy of your Joint Venture Agreement to: Division of Small Business Opportunity, 201 West Colfax Avenue, Denver, CO 80202, at least ten (10) working days prior to bid opening or proposal.

If you have questions regarding this process, please contact DSBO at 720-913-1999.

**Joint Venture Information**

Name:		Contact Person:	
Address:			
City:	State:	Zip:	Phone:

**Joint Venture Participants**

Name:		Contact Person:	
Address:			
City:	State:	Zip:	Phone:
% Ownership:	Certifying Entity:	Type Certification & Date: (S/E/M/W or DBE)	
Type of Work for which Certification was granted:			

Name:		Contact Person:	
Address:			
City:	State:	Zip:	Phone:
% Ownership:	Certifying Entity:	Type Certification & Date: (S/E/M/W or DBE)	
Type of Work for which Certification was granted:			

**General Information**

SBE/EBE/MBE/WBE/DBE Initial Capital Contributions: \$	%
Future capital contributions (explain requirements) (attach additional sheets if necessary):	

Source of Funds for the SBE/EBE/MBE/WBE/DBE Capital Contributions:

Describe the portion of the work or elements of the business controlled by the SBE/EBE/MBE/WBE or DBE: (attach additional sheets if necessary)




Describe the portion of the work or elements of the business controlled by non-SBE/EBE/MBE/WBE or DBE: (attach additional sheets if necessary)


**JOINT VENTURE ELIGIBILITY FORM**

**General information**

Describe the SBE/EBE/MBE/WBE or DBE's involvement in the overall management of the joint venture (e.g., participation on a management committee or managing board voting rights, etc.) (attach additional sheets if necessary)


Describe the SBE/EBE/MBE/WBE or DBE's share in the profits of the joint venture:


Describe the SBE/EBE/MBE/WBE or DBE's share in the risks of the joint venture:


Describe the roles and responsibilities of each joint venture participant with respect to managing the joint venture (use additional sheets if necessary):

a. SBE/EBE/MBE/WBE or DBE joint venture participant:


b. Non- SBE/EBE/MBE/WBE or DBE joint venture participant:


Describe the roles and responsibilities of each joint venture participant with respect to operation of the joint venture (use additional sheets if necessary):

a. SBE/EBE/MBE/WBE or DBE joint venture participant:


b. Non- SBE/EBE/MBE/WBE or DBE joint venture participant:


Which firm will be responsible for accounting functions relative to the joint venture's business?

---

Explain what authority each party will have to commit or obligate the other to insurance and bonding companies, financing institutions, suppliers, subcontractors, and/or other parties?

---



---

Please provide information relating to the approximate **number** of management, administrative, support and non-management employees that will be required to operate the business and indicate whether they will be employees of the S/E/MWBE/DBE, non-S/E/MWBE/DBE or joint venture:

	Non- SBE/EBE/MWBE/DBE	SBE/EBE/MWBE/DBE	Joint Venture
Management			
Administrative			
Support			
Hourly Employees			

**JOINT VENTURE ELIGIBILITY FORM**

**General Information**

Please provide the name of the person who will be responsible for hiring employees for the joint venture.

---

Who will they be employed by?

Are any of the proposed joint venture employees currently employees of any of the joint venture partners?	<input type="checkbox"/>	Yes (✓)	<input type="checkbox"/>	No (✓)
---	--------------------------	------------	--------------------------	-----------

If yes, please list the number and positions and indicate which firm currently employs the individual(s), (use additional sheets if necessary)

Number of employees	Position	Employed By

**Attach** a copy of the proposed joint venture agreement, promissory note or loan agreement (if applicable), and any and all written agreements between the joint venture partners.

List all other business relationships between the joint venture participants, including other joint venture agreements in which the parties are jointly involved.

---

If there are any significant changes in or pertaining to this submittal, the joint venture members must immediately notify the Division of Small Business Opportunity.

COMP-FRM-015

CITY AND COUNTY OF DENVER  
DEPARTMENT OF PUBLIC WORKS

BID BOND

KNOW ALL MEN BY THESE PRESENTS:

THAT Keene Concrete, Inc., 30263 WCR 8, Keenesburg, CO 80643, as Principal, and The Ohio Casualty Insurance Company, 62 Maple Ave., Keene, NH 03431, a corporation organized and existing under and by virtue of the laws of the State of New Hampshire, and authorized to do business within the State of Colorado, as Surety, are held and firmly bound unto the City and County of Denver, Colorado, as Oblige, in full and just sum of Five percent of the bid amount\*\*\*\*\* Dollars, (\$ 5%\*\*\*\*\* ), lawful money of the United States, for the payment of which sum, well and truly to be made, we bind ourselves, our heirs, executors, administrators, successors and assigns, jointly and severally, firmly by these presents:

WHEREAS, the said Principal is herewith submitting its bid, dated December 20th, 2018, for the construction of: **CONTRACT NO. 201845779, 2018 CITYWIDE BOND CONCRETE REPAIR**, as set forth in detail in the Contract Documents for the City and County of Denver, Colorado, and said Oblige has required as a condition for receiving said bid that the Principal deposit specified bid security in the amount of not less than five percent (5%) of the amount of said bid, as it relates to work to be performed for the City, conditioned that in event of failure of the Principal to execute the Contract, for such construction and furnish required Performance and Payment Bond if the contract is offered him that said sum be paid immediately to the Oblige as liquidated damages, and not as a penalty, for the Principal's failure to perform.

The condition of this obligation is such that if the aforesaid Principal shall, within the period specified therefore, on the prescribed form presented to him for signature, enter into a written contract with the Oblige in accordance with his bid as accepted and give Performance and Payment Bond with good and sufficient surety or sureties, upon the form prescribed by the Oblige, for the faithful performance and the proper fulfillment of said Contract, or in the event of withdrawal of said bid within the time specified, or upon the payment to the Oblige of the sum determined upon herein, as liquidated damages and not as penalty, in the event the Principal fails to enter into said contract and give such Performance and Payment Bond within the time specified, then this Obligation shall be null and void, otherwise to remain in full force and effect.

Signed, sealed and delivered this 20th day of December, 2018.

ATTEST

Gail Darnell  
Secretary Gail Darnell

Keene Concrete, Inc.

Principal  
By

Chris C. Bailey  
Chris C. Bailey

Title President

The Ohio Casualty Insurance Company

Surety

By

Tristin Rosen  
Tristin Rosen, Attorney-in-Fact

Seal if Bidder is Corporation  
(Attach Power-of-Attorney)

[SEAL]

**THIS POWER OF ATTORNEY IS NOT VALID UNLESS IT IS PRINTED ON RED BACKGROUND.**

This Power of Attorney limits the acts of those named herein, and they have no authority to bind the Company except in the manner and to the extent herein stated.

Certificate No. 7987517

Liberty Mutual Insurance Company  
The Ohio Casualty Insurance Company West American Insurance Company

**POWER OF ATTORNEY**

KNOWN ALL PERSONS BY THESE PRESENTS: That The Ohio Casualty Insurance Company is a corporation duly organized under the laws of the State of New Hampshire, that Liberty Mutual Insurance Company is a corporation duly organized under the laws of the State of Massachusetts, and West American Insurance Company is a corporation duly organized under the laws of the State of Indiana (herein collectively called the "Companies"), pursuant to and by authority herein set forth, does hereby name, constitute and appoint, Judith Miller; Annette M. Campbell; Janine Darling; Carolyn Evans; Mary E. Ficken; Loren B. Mahoney; Thomas W. Patton; Tristin Rosen; Virginia Shaw

all of the city of Greenwood Village, state of CO each individually if there be more than one named, its true and lawful attorney-in-fact to make, execute, seal, acknowledge and deliver, for and on its behalf as surety and as its act and deed, any and all undertakings, bonds, recognizances and other surety obligations, in pursuance of these presents and shall be as binding upon the Companies as if they have been duly signed by the president and attested by the secretary of the Companies in their own proper persons.

IN WITNESS WHEREOF, this Power of Attorney has been subscribed by an authorized officer or official of the Companies and the corporate seals of the Companies have been affixed thereto this 22nd day of January, 2018.



The Ohio Casualty Insurance Company  
Liberty Mutual Insurance Company  
West American Insurance Company

By: David M. Carey  
David M. Carey, Assistant Secretary

STATE OF PENNSYLVANIA ss  
COUNTY OF MONTGOMERY

On this 22nd day of January, 2018, before me personally appeared David M. Carey, who acknowledged himself to be the Assistant Secretary of Liberty Mutual Insurance Company, The Ohio Casualty Company, and West American Insurance Company, and that he, as such, being authorized so to do, execute the foregoing instrument for the purposes therein contained by signing on behalf of the corporations by himself as a duly authorized officer.

IN WITNESS WHEREOF, I have hereunto subscribed my name and affixed my notarial seal at King of Prussia, Pennsylvania, on the day and year first above written.



COMMONWEALTH OF PENNSYLVANIA  
Notarial Seal  
Teresa Pastella, Notary Public  
Upper Merion Twp., Montgomery County  
My Commission Expires March 28, 2021  
Member, Pennsylvania Association of Notaries

By: Teresa Pastella  
Teresa Pastella, Notary Public

This Power of Attorney is made and executed pursuant to and by authority of the following By-laws and Authorizations of The Ohio Casualty Insurance Company, Liberty Mutual Insurance Company, and West American Insurance Company which resolutions are now in full force and effect reading as follows:

**ARTICLE IV – OFFICERS** – Section 12. Power of Attorney. Any officer or other official of the Corporation authorized for that purpose in writing by the Chairman or the President, and subject to such limitation as the Chairman or the President may prescribe, shall appoint such attorneys-in-fact, as may be necessary to act in behalf of the Corporation to make, execute, seal, acknowledge and deliver as surety any and all undertakings, bonds, recognizances and other surety obligations. Such attorneys-in-fact, subject to the limitations set forth in their respective powers of attorney, shall have full power to bind the Corporation by their signature and execution of any such instruments and to attach thereto the seal of the Corporation. When so executed, such instruments shall be as binding as if signed by the President and attested to by the Secretary. Any power or authority granted to any representative or attorney-in-fact under the provisions of this article may be revoked at any time by the Board, the Chairman, the President or by the officer or officers granting such power or authority.

**ARTICLE XIII – Execution of Contracts** – SECTION 5. Surety Bonds and Undertakings. Any officer of the Company authorized for that purpose in writing by the chairman or the president, and subject to such limitations as the chairman or the president may prescribe, shall appoint such attorneys-in-fact, as may be necessary to act in behalf of the Company to make, execute, seal, acknowledge and deliver as surety any and all undertakings, bonds, recognizances and other surety obligations. Such attorneys-in-fact subject to the limitations set forth in their respective powers of attorney, shall have full power to bind the Company by their signature and execution of any such instruments and to attach thereto the seal of the Company. When so executed such instruments shall be as binding as if signed by the president and attested by the secretary.

**Certificate of Designation** – The President of the Company, acting pursuant to the Bylaws of the Company, authorizes David M. Carey, Assistant Secretary to appoint such attorneys-in-fact as may be necessary to act on behalf of the Company to make, execute, seal, acknowledge and deliver as surety any and all undertakings, bonds, recognizances and other surety obligations.

**Authorization** – By unanimous consent of the Company's Board of Directors, the Company consents that facsimile or mechanically reproduced signature of any assistant secretary of the Company, wherever appearing upon a certified copy of any power of attorney issued by the Company in connection with surety bonds, shall be valid and binding upon the Company with the same force and effect as though manually affixed.

I, Renee C. Llewellyn, the undersigned, Assistant Secretary, The Ohio Casualty Insurance Company, Liberty Mutual Insurance Company, and West American Insurance Company do hereby certify that the original power of attorney of which the foregoing is a full, true and correct copy of the Power of Attorney executed by said Companies, is in full force and effect and has not been revoked.

IN TESTIMONY WHEREOF, I have hereunto set my hand and affixed the seals of said Companies this 20th day of December, 2018.



By: Renee C. Llewellyn  
Renee C. Llewellyn, Assistant Secretary

Not valid for mortgage, note, loan, letter of credit, currency rate, interest rate or residual value guarantees.

To confirm the validity of this Power of Attorney call 1-610-832-8240 between 9:00 am and 4:30 pm EST on any business day.



Office of Economic Development  
 Division of Small Business Opportunity  
 201 W. Colfax Ave, Dept. 907  
 Denver, CO 80202  
 p: 720.913.1999  
 f: 720.913.1809  
[www.denvergov.org/dsbo](http://www.denvergov.org/dsbo)

## Diversity and Inclusiveness \* in City Solicitations Information Request Form

Type in your response, print out, sign and date; or print out and complete manually. Please print legibly.

Denver Executive Order No. 101 establishes strategies between the City and private industry to use diversity and inclusiveness to promote economic development in the City and County of Denver and to encourage more businesses to compete for City contracts and procurements. The Executive Order requires, among other things, the collection of certain information regarding the practices of the City's contractors and consultants toward diversity and inclusiveness and encourages/requires City agencies to include diversity and inclusiveness policies in selection criteria where legally permitted in solicitations for City services or goods.

Answer each question below. Missing or incomplete responses will be recorded as "no", "not applicable", or "none". A proposal or response to a solicitation by a contractor/consultant that does not include this completed form shall be deemed non-responsive and rejected.

Business Email Address: tylerv@keeneconcrete.com

Please include the Email address of the contact person facilitating this solicitation for the City and County of Denver: Debby.Gibson@denvergov.org

Agency Name:

- |   |  |  |
|---|--|--|
| <input type="checkbox"/> Arts and Venue               | <input type="checkbox"/> Purchasing Division     | <input type="checkbox"/> Sheriff Department  |
| <input type="checkbox"/> Auditor Office               | <input type="checkbox"/> Human Services          | <input type="checkbox"/> Technology Services |
| <input type="checkbox"/> Community Planning           | <input type="checkbox"/> Economic Development    | <input type="checkbox"/> Other               |
| <input type="checkbox"/> Denver International Airport | <input type="checkbox"/> Parks and Recreation    |  |
| <input type="checkbox"/> Environmental Health         | <input type="checkbox"/> Police Department       |  |
| <input type="checkbox"/> Fire Department              | <input checked="" type="checkbox"/> Public Works |  |

Project Name: 2018 Citywide Bond Concrete Repair

BID / RFP No.: 201845779

Name of Contractor/Consultant: Keene Concrete, Inc.

What industry is your business? Concrete Construction

Address:  
30263 WCR 8  
Keenesburg CO  
80643

Business Phone No.: 303-227-1901

Business Facsimile No.: 303-227-1904

OED - Executive Order No. 101  
 Diversity and Inclusiveness in City Solicitations Information Request Form  
 Rev. 12/29/2015

1. How many employees does your company employ?

- 1-10       51-100  
 11-50       over 100

1.1. How many of your company's employees are:

Full-time 55      Part-Time \_\_\_\_\_

2. Do you have a Diversity and Inclusiveness Program?  Yes       No

If No, and your company size is less than 10 employees continue to question 11. Complete and sign the form.

If Yes, does it address:

- 2.1 Employment and retention?       Yes       No  
2.2 Procurement and supply chain activities?       Yes       No  
2.3 Customer service?       Yes       No

3. Provide a detailed narrative of your company's diversity and inclusiveness principles and programs. This may include, for example, (i) diversity and inclusiveness employee training programs, equal opportunity policies, and the budget amount spent on an annual basis for workplace diversity; or (ii) diversity and inclusiveness training and information to improve customer service.

4. Does your company regularly communicate its diversity and inclusiveness policies to employees? No

If Yes, how does your company regularly communicate its diversity and inclusiveness policies to employees? (select all that apply)

- Employee Training  
 Pamphlets  
 Public EEO postings  
 Other  
 Not Applicable

5. If you responded that you do not have a diversity and inclusiveness program, describe any plans your company may have to adopt such a program.

None at this time

6. How often do you provide training in diversity and inclusiveness principles?

- Monthly                       Annually  
 Quarterly                     Not Applicable                       Other \_\_\_\_\_

6.1 What percentage of the total number of employees generally participate?

- 0 - 25%                       51 - 75%  
 26 - 50%                     76 - 100%                       Not Applicable

7. State how you achieve diversity and inclusiveness in supply and procurement activities. This may include, for example, narratives of training programs, equal opportunity policies, diversity or inclusiveness partnership programs, mentoring and outreach programs, and the amount and description of budget spent on an annual basis for procurement and supplier diversity and inclusiveness.

8. Do you have a diversity and inclusiveness committee?  Yes  No

8.1 If Yes, how often does it meet?

- Monthly                       Annually                       No Committee  
 Quarterly                     Other \_\_\_\_\_

8.2 If you responded that you do not have a diversity and inclusiveness committee, describe any plans your company may have to establish such a committee.

None at this time

9. Do you have a budget for diversity and inclusiveness efforts?  Yes  No

10. Does your company integrate diversity and inclusion competencies into executive/manager performance evaluation plans?  Yes  No

11. Would you like information detailing how to implement a Diversity and Inclusiveness program?  Yes  No

If yes, please email [X0101@denvergov.org](mailto:X0101@denvergov.org).

I attest that the information represented herein is true, correct and complete, to the best of my knowledge.

Gail Darnell 12/20/18  
Signature of Person Completing Form Date

Gail Darnell  
Printed Name of Person Completing Form

**NOTE: Attach additional sheets or documentation as necessary for a complete response.**

\*"Diversity and inclusiveness program" means a program that invites values, perspectives and contributions of people from diverse backgrounds, and integrates diversity into its hiring and retention policies, training opportunities, and business development methods to provide an equal opportunity for each person to participate, contribute, and succeed within the organization's workplace. "Diversity" encompasses a wide variety of human differences, including differences such as race, age, gender, gender identity, sexual orientation, ethnicity, physical disabilities, appearance, historically underutilized and disadvantaged persons, as well as social identities such as religion, marital status, socio-economic status, lifestyle, education, parental status, geographic background, language ability, and veteran status."



CITY AND COUNTY OF DENVER

STATE OF COLORADO



**DENVER**  
THE MILE HIGH CITY

DEPARTMENT OF PUBLIC WORKS

Bid Documents

Contract Number: 201845779



2018 Citywide Bond Concrete Repair

November 16, 2018

**CITY AND COUNTY OF DENVER**  
**DEPARTMENT OF PUBLIC WORKS**

**TABLE OF CONTENTS FOR CONTRACT DOCUMENTS**

<b>BID FORM AND SUBMITTAL PACKAGE</b>	<b><u>PAGE</u></b>
Bid Form and Submittal Package (bound separately and attached as part of these Bid Documents)	
Table of Contents	BF-1
Bidder's Checklist	BF-2 through BF-3
Bid Form and Submittal Package Acknowledgment Form	BF-4 through BF-5
Bid Form	BF-6 through BF-8
List of Proposed Minority and Woman Business Enterprise(s)	BF-9 through BF-12
Commitment to Minority and Woman Business Enterprise Participation	BF-13
Minority and Woman Business Enterprise Letter(s) of Intent & Checklist	BF-14 through BF-15
Joint Venture Affidavit	BF-16
Joint Venture Eligibility Form	BF-17 through BF-19
Bid Bond	BF-20
Diversity and Inclusiveness in City Solicitations Form	BF-21 through BF-24
<b>BID DOCUMENTS</b>	
Table of Contents	BDP-1
Statement of Quantities	SQ-1 through SQ-4
Notice of Invitation for Bids	BDP-2 through BDP-3
Instructions to Bidders	BDP-4 through BDP-15
Equal Employment Opportunity Provisions	BDP-16 through BDP-25
Appendix A	
Appendix F	
Contract Form	BDP-26 through BDP-30
Index of the General Contract Conditions	BDP-31 through BDP-35
Special Contract Conditions	BDP-36 through BDP-44
Final/Partial Release and Certificate of Payment Forms (Samples)	BDP-39 through BDP-41
Performance and Payment Bond Form	BDP-45 through BDP-46
Performance and Payment Bond Surety Authorization letter (Sample)	BDP - 47
Notice to Apparent Low Bidder (Sample)	BDP-48 through BDP-49
Notice To Proceed (Sample)	BDP-50
Certificate of Contract Release (Sample)	BDP-51
Prevailing Wage Rate Schedule	6 pages
Technical Specifications	TS-1 through TS-77



**DENVER**  
THE MILE HIGH CITY

**CITY AND COUNTY OF DENVER**  
**DEPARTMENT OF PUBLIC WORKS**  
**201845779**  
**2018 Citywide Bond Concrete Repair**

**STATEMENT OF QUANTITIES**

<u>Item No.</u>	<u>Description</u>	<u>Estimated</u>	<u>Quantity</u>
202-00019	REMOVAL OF INLET	10	EA
202-00033	REMOVAL OF SIPHON	10	EA
202-00200	REMOVAL OF SIDEWALK	3,750	SY
202-00201	REMOVAL OF CURBHEAD	2,000	LF
202-00203	REMOVAL OF CURB AND GUTTER	5,500	LF
202-00204	REMOVAL OF COMBINATION CURB, GUTTER AND WALK	4,000	LF
202-00208	REMOVAL AND RESET FLAGSTONE (INCLUDES SALVAGE AND STORAGE)	500	SY
202-00210	REMOVAL OF CONCRETE PAVEMENT	2,500	SY
202-00220	REMOVAL OF ASPHALT MAT	7,500	SY
202-01000	REMOVAL OF FENCE	500	LF
202-05021	TRIP HAZARD SAWING (>5 LOCATIONS 1 MONTH COMPLETION)	100	IN-FT
202-05020	TRIP HAZARD SAWING (<= 5 LOCATIONS 1 WEEK COMPLETION)	100	IN-FT
203-00200	UNCLASSIFIED EXCAVATION	2,500	CY
203-02330	3-MAN LABOR CREW	300	HR
206-00065	STRUCTURE BACK FILL (FLOW FILL)	150	CY
208-00050	STORM DRAINAGE INLET PROTECTION	750	EA
210-00810	RESET GROUND SIGN	250	EA



**DENVER**  
THE MILE HIGH CITY

**CITY AND COUNTY OF DENVER**  
**DEPARTMENT OF PUBLIC WORKS**  
**201845779**  
**2018 Citywide Bond Concrete Repair**

**STATEMENT OF QUANTITIES**

<u>Item No.</u>	<u>Description</u>	<u>Estimated</u>	<u>Quantity</u>
210-04010	ADJUST MANHOLE/METER/VALVE/PULLBOX	60	EA
210-04011	ADJUST INLET FRAME AND ADJUSTABLE CURBHEAD	60	EA
210-04020	RESET INLET GRATE,FRAME, AND ADJUSTABLE CURB BOX (NEW CASTING)	100	EA
212-00050	SODDING	500	SF
212-01200	RESTORE LANDSCAPING	2,500	SF
212-01201	AMENDED TOP SOIL OR LANDSCAPE PLANTER'S SOIL MIX	250	CY
304-06000	AGGREGATE BASE COURSE	1,000	TON
403-00720	HBP PATCH/OVERLAY	2,000	TON
412-00000	24-HOUR HIGH EARLY STRENGTH CONCRETE	2,400	CY
412-00001	ADD PIGMENT TO CONCRETE	100	CY
412-00100	GEO TECH MATERIAL TESTING CONCRETE	50	EA
412-00400	4" CONCRETE PAVEMENT	150	SY
412-00600	6" CONCRETE PAVEMENT	2,500	SY
412-00800	8" CONCRETE PAVEMENT	500	SY
412-01000	10" CONCRETE PAVEMENT	200	SY
412-01200	12" CONCRETE PAVEMENT	200	SY
413-00100	CONCRETE PATCHING (STRUCTURAL SURFACE REPAIR <2" DEPTH)	200	SF-IN



**DENVER**  
THE MILE HIGH CITY

**CITY AND COUNTY OF DENVER**  
**DEPARTMENT OF PUBLIC WORKS**  
**201845779**  
**2018 Citywide Bond Concrete Repair**

**STATEMENT OF QUANTITIES**

<u>Item No.</u>	<u>Description</u>	<u>Estimated</u>	<u>Quantity</u>
601-00100	PAVESTONE STACKED PRE-CAST WALL BLOCK	500	SF
601-00400	REINFORCED VARIABLE HEIGHT CONCRETE RETAINING WALL	1,500	SF
601-06150	CONCRETE PATCHING (STRUCTURAL CURB REPAIR)	500	LF
603-01150	15" REINFORCED CONCRETE PIPE (RCP)	50	LF
603-01180	18" REINFORCED CONCRETE PIPE (RCP)	50	LF
604-14050	NUMBER 14 INLET (L=6')	10	EA
604-16050	SINGLE NUMBER 16 INLET	10	EA
608-00000	CONCRETE SIDEWALK	2,500	SY
608-00010	CONCRETE CURB RAMP	8,500	SY
608-00018	TRUNCATED DOMES (SPECIAL CAST IRON) MATERIAL ONLY	500	SF
609-20000	CONCRETE GUTTER OVERLAY	3,000	LF
609-21020	CURB & GUTTER TYPE II, SECTION 2B	5,500	LF
609-21023	CURB & GUTTER TYPE IIB (9") CURBHEAD	300	LF
609-22021	COMBINATION CURB, GUTTER & SIDEWALK (2- '8")	3,500	LF
609-22025	COMBINATION CURB, GUTTER & SIDEWALK (3'-11")	400	LF
610-00026	MEDIAN COVER MATERIAL (6" PATTERNED COLORED CONCRETE)	100	SY



**DENVER**  
THE MILE HIGH CITY

**CITY AND COUNTY OF DENVER**  
**DEPARTMENT OF PUBLIC WORKS**  
**201845779**  
**2018 Citywide Bond Concrete Repair**

**STATEMENT OF QUANTITIES**

<u>Item No.</u>	<u>Description</u>	<u>Estimated</u>	<u>Quantity</u>
613-07000	RESET PULL BOX	50	EA
614-72875	LOOP DETECTOR WIRE	50	LF
623-00204	SPRINKLER SYSTEM/ADJUST SPRINKLER HEAD	500	EA
623-00205	SPRINKLER SYSTEM/NEW SPRINKLER HEAD	500	EA
623-00505	SPRINKLER SYSTEM/IRRIGATION RECONSTRUCTION	7,500	LF
630-00000	TRAFFIC CONTROL - ARTERIAL/COLLECTOR	50	DAY
630-00002	TRAFFIC CONTROL - LOCAL	100	DAY
630-00003	TRAFFIC CONTROL - UNIFORMED TRAFFIC CONTROL	20	HR

**CITY AND COUNTY OF DENVER  
DEPARTMENT OF PUBLIC WORKS**

**NOTICE FOR INVITATION FOR BIDS  
FOR CONTRACT NO. 201845779**

**2018 CITYWIDE BOND CONCRETE REPAIR**

**BID SCHEDULE:  
11:00 a.m., Local Time  
DECEMBER 20, 2018**

Sealed bids will be received in Room 6.G.7, 201 W. Colfax Ave., Denver, CO 80202, beginning at 10:30 a.m., no later than 11:00 a.m., on bid day. All properly delivered bids will then be publicly opened and read aloud.

Bids submitted prior to 10:30 a.m. on the specified bid opening date/time shall be presented at the Office of Contract Administration, Attention: Public Works Contract Administration, 201 W. Colfax Ave., Department 614, Denver, CO 80202.

Prior to submitting a bid, the bidder shall consult the Contractor's Bulletin Board located at 201 W. Colfax Ave., 2<sup>nd</sup> Floor, Denver, CO 80202 and/or [www.work4denver.com](http://www.work4denver.com).

**ABOUT ELEVATE DENVER BOND PROGRAM:**

Elevate Denver is a 10-year, \$937 million general obligation bond program approved by voters in 2017, that will enhance the City and County of Denver by providing critical improvements to the city's infrastructure – improving our roads, sidewalks, parks, recreation centers, libraries, cultural centers, public-owned buildings, and safety facilities.

**GENERAL STATEMENT OF WORK:**

Remove and replace damaged curb and gutter and curb and out of compliance curb ramps on stretches of arterial/collector streets throughout Denver.

**ESTIMATED CONSTRUCTION COST:**

The estimated cost of construction for this project is between \$2,659,000 and \$3,250,000.

**TEXTURA CONSTRUCTION PAYMENT MANAGEMENT:**

Bidders are required, when preparing a bid, to agree it shall use the Textura® Construction Payment Management System (“Textura”) to request payment from the City and to pay subcontractors. All certified subcontractors or suppliers who are listed for participation towards any assigned program goal must be paid via Textura. All fees associated with Textura are to be paid by the awarded Contractor. Bidders shall use the pricing scale provided in Instructions to Bidders to price the Textura service appropriately. For details on the company and service, contact the Textura® Corporation at 866-TEXTURA or [www.texturacorp.com](http://www.texturacorp.com).

**DOCUMENTS AND BID INFORMATION AVAILABLE:**

Contract Documents complete with Technical Specifications and, if applicable, construction drawings will be available on the first day of publication at: [www.work4denver.com](http://www.work4denver.com). To download digital Contract Documents at a cost of \$15.00 per download, reference eBid Document Number #6013633. Contact QuestCDN at 952-233-1632 or [info@questcdn.com](mailto:info@questcdn.com) for assistance.

**PRE-BID CONFERENCE:**

A pre-bid conference will be held for this Project at 2:00 p.m., local time, on November 28, 2018. This meeting will take place at: 201 W. Colfax Ave., Room 4.I.5, Denver, CO 80202.

**DEADLINE TO SUBMIT QUESTIONS:** December 5, 2018 by 2:00 p.m. local time.

**PREQUALIFICATION REQUIREMENTS:**

Each bidder must be prequalified as a 1F(2) Concrete in the \$3M monetary level in accordance with the City’s Rules and Regulations Governing Prequalification of Contractors. Each bidder must have submitted a prequalification application a minimum of ten (10) calendar days prior to the bid opening date. Applications must be submitted to the Department of Public Works, Prequalification Section, 201 W. Colfax Ave., Department 614, Denver, CO 80202. To view the Rules and Regulations and to obtain a prequalification application, please visit our website at [www.denvergov.org/prequalification](http://www.denvergov.org/prequalification) or call 720-865-2539 for prequalification information ONLY.

**MINORITY AND WOMAN BUSINESS ENTERPRISE PARTICIPATION:**

Construction, reconstruction and remodeling contracts made and entered into by the City and County of Denver are subject to Article III, Divisions 1 and 3 of Chapter 28 of the Denver Revised Municipal Code, (Sections 28-31 to 28-36 and 28-52 to 28-90 D.R.M.C) and all Minority and Woman Business Enterprise and Equal Employment Opportunity Rules and Regulations adopted by the Director of the Division of Small Business Opportunity.

Article III, Division 3 of Chapter 28 of the D.R.M.C. directs the Director of the Division of Small Business Opportunity to establish a project goal for expenditures on construction, reconstruction, and remodeling work contracted by the City and County of Denver. The specific goal for this project is:

**20% Minority and Woman Business Enterprise (M/WBE) Participation**

Project goals must be met with certified participants as set forth in Section 28-60, D.R.M.C. or through the demonstration of a sufficient good faith effort under Section 28-62 D.R.M.C. For compliance with good faith requirements under Section 28-62(b), **the M/WBE percentage solicitation level required for this project is 100%.**

The Director of the Division of Small Business Opportunity urges all participants in City construction, reconstruction and remodeling projects to assist in achieving these goals.

**MISCELLANEOUS:**

Contracts for construction, reconstruction, and remodeling are subject to the City prevailing wage rate requirements established pursuant to Section 20-76, D.R.M.C.

As its best interest may appear, the City and County of Denver reserves the right to reject any or all bids and to waive informalities in bids.

A modified version of this Notice of Invitation for Bids and the project’s Statement of Quantities is available on the City and County of Denver’s website at: [www.work4denver.com](http://www.work4denver.com).

Publication Dates: November 16, 19, 20, 2018  
Published In: The Daily Journal



**CITY AND COUNTY OF DENVER**  
**DEPARTMENT OF PUBLIC WORKS**

**INSTRUCTIONS TO BIDDERS**

**IB-1 INSTRUCTION TO BIDDERS**

These Instructions to Bidders are a part of the Contract Documents and are intended to serve as a guide to bidders. They are general in nature and may be amended or supplemented as needed to support any one specific invitation to bid. Each bidder shall prepare its bid in strict compliance with all requirements of the Contract Documents and by careful application of these instructions.

**IB-2 BIDDING**

The copy of the Contract Documents contains the Bid Form and Submittal Package for this Project, which must be used to submit a bid hereunder. The bidder must fully complete, execute and submit this Bid Form and Submittal Package, along with any other specified components of the Contract Documents, as its bid for the referenced Project.

A bidder is not required to submit as part of its bid the entire set of Contract Documents distributed by the City pursuant to the Notice of Invitation for Bids, if the bidder executes and submits the Bidder Acknowledgment Form included with the Bid Form and Submittal Package as part of its bid. However, each bidder, by submitting its bid, shall be conclusively presumed to have received and reviewed all of the information contained in the Contract Documents as this term is further defined herein.

Each bid must be enclosed in a sealed envelope, must be addressed to the Manager and must show on the face of the envelope the full name of the bidder, the City Project number, and descriptive title of the Project for which the bid is made.

The advertisement for Notice of Invitation for Bids will identify where and when the bid must be delivered.

**IB-3 CONTRACT DOCUMENTS AS PUBLISHED BY CITY**

Each bidder shall be responsible for, and shall be deemed to have received, all the information contained in the Contract Documents as distributed by the City pursuant to the Notice of Invitation for Bids, including addenda, whether or not such bidder has reviewed all or part of the Contract Documents in either its hard copy form or in any other format. If organizations or companies other than the City or its design professional distribute the City's Contract Documents for review by prospective bidders, whether in hard copy or via electronic or other media, neither the City nor its design professional shall be responsible for the content, completeness or accuracy of any information distributed or transmitted by any such organization or company.

**IB-4 COMPLETING AND SIGNING THE BID FORMS**

The bidder must complete the Bid Form by legibly writing or printing in ink, in words and figures as required, all the bidder's prices offered for the Work to be performed. All blank spaces, which require a response of the bidder, must be properly completed in full. If in the process of evaluating a bid, words and figures, as written on the Bid Form by the bidder, do not agree, the written words will govern.

For Bid Forms requiring unit price bids, the bidder shall write in the Bid Form spaces provided a unit price for each item for which a quantity is given and shall also write the product of each unit price and the quantity specified in the "Amount" or "Total" space provided.

Each bidder must sign the Bid Form and give the bidder's current business address. If an individual, the signature must be of the individual offering the bid; if a partnership, the signature must be that of a general partner; and if a corporation, both the president and the secretary must sign and the seal of the corporation must be affixed. Signatures of other persons may be acceptable if the bid contains sufficient evidence, satisfactory to the City in its sole discretion, to indicate that the other persons are authorized to bind the bidder.

**IB-5 UNACCEPTABLE BIDS**

The City will not accept bids from Bidders not prequalified with the Department of Public Works (if prequalification is required for this project), in arrears to the City upon debt or contract, or which are defaulters (as surety or otherwise) upon any obligation to the City.

**IB-6 INFORMAL AND UNBALANCED BIDS**

Any alteration, interlineations, erasure, omission, deletion or addition by the bidder to the Bid Form and Submittal Package or other parts of the Contract Documents submitted with the Bid Form and Submittal Package, as originally issued to the bidder, shall render the accompanying bid informal and may constitute cause for rejection.

Any unauthorized addition, conditional or alternate bids, failure to provide a unit price, lump sum amount or authorized alternate item specified or other irregularities of any kind which tend to render the bid incomplete, indefinite or ambiguous shall render the bid informal and may constitute cause for rejection.

Bids that are unbalanced so that each item does not reasonably carry its own proportion of cost or that contain inadequate or unreasonable prices for any item may be rejected. Bids, which have not acknowledged all addenda to the Contract Documents issued for this bid, may also be rejected.

The right is reserved by the City to reject any or all bids and to waive any informalities where it is deemed by the City to be in the best interests of the City to do so.

**IB-7 ONLY ONE BID ACCEPTED**

The City will accept only one bid for the same work from any one bidder. This includes bids that may be submitted under different names by one business enterprise.

**IB-8 BID GUARANTEE**

As a guarantee of good faith on the part of the bidder, each bid must be accompanied by a bid guarantee, consisting of either a certified or cashier's check made payable without condition to the order of the City and County of Denver or a bid bond written by an approved corporate surety in favor of the City and County of Denver. If the bid of a bidder is acceptable and the bidder is notified by the Manager that it is considered to be the Apparent Low Bidder and said bidder fails to execute a contract in the form prescribed or to furnish a performance and payment bond with a legally responsible and approved surety or to furnish the required evidence of insurance or satisfy all conditions precedent to contract execution within five (5) days after such notice is made by the City, said bid guarantee shall be forfeited to the City as liquidated damages and not as a penalty.

The bid guarantee shall be in the amount of five percent (5%) of the total bid unless otherwise specified in the Notice of Invitation for Bids and on the form appearing in the Contract Documents in the Bid Form and Submittal Package. Failure to submit a properly executed bid guarantee, on the form provided herein may, in the City's sole discretion, constitute cause for rejection.

Following award and execution of the Contract by the Apparent Low Bidder, or earlier in the sole discretion of the City, bid guarantees of all but the Apparent Low Bidder will be returned. When the Apparent Low Bidder executes the Contract and delivers to the City satisfactory performance and payment bonds, required insurance documentation, and has satisfied all conditions precedent to contract execution by the City, and after approval, if any, by the Council of the City of the proposed Contract with the Apparent Low Bidder, the bid guarantee of the Apparent Low Bidder shall be returned. Such return shall be made within one hundred twenty (120) days from date bids are opened unless otherwise specified in the Special Contract Conditions.

**IB-9 SITE INSPECTION AND INVESTIGATIONS**

Prior to submitting a bid, the bidder is invited to inspect the work site and its surroundings. Although the bidder is not required to make such an inspection before bidding, for purposes of the Contract it shall be conclusively presumed that by failing to make such an inspection, the bidder has waived the right to later claim additional compensation or time extensions for conditions which would have been evident had the site been inspected.

Drawings and Technical Specifications, defining the Work to be done, were prepared on the basis of interpretation by the design professionals of information derived from investigations of the work site. Such information and data are subject to sampling errors, and the interpretation of the information and data depends to a degree on the judgment of the design professional. In view of this, the bidder is invited to make such additional investigations as the bidder's judgment dictates the need for such investigations. Information about the degree of difficulty of the Work to be done cannot totally be derived from either the Drawings or Technical Specifications or from the Manager or his representatives.

Since the bid information cannot be guaranteed, the Contractor shall have assumed the risks attendant to successful performance of the Work and shall never make claim for additional compensation or time extensions on the grounds that the nature or amount of work to be done was not understood by the bidder at the time of the bidding.

**IB-10 INCONSISTENCIES**

Any seeming inconsistencies or ambiguities between different provisions of the Contract Documents or any point which the bidder believes requires a decision or interpretation by the City must be inquired into by the bidder by addressing a formal written communication to the Manager of Public Works and sending or delivering it to the offices of the Division of Public Works advertising this Project for bid at least forty-eight (48) hours, excluding Saturdays, Sundays, and holidays, before the time set for the opening of bids

Information about the decision or interpretation made in response to any inquiry will be posted on the Contractor's Bulletin Board (refer to IB-12 CONTRACTOR'S BULLETIN BOARD, for the location of the Contractor's Bulletin Board). If the matter raised requires, in the sole discretion of the Manager, that an addendum to the bid documents be issued, such addendum will be published and each bidder shall be required to acknowledge the addendum by signing and identifying it in the Bid Form when submitting the bid.

After bids are opened, all bidders must abide by the formal response of the Manager, as to any interpretation. The City shall not be bound and the bidder shall not rely on any oral communication, interpretation clarification or determination of the Contract Documents prior to bid opening.

**IB-11 WITHDRAWAL OF BID**

A bidder may withdraw its bid at any time prior to the time for receipt of bids set forth in the Notice of Invitation for Bids by making written request upon the Manager of Public Works. After such time, no bid may be withdrawn or modified.

Such request must be signed by the persons authorized to bind the bidder as defined in IB-3, COMPLETING AND SIGNING BID FORMS.

**IB-12 CONTRACTOR'S BULLETIN BOARD**

It shall be conclusively presumed that the bidder has, before submitting any bid, read and shall take full responsibility for all addenda, posted decisions, and other information relevant to the bid posted by the City on the Contractor's Bulletin Board. The Contractor's Bulletin Board is located at 201 W. Colfax, 2<sup>nd</sup> Floor, Denver, CO 80202, in the Wellington E. Webb Municipal Office Building.

**IB-13 PRE-BID MEETING**

Bidders are urged to attend the pre-bid meeting(s) scheduled for this Project. Attendance is not mandatory; however, bidders will be held responsible for all information presented at such meeting(s).

**IB-14 ADDENDA**

As its best interests may require, the City may issue addenda to the Contract Documents. Such addenda shall be posted on the Contractor's Bulletin Board and made available to all persons having purchased a set of Contract Documents as set forth in the Notice of Invitation for Bids contained herein. All bidders must acknowledge receipt of all addenda on the Bid Form at the time of submission of the bid.

**IB-15 BID OPENING**

Bidders are invited to be present at the bid opening. Unless otherwise suspended, delayed or canceled by posted notice from the Manager, bid opening will occur at the time and place designated in the Notice of Invitation for Bid.

**IB-16 EVALUATION OF BIDS AND BASIS OF BID SELECTION**

Bids will be evaluated after being read in open meeting at the place designated for such bid opening. All low bidders' bids will be reviewed for responsiveness to the requirements of the Contract Documents and whether or not the bids contain irregularities which could give any bidder an unfair advantage.

Selection will be made on the basis of the lowest, total, responsive, qualified bid, which bid shall include the total base bid set forth on the Bid Form, plus the total of any alternates set forth on the Bid Form and selected by the City during evaluation. Alternates, if any are included in the bid, will be selected in the priority shown on the Bid Form, subject to the limits of available funds. Bid selection will be subject to all requirements and special bidder qualifications contained herein and subject to approval of such resulting Contract in accordance with the Charter and Revised Municipal Code of the City and County of Denver. In addition to all other specified requirements, the City will correct arithmetical errors in all bids and corrected totals only will be considered as the basis of selection.

Upon concluding that the bid is, in fact, the lowest, total, responsive bid to the bidding conditions and that of a responsible, qualified bidder, the City will notify the Apparent Low Bidder.

As its best interests may appear, the City and County of Denver reserves the right to waive informalities in bids, to reject any and all bids and to rebid the Project.

**IB-17 NOTICE TO APPARENT LOW BIDDER**

The Notice to Apparent Low Bidder, a form of which is included in the Contract Special Conditions Section of the Contract Documents, is issued by the City directly to the selected bidder and informs the bidder that the Manager intends to seek approval of the execution of the Contract by the City in accordance with the Charter and Revised Municipal Code of the City and County of Denver. Specifically, it informs the bidder of its obligations with respect to execution of the Contract and instructs the bidder on how to proceed toward execution of the Contract. The City reserves the right to notify the Apparent Low Bidder, at any time within one hundred twenty (120) days from the date of the opening of the bids, that approval to contract with the Apparent Low Bidder shall be sought in accordance with the Charter and Revised Municipal Code of the City and County of Denver.

In accordance with the terms and conditions contained in the Bid Form and Submittal Package and any additional requirements set forth in the Notice to Apparent Low Bidder or elsewhere in the Contract Documents, the Apparent Low Bidder shall execute the Contract Form contained in the Contract Documents made available by the City for execution in the appropriate number of counterparts. The Apparent Low Bidder shall return the fully executed Contract Document sets, along with any supplemental documents required herein, to the City and shall comply with all other conditions precedent to Contract execution within five (5) days of the date of issuance of the Notice to Apparent Low Bidder by the City. Failure to comply with each of these requirements within five (5) days of the date of issuance of the Notice to Apparent Low Bidder by the City shall render the bid nonresponsive and may constitute cause for rejection.

Issuance of such Notice shall not, however, constitute a commitment on the part of the City or create any rights in the Apparent Low Bidder to any contract with the City.

**IB-18 EXECUTION OF CONTRACT**

The process of executing a contract requires action by both the apparent low bidder and the City. After it notifies the Apparent Low Bidder, the City will prepare the Contract Documents by incorporating all of the documents submitted by the Apparent Low Bidder into one or more executable copies. Upon notification that contracts documents are ready for execution the Apparent Low Bidder shall execute the contract documents. At this time, the successful bidder shall also provide certain supplemental documents for incorporation into the Contract Documents. These supplemental documents shall include: the properly executed Certificate of Insurance Forms evidencing the apparent low bidder's satisfactory compliance with the insurance requirements set forth in the Contract Documents; a properly executed Payment and Performance Bond Form and appropriate Power of Attorney evidencing the Apparent Low Bidder's satisfactory compliance with the bonding requirements set forth in the Contract Documents; and documentation of compliance with any other conditions precedent to execution of the Contract by the City set forth in the Contract Documents. The insurance and bond forms contained in the Contract Special

Conditions Section of the Contract Documents must be used in satisfying these supplemental document requirements.

These documents are then delivered to the City within the prescribed time period for examination of the documents to determine whether or not the Contractor has correctly executed the Contract and has correctly provided the required supplemental documents and that these documents are satisfactorily and properly completed. From here, all of the documents are forwarded to the City Attorney who will, if the insurance and bonding offered is acceptable and if all other elements of the Contract Documents are in order, recommend that the Manager and the Mayor approve the documents and, when required by the City Charter, prepare an ordinance for submittal to City Council authorizing the execution of the Contract. The City Attorney shall in all applicable instances submit the proposed contract and ordinance to City Council. After City Council approval, the Contract shall be reviewed by the City Attorney and routed for execution by the Mayor, the Clerk for attestation and the Auditor for countersignature and registration. When the total process of contract execution is complete, a Notice to Proceed will be issued and a single executed copy of the Contract will be delivered to the Contractor. Any work performed or a material purchased prior to the issuance of Notice to Proceed is at the Contractor's risk.

**IB-19 BONDING REQUIREMENTS**

In accordance with the provisions of General Contract Conditions, Title 15, PERFORMANCE AND PAYMENT BONDS, the minimum bonding requirements for this Contract are set forth in the form **CITY AND COUNTY OF DENVER PERFORMANCE AND PAYMENT BOND** contained in the Special Conditions Section of the Contract Documents. Upon receipt of Notice to Apparent Low Bidder, the apparent low bidder must cause this form bond to be purchased, executed and furnished, along with appropriate Powers of Attorney and a surety authorization letter (in form similar to the one attached), to the City in accordance with the instructions contained herein.

**IB-20 INSURANCE REQUIREMENTS**

The minimum insurance requirements for this Contract are set forth in the Special Conditions Section of the Contract Documents. Bidders are urged to consider, in preparing a bid hereunder, that each condition, requirement or specification set forth in the form certificate must be complied with by the Contractor and all subcontractors performing Work on the Project, unless such requirements are specifically accepted in writing by the City's Risk Management Office. The Contractor must either include all subcontractors performing work hereunder as insureds under each required policy or furnish a separate certificate for each subcontractor. In either case, the Contractor shall insure that each subcontractor complies with all of the coverage requirements.

**IB-21 PERMITS AND LICENSES**

All permits, licenses and approvals required in the prosecution of the work shall be obtained and paid for by the Contractor.

**IB-22 PREVAILING WAGE REQUIREMENTS**

Contractor shall comply with, and agrees to be bound by, all requirements, conditions and City determinations regarding the Payment of Prevailing Wages Ordinance, Sections 20-76 through 20-79, D.R.M.C. including, but not limited to, the requirement that every covered worker working on a City owned or leased building or on City-owned land shall be paid no less than the prevailing wages and fringe benefits in effect on the date the bid or request for proposal was advertised. In the event a request for bids, or a request for proposal, was not advertised, Contractor shall pay every covered worker no less than the prevailing wages and fringe benefits in effect on the date funds for the contract were encumbered.

Date bid or request for qualifications/proposals was advertised: November 16, 2018.

Prevailing wage and fringe rates will adjust on, and only on, the anniversary of the date the Contract was fully executed. Unless expressly provided for in this Agreement, Contractor will receive no additional compensation for increases in prevailing wages or fringe benefits.

Contractor shall provide the Auditor with a list of all subcontractors providing any services under the contract.

Contractor shall provide the Auditor with electronically-certified payroll records for all covered workers employed under the contract.

Contractor shall prominently post at the work site the current prevailing wage and fringe benefit rates. The posting must inform workers that any complaints regarding the payment of prevailing wages or fringe benefits may be submitted to the Denver Auditor by calling 720-913-5000 or emailing [auditor@denvergov.org](mailto:auditor@denvergov.org).

If Contractor fails to pay workers as required by the Prevailing Wage Ordinance, Contractor will not be paid until documentation of payment satisfactory to the Auditor has been provided. The City may, by written notice, suspend or terminate work if Contractor fails to pay required wages and fringe benefits.

#### **IB-23 TAX REQUIREMENTS**

General. Bidders are referred to the General Contract Condition 323, TAXES, as to taxes to which they may be subject in performing the Work under this Contract, including but not limited to sales and use taxes and the Denver Occupational Privilege Tax. The following instructions are to be considered along with the General Contract Conditions and not in lieu of them.

Sales and Use Tax. Construction and building materials sold to contractors and subcontractors for use on structures, roads, streets, highways, and other public works owned by the City and County of Denver are exempt from state, RTD, and Cultural Facilities District sales and use taxes. However, such materials will be subject to sales and use taxes imposed by the City and County of Denver.

It is the responsibility of the Contractor and its subcontractors to apply to the Colorado Department of Revenue (“CDOR”) for a certificate, or certificates, of exemption indicating that their purchase of construction or building materials is for a public project, and to deliver to the City copies of such applications as soon as possible after approval by the CDOR. Bidders shall not include in their bid amounts the exempt state, RTD, and Cultural Facilities District Sales and Use Taxes.

Denver Occupational Privilege Tax. Any employee working for a contractor, or a subcontractor, who earns over \$500 working in Denver during a calendar month, is subject to the payment of the Employee Occupational Privilege Tax. The Contractor and any subcontractor must pay the Business Occupational Privilege Tax for each of its employees who are subject to such tax.

#### **IB-24 DIVERSITY AND INCLUSIVENESS IN CITY SOLICITATIONS**

Each bidder shall, as a condition of responsiveness to this solicitation, complete and return the “Diversity and Inclusiveness in City Solicitations Information Request Form” with their Bid.

Using the “Diversity and Inclusiveness in City Solicitations Information Request Form” provided, please state whether you have a diversity and inclusiveness program for employment and retention, procurement and supply chain activities, or customer service and provide the additional information requested on the form. The information provided on the “Diversity and Inclusiveness in City Solicitations Information Request Form” will provide an opportunity for City contractors to describe their own diversity and inclusiveness practices. Contractors are not expected to conduct intrusive examinations of its employees, managers, or business partners in order to describe diversity and inclusiveness measures. Rather, the City simply seeks a description of the contractor’s current practices, if any.

Diversity and Inclusiveness information provided by City contractors in response to City solicitations for services or goods will be collated, analyzed, and made available in reports consistent with City Executive Order No. 101. However, no personally identifiable provided by or obtained from contractor’s will be in such reports.

#### **IB-25 MINORITY AND WOMAN BUSINESS ENTERPRISE (M/WBE) REQUIREMENTS**

Article III, Divisions 1 and 3 of Chapter 28, Denver Revised Municipal Code (D.R.M.C.), designated as Sections 28-31 – 28-36 and 28-52 – 28-90 D.R.M.C. and referred to in these Bid Documents as the “M/WBE Ordinance” and any Rules or Regulations promulgated pursuant thereto apply to this Project and are incorporated into these Bid Documents by reference. Generally, the M/WBE Ordinance provides for the adoption of a good faith goals program, to be administered by the Division of Small Business Opportunity (DSBO), devised to provide increased bidding opportunities for Minority and Woman Business Enterprises

(M/WBEs). As such, each bidder must comply with the terms and conditions of the M/WBE Ordinance in making its bid and, if awarded the Contract, in performing all Work thereunder. A bidder's failure to comply with the M/WBE Ordinance, any Rules or Regulations promulgated pursuant thereto, or any additional requirement contained herein shall render the bid non-responsive and shall constitute cause for rejection. Failure by the contractor awarded the contract to comply with M/WBE Ordinance requirements during the performance of the contract is a material breach of the contract, which may result in the in the imposition of sanctions on the Contractor, as deemed appropriate by DSBO. Copies of the M/WBE Ordinance and its accompanying Rules and Regulations are available for the use and review of bidders from DSBO. In order to comply with the bid requirements of the M/WBE Ordinance, a bidder shall either meet the established project goal or, in the alternative, demonstrate that the bidder has made sufficient good faith efforts to meet the goal in accordance with the M/WBE Ordinance.

### **Meeting Established Goal**

In preparing a bid to meet the established Project goal, bidders should consider the following instructions relating to compliance with the M/WBE Ordinance:

1. Under the M/WBE Ordinance, the Director of DSBO ("Director") is directed to establish project goals for expenditures on construction, reconstruction, and remodeling work performed for the City and County of Denver. The specific goal for this project is stated in the Notice of Invitation for Bids bound herein.
2. In preparing its bid, each bidder shall list on the Bid Form pages entitled "List of Proposed MWBE Bidders, Subcontractors, Suppliers, Manufacturers, Manufacturers' Representatives or Brokers" the name, address, work description/supply, committed level of participation and other required information for each M/WBE of any tier which the bidder intends to use in performing the work on this Project. **Only the M/WBEs identified and the precise levels of participation listed for each on the Bid Form page, at the time of bid opening, will be considered in determining whether the bidder has met the designated participation goal. Additional, revised or corrected participation submitted after bid opening will not be considered.** M/WBE bidders may count self-performance or joint venture activity in meeting the M/WBE project goal, but only for the scope of work performed as a commercially useful function and at a percentage level the M/WBE will be performing itself.
3. Any agreement between a bidder or proposer and an MBE or WBE in which the bidder or proposer requires that the MBE or WBE not provide subcontracting quotations to other bidders or proposers is prohibited and shall render a bidder's bid or proposer's proposal nonresponsive. D.R.M.C. 28-63(f)
4. If a bidder/proposer is participating in a joint venture with a certified M/WBE firm, complete the Joint Venture Eligibility Form and Joint Venture Affidavit contained in this bid document/RFP. Submit the aforementioned forms with the firm's Joint Venture Agreement, to the DSBO Director, **at least 10 working days prior to the proposal submittal.** The Joint Venture must be approved prior to the bid opening or proposal submittal by the DSBO Director. Approval by the DSBO Director includes determining the amount the Joint Venture will count towards meeting the project goal.
5. All M/WBEs listed on the Bid Form must be properly certified by the City on or before the date bids are opened in order to count towards meeting the designated goal. DSBO maintains an M/WBE Directory ("Directory"), which is a current listing of M/WBEs that have been certified by the City. A copy of the DSBO Directory is located at DSBO web site at <https://www.denvergov.org/dsbo>. Bidders are encouraged to use the Directory to assist in locating M/WBEs for the work and supplies required on the Project. Bidders are reminded that changes may be made to the Directory at anytime in accordance with the City's M/WBE Ordinance and procedures established to administer this program and a current copy of the Directory must always be used in preparing a bid. M/WBE certification or listing in the Directory is not a representation or warranty by the City as to the qualifications of any listed M/WBE.

6. In accordance with the provisions of the M/WBE Ordinance, DSBO will evaluate each bid to determine the responsiveness of the bid to the requirements of the M/WBE Ordinance. In determining whether a bidder's committed level of participation meets or exceeds the stated M/WBE goal, DSBO shall base its calculation of applicable amounts and percentages on the total base bid amount, not including any listed alternates, of each bid as follows:
  - a. The bid information provided by the agency will be used to determine the total base bid amount of each bid. Each bidder's total base bid amount will be multiplied by the M/WBE percentage established for the project to determine the exact dollar amount of required M/WBE participation for the Project. This amount will then be compared against the exact dollar amounts for the M/WBE committed for participation by the bidder. If the total dollar amount of participation listed meets or exceeds the established M/WBE dollar amount goal listed, then DSBO will determine that the goal has been met.
  - b. In addition, DSBO will determine the exact commitment percentage for each listed M/WBE by dividing the dollar amount listed for each M/WBE by the total base bid dollar amount submitted by the bidder. These individual percentages, when totaled for all listed M/WBE, will establish the total committed percentage level of M/WBE participation that the bidder must comply with during the life of the contract. In all cases, the committed percentage level of M/WBE participation must equal or exceed the assigned M/WBE goal for the Project.
  - c. In providing the exact dollar amount of participation for each listed M/WBE, a bidder should take care never to round up in determining whether or not the total of these amounts meets or exceeds the established percentage goal. The goal must be met or exceeded by dollar amounts and percentages in order for DSBO to determine that the bidder has met or exceeded the applicable M/WBE goal.
  - d. As previously mentioned, compliance with the M/WBE goal will be determined on the base bid alone. If a bid contains alternates, participation contained in any alternate will not count towards satisfaction of the Project goal. However, should any designated alternate be selected by the City for inclusion in the contract ultimately awarded, the M/WBE goal percentage level submitted at bid time, on the base bid, will also apply to the selected alternates and must be maintained for the life of the contract on the total contract amount, including any alternate work. Thus, even though such participation will not be considered in evaluating bids, bidders are urged to consider participation in preparing bids for designated alternates.
  - e. On projects where force account or allowance bid items have been included, bidders must meet the M/WBE goal percentage based upon the total base bid, including all such items that are submitted to the City. However, when a force account or allowance is designated by the City to be either performed or purchased from a specific company, the bidder may back out the dollar amount of the force account or allowance from the total base bid and meet the M/WBE goal on the remaining reduced amount.
  - f. On bids which, at the time of bid opening, are equal to or exceed Five Million Dollars (\$5,000,000.00), including any alternates which may be selected, only sixty percent (60%) of the value of the commercially useful function performed by M/WBE suppliers shall count toward satisfaction of the Project goal. On Projects under Five Million (\$5,000,000.00) the value of the commercially useful function of M/WBE supplier(s) will count at a one hundred percent (100%) level. Manufacturer's representatives and packagers shall be counted in the same manner as brokers.
  - g. In utilizing the M/WBE participation of a Broker only the bona fide commissions earned by such Broker for its performance of a commercially useful function will count toward meeting the Project goals. The bidder must separate the bona fide brokerage commissions from the actual cost of the supplies or materials provided to determine the actual dollar amount of participation that can be counted towards meeting the goal.



7. On or before the third (3<sup>rd</sup>) working day after bid opening, all of the Bidders are required to submit an executed "Letter of Intent" for each M/WBE listed on the Bid Form as a joint venture member, subcontractor, supplier, manufacturer, manufacturers' representative or broker of any tier. **An MBE or WBE Prime Bidder needs to submit a Letter of Intent for itself for self performed work**, and must identify their level of participation on the designated M/WBE participation page bound herein. A Letter of Intent shall be submitted only for the M/WBEs listed at the time of bid opening, since this is the only participation that will be counted toward satisfaction of the project goal. A form for the M/WBE Letter of Intent is included with the Bid Form. The M/WBE Letter of Intent is a written communication from the Bidder to the City evidencing an understanding that the Bidder has or will enter into a contractual relationship with the M/WBE or that its subcontractor(s) and supplier(s), manufacturer(s), manufacturers' representative(s) and broker(s) will do so. Each M/WBE Letter of Intent shall be accompanied by a copy of the City and County of Denver's M/WBE certification letter for each proposed M/WBE identified at bid time. Bidders are urged to carefully review these Letters before submission to the City to ensure that they are properly completed and executed by the appropriate parties.

### **Good Faith Effort.**

In preparing a bid to demonstrate a good faith effort, bidders should consider the following instructions relating to compliance with the M/WBE Ordinance:

1. If the bidder or proposer has not fully met the project goal as provided in section 28-60, then it shall demonstrate that it has made good faith efforts to meet such goal. The bidder or proposer shall furnish to the director, within three (3) working days after bid opening by the City or on or before the time of the final project-specific proposal submitted to and authorized by the City pursuant to a competitive selection process, or bid selection by a private owner, a detailed statement of its good faith efforts to meet the project goal set by the director. This statement shall address each of the items in subsection (b) and any additional criteria that the director may establish by rule or regulation consistent with the purposes of this division 3. Good faith efforts must be demonstrated to be meaningful and not merely for formalistic compliance with this Division 3. The scope and intensity of the efforts will be considered in determining whether the bidder or proposer has achieved a good faith effort.
2. The statement of good faith efforts shall include a specific response and verification with respect to each of the following good faith effort categories, which may be further defined by rule or regulation. A bidder or proposer may include any additional information it believes may be relevant. Failure of a bidder or proposer to show good faith efforts as to any one (1) of the following categories shall render its overall good faith effort showing insufficient and its bid or proposal non-responsive:
  - a. If prebid or preselection meetings are scheduled by the City at which MBEs and WBEs may be informed of subcontracting or joint venture opportunities under a proposed contract to be bid, or procured pursuant to the competitive selection process, attendance at such prebid or preselection meetings is not mandatory; however, bidders and proposers are responsible for the information provided at these meetings.
  - b. The bidder or proposer must solicit through all reasonable and available means, the interest of all MBEs and WBEs certified in the scopes of work of the contract. The bidder or proposer must solicit the interest of such MBEs and WBEs within sufficient time, prior to the bid opening or date of final project-specific proposal in the case of a competitive selection process, to allow such MBEs and WBEs to respond to the solicitation. The bidder or proposer must determine with certainty if the MBEs and WBEs are interested by demonstrating appropriate steps to follow up initial solicitations.
  - c. The bidder or proposer must select portions of the work of the contract to be performed by MBEs and WBEs in order to increase the likelihood that the project goal will be achieved. This includes, where appropriate, breaking out contract work items into economically feasible units to facilitate MBE and WBE participation as subcontractors or joint venturers, and for bidder or proposer self-performed work, as suppliers, manufacturers, manufacturer's representatives and

brokers, all reasonably consistent with industry practice, even when the bidder or proposer would otherwise prefer to perform these work items with its own forces. The bidder or proposer must identify what portions of the contract will be self-performed and what portions of the contract will be opened to solicitation of bids, proposals and quotes from MBE and WBEs. All portions of the contract not self-performed must be solicited for MBE and WBE participation. The ability or desire of a bidder or proposer to perform the work of a contract with its own forces does not relieve the bidder or proposer of the responsibility to meet the project goal or demonstrate good faith efforts to do so.

- d. The bidder or proposer, consistent with industry practice, must provide MBEs and WBEs at a clearly stated location with timely, adequate access to and information about the plans, specifications, and requirements of the contract, including bonding and insurance requirements, if any, to assist them in responding to a solicitation.
  - e. The bidder or proposer must negotiate in good faith with interested MBEs and WBEs and provide written documentation of such negotiation with each such MBE or WBE.
  - f. For each MBE or WBE which contacted the bidder or proposer or which the bidder or proposer contacted or attempted to subcontract or joint venture with, consistent with industry practice, the bidder or proposer must supply a statement giving the reasons why the bidder or proposer and the MBE or WBE did not succeed in negotiating a subcontracting, supplier, manufacturer, manufacturer's representative, broker or joint venture agreement, as applicable.
3. The bidder or proposer must provide verification that it rejected each non-utilized MBE and WBE because the MBE or WBE did not submit the lowest bid or it was not qualified. Such verification shall include a verified statement of the amounts of all bids received from potential or utilized subcontractors, suppliers, manufacturers, manufacturer's representatives, brokers or joint venturers on the contract, whether or not they are MBEs or WBEs. In making such a determination of not being qualified, the bidder or proposer shall be guided by the definition of qualified in section 28-54(42), but evidence of lack of qualification must be based on factors other than solely the amount of the MBE's or WBE's bid. For each MBE or WBE found not to be qualified by the bidder or proposer, the verification shall include a statement giving the bidder's or proposer's reasons for its conclusion. A bidder's or proposer's industry standing, or group memberships may not be the cause of rejection of an MBE or WBE. A bidder or proposer may not reject an MBE or WBE as being unqualified without sound reasons based on a reasonably thorough investigation and assessment of the MBE's or WBE's capabilities and expertise.
  4. If requested by a solicited MBE or WBE, the bidder or proposer must make reasonable efforts to assist interested MBEs and WBEs in obtaining bonding, lines of credit, or insurance as required by the City or by the bidder or proposer, provided that the bidder or proposer need not provide financial assistance toward this effort.
  5. If requested by a solicited MBE or WBE, the bidder or proposer must make reasonable efforts to assist interested MBEs and WBEs in obtaining necessary and competitively priced equipment, supplies, materials, or related assistance or services for performance under the contract, provided that the bidder or proposer need not provide financial assistance toward this effort.
  6. The bidder or proposer must use the DSBO MBE/WBE directories to identify, recruit, and place MBEs and WBEs.
  7. In determining whether a bidder or proposer has satisfied good faith efforts as to a project goal, the success or failure of other bidders or proposers on the contract in meeting such project goal may be considered.

#### **Continuing Commitments.**

In accordance with the provisions of the M/WBE Ordinance, the bidder agrees that it is committed to meeting either the M/WBE participation goal or the M/WBE participation set forth in its statement of good faith. This commitment  
Contract No. 201845779  
2018 Bond Concrete

must be expressly indicated on the "Commitment to MWBE SBE Participation" form included with the Bid Form. This commitment includes the following understandings:

1. The bidder understands it must maintain M/WBE goals throughout the performance of the Contract pursuant to the requirements set out in D.R.M.C. 28-72.
2. The bidder understands that it must establish and maintain records and submit regular reports, as required, which will allow the City to assess progress in achieving the M/WBE participation goal.
3. The bidder understands that if change orders or any other contract modifications are issued under the contract, the bidder shall have a continuing obligation to immediately inform DSBO in writing of any agreed upon increase or decrease in the scope of work of such contract, upon any of the bases discussed in Section 28-73 of the M/WBE Ordinance, regardless of whether such increase or decrease in scope of work has been reduced to writing at the time of notification.
4. The bidder understands that if change orders or other contract modifications are issued under the contract, that include an increase in scope of work of a contract for construction, reconstruction, or remodeling, whether by amendment, change order, force account or otherwise which increases the dollar value of the contract, whether or not such change is within the scope of work designated for performance by an M/WBE at the time of contract award, such change orders or contract modification shall be immediately submitted to DSBO for notification purposes. Those amendments, change orders, force accounts or other contract modifications that involve a changed scope of work that cannot be performed by existing project subcontractors or by the contractor shall be subject to a goal for M/WBEs equal to the original goal on the contract which was included in the bid. The contractor shall satisfy such goal with respect to such changed scope of work by soliciting new M/WBEs in accordance with Section 28-73 of the M/WBE Ordinance as applicable, or the contractor must show each element of modified good faith set out in Section 28-75(c) of the M/WBE Ordinance. The contractor shall supply to the director the documentation described in Section 28-75(c) of the M/WBE Ordinance with respect to the increased dollar value of the contract.

All bidders are charged with knowledge of and are solely responsible for complying with each and every provision of the M/WBE Ordinance in making a bid and, if awarded, in performing the work described in the Contract Documents. Failure to comply with these provisions could constitute cause for rejection of a bid or subject the selected contractor to sanctions set forth in the M/WBE Ordinance. These instructions are intended only to generally assist the bidder in preparing and submitting a compliant bid. Should any questions arise regarding specific circumstances, bidders must consult the M/WBE Ordinance or contact the Project's designated DSBO representative at (720) 913-1999.

#### **IB- 26 DISCLOSURE OF INFORMATION**

All submissions and other materials provided or produced pursuant to this Invitation for Bids may be subject to the Colorado Open Records Law, C.R.S. 24-72-201, et seq. As such, bidders are urged to review these disclosure requirements and any exceptions to disclosure of information furnished by another party and, prior to submission of a bid to the City, appropriately identify materials that are not subject to disclosure. In the event of a request to the City for disclosure of such information, the City shall advise the bidder of such request to give the bidder an opportunity to object to the disclosure of designated confidential materials furnished to the City. In the event of the filing of a lawsuit to compel such disclosure, the City will tender all such material to the court for judicial determination of the issue of disclosure and each bidder agrees to intervene in such lawsuit to protect and assert its claims of privilege against disclosure of such material. Each bidder further agrees to defend, indemnify and save and hold harmless the City, its officers, agents and employees, from any claim, damages, expense, loss or costs arising out of the bidder's intervention to protect and assert its claims of privilege against disclosure under the Open Records Law including, but not limited to, prompt reimbursement to the City of all reasonable attorney fees, costs and damages that the City may incur directly or may be ordered to pay by such court.

#### **IB-27 GENERAL BIDDING INFORMATION**

Bidders are instructed to contact the Contract Administrator designated below for this Project for pre-bid, post-bid and general City bidding information. Bidders can also visit [www.work4denver.com](http://www.work4denver.com) for information, both general and project specific. The Contract Administrator assigned to this project is Debby Gibson who can be reached via email at [pw.procurement@denvergov.org](mailto:pw.procurement@denvergov.org).

**IB-28 PAYMENT PROCEDURE REQUIREMENTS**

Bidder recognizes and agrees that it shall be required to use the Textura® Construction Payment Management System (“Textura”) for this Project to request payment from the City and to pay subcontractors. All certified subcontractors or suppliers who are listed for participation towards any assigned program goal must be paid via Textura. All fees associated with Textura are to be paid by the bidder for billings for work performed. Bidders are required, when preparing a bid, to enter the price of Textura on the line provided for the service. The fee is all inclusive of all subcontractor, project and subscription fees associated with Textura. The bidder will calculate the fee based on their total bid (not including any alternates, if applicable) and the table below, and then include it on the line item provided in the bid form labeled **“Textura® Construction Payment Management System Fee”**. This expense becomes part of the contract and billable to the City. All costs including, but not limited to, costs associated with training, entering data, and/or utilizing Textura other than the Textura Construction Payment Management System Fee are overhead and shall not be reimbursed by the City. Bidder will be responsible for any tax on the Textura fee. As with other taxes, the City will not reimburse bidder for this cost and therefore this cost should be included in bidder’s bid. Textura will invoice the awarded bidder directly.

Project Value	Project Fee (GC + Sub Usage)
\$100,000 – 249,999.99	\$780
\$250,000 - \$499,999.99	\$1,625
\$500,000 - \$999,999.99	\$3,250
\$1,000,000 - \$2,999,999.99	\$5,850
\$3,000,000 - \$4,999,999.99	\$9,100
\$5,000,000 - \$9,999,999.99	\$12,220
\$10,000,000 - \$19,999,999.99	\$20,345
\$20,000,000 - \$49,999,999.99	\$32,500
\$50,000,000 - \$99,999,999.99	\$48,750
\$100,000,000 - \$199,999,999.99	\$69,095
\$200,000,000 - \$299,999,999.99	\$85,345
\$300,000,000 - \$399,999,999.99	\$109,720
\$400,000,000 - \$499,999,999.99	\$142,220
\$500,000,000 - \$999,999,999.99	\$162,500
\$1,000,000,000 - \$1,999,999,999.99	\$345,345
\$2,000,000,000 - \$4,999,999,999.99	\$650,000
\$5,000,000,000 - \$9,999,999,999.99	\$1,015,625
\$10,000,000,000 or greater	\$1,503,125

**RULES AND REGULATIONS  
REGARDING  
EQUAL EMPLOYMENT OPPORTUNITY**

Promulgated and adopted by the Manager of Public Works pursuant to and by authority of Article III, Division 2, Chapter 28 of the Revised Municipal Code of the City and County of Denver, and for the purpose of insuring that contractors, subcontractors and suppliers soliciting and receiving compensation for contract work from or through the City and County of Denver provide equal opportunity in employment without regard to race, color, creed, sex, national origin, age, religion, marital status, political opinion or affiliation or mental or physical handicap and meet certain requirements for the hiring, training, promotion, and treatment during employment of members of ethnic groups subject to differential treatment, including persons of African descent (Black), Spanish-surnamed (Hispanic), Asian-American and American Indian Groups.

**RULE I - DEFINITIONS**

- A. "City" means the City and County of Denver.
- B. "Manager" shall mean the Manager of Public Works for the City and County of Denver.
- C. "Contract" means a contract entered into with the City and County of Denver, financed in whole or in part by local resources or funds of the City and County of Denver, for the construction of any public building or prosecution or completion of any public work.
- D. "Contractor" means the original party to a contract with the City and County of Denver, also referred to as the "general" or "prime" contractor.
- E. "Director" means the Director of the Division of Small Business Opportunity.
- F. "Subcontractor" means any person, company, association, partnership, corporation, or other entity, which assumes by subordinate agreement some or all of the obligations of the general or prime contractor.
- G. The phrase "Bidding Specifications" as used in Article III, Division 2 of Chapter 28 of the Revised Municipal Code shall include BID CONDITION, INVITATION TO BID, and NOTICE OF PROPOSAL.
- H. "Affirmative Action Program" means a set of specific and result-oriented procedures or steps to which a contractor commits himself to apply every good faith effort to employ members of ethnic minority groups, to include persons of African descent (Black), Spanish surnamed (Hispanic), Asian-American, American Indians, and persons with mental or physical handicap.
- I. "Division of Small Business Opportunity" means the City agency established pursuant to Article III, Division 1 of Chapter 28 of the Denver Revised Municipal Code.

**RULE II - NOTICE OF HEARING**

When results of conciliation efforts are unsatisfactory to the Manager and he is informed in accordance with Article III, Division 2 of Chapter 28 of the Revised Municipal code that a contractor or subcontractor has apparently failed to meet affirmative action and equal employment opportunity requirements after a reasonable period of notice to correct deficiencies, the Manager will, prior to imposition of any sanctions, afford the general contractor a hearing in order to determine whether the contractor or his subcontractors have failed to comply with the affirmative action and equal employment opportunity requirements of Article III, Division 2 of Chapter 28 of the Revised Municipal Code or of the contract. Written notice of such hearing shall be delivered personally or sent by certified mail, return receipt requested, to the contractor and to any subcontractor involved, at least ten (10) days prior to the date scheduled for the hearing.

### **RULE III - HEARING**

- A. Contractors will appear at hearings and may be represented by counsel, and may present testimony orally and other evidence.
- B. Hearings shall be conducted by one or more hearing examiners designated as such by the Manager.
- C. The Director of the Division of Small Business Opportunity may participate in hearings as a witness.
- D. Hearings shall be held at the place specified in the notice of hearing.
- E. All oral testimony shall be given under oath or affirmation and a record of such proceedings shall be made.
- F. All hearings shall be open to the public.
- G. The hearing officer shall make recommendations to the Manager who shall make a final decision.

### **REGULATIONS**

#### **REGULATION NO. 1 - ORDINANCE:**

The Rules and Regulations of the Manager shall be inserted in the bidding specifications for every contract for which bidding is required.

#### **REGULATION NO. 2 - EXEMPTIONS:**

Each contract and subcontract, regardless of the dollar amount, shall be subject to affirmative action requirements unless specifically exempted in writing individually by the Manager. Exemptions apply only to "affirmative action" in equal employment opportunity, and are not to be construed as condonation in any manner of "discrimination" or "discriminatory practices" in employment because of race, color, creed, sex, age, national origin, religion, marital status, political opinion or mental or physical handicap.

#### **REGULATION NO. 3 - DIRECTOR OF CONTRACT COMPLIANCE:**

The Director of the Division of Small Business Opportunity shall perform the duties assigned to such official by Article III, Division 2 Chapter 28 of the Revised Municipal Code and by the Manager. (1) The Director of the Division of Small Business Opportunity or designated representatives shall inform bidders and contractors of affirmative action procedures, programs, and goals in accordance with the Ordinance at pre-bid and pre-construction conference; (2) make regular on-site inspections; (3) supply contractors and subcontractors with report forms to be completed by them when requested, and furnished to the Director of the Division of Small Business Opportunity; and (4) review payroll records, employment records and practices of general contractors and their subcontractors and suppliers during the performance of any contract. The Director of the Division of Small Business Opportunity shall promptly report apparent affirmative action deficiencies to the Manager.

#### **REGULATION NO. 4 - GOALS AND TIMETABLES:**

In general, goals and timetables should take into account anticipated vacancies and the availability of skills in the market place from which employees should be drawn. In addition, where discrimination in employment by a general contractor or any of his subcontractors is indicated, a corrective action program will take into account the need by the general contractor and his subcontractors to correct past discriminatory practices and reach goals of minority manpower utilization on a timely basis through such recruiting and advertising efforts as are necessary and appropriate.

#### **REGULATION NO. 5 - AWARD OF CONTRACTS:**

It shall be the responsibility of the Director of the Division of Small Business Opportunity to determine the affirmative action capability of bidders, contractors and subcontractors and to recommend to the Manager the award of contracts to those bidders, contractors and subcontractors and suppliers who demonstrate the ability and willingness to comply with the terms of their contract.

**REGULATION NO. 6 - PUBLICATION AND DUPLICATION:**

Copies of these Rules and Regulations as amended by the Manager from time to time, shall as soon as practicable and after Notice being published will be made a part of all City Contracts.

**REGULATION NO. 7 - NOTICE TO PROCEED:**

Prior to issuance of the Notice to Proceed, a sign-off will be required of the Director of the Division of Small Business Opportunity or his designee.

**REGULATION NO. 8 - CONTRACTS WITH SUBCONTRACTORS:**

To the greatest extent possible, the contractor shall make a good faith effort to contract with minority contractors, subcontractors and suppliers for services and supplies by taking affirmative actions, which include but are not limited to the following:

1. Advertise invitations for subcontractor bids in minority community news media.
2. Contact minority contractor organizations for referral of prospective subcontractors.
3. Purchase materials and supplies from minority material suppliers.

**REGULATION NO. 9 - AGENCY REFERRALS:**

It shall be no excuse that the union with which the contractor or subcontractor has an agreement providing for referral, exclusive or otherwise, failed to refer minority employees.

**REGULATION NO. 10 - CLAUSES:**

The Manager shall include the appropriate clauses in every contract and the contractor shall cause to be inserted in every subcontract the appropriate clauses:

1. APPENDIX A: City and County of Denver Equal Opportunity Clause - ALL CONTRACTS funded only with City and County of Denver monies.
2. APPENDIX B: Equal Opportunity Clause (11246) - ALL FEDERAL ASSISTED.
3. APPENDIX C: Section 3 - Assurance of Compliance - HUD ASSISTED PROJECTS.
4. APPENDIX D: Section 3 - Clause - HUD ASSISTED PROJECTS.

All amendments to the appendices shall be included by reference.

**REGULATION NO. 11 - SHOW CAUSE NOTICES:**

When the Manager has reasonable cause to believe that a contractor has violated Article III, Division 2 of Chapter 28 of the Denver Revised Municipal Code, he may issue a notice requiring the contractor to show cause, within fifteen (15) days why enforcement procedures, or other appropriate action to insure compliance, should not be instituted.

**REGULATION NO. 12 - BID CONDITIONS - AFFIRMATIVE ACTION REQUIREMENTS - EQUAL EMPLOYMENT OPPORTUNITY:**

1. APPENDIX E: The Bid Conditions - Affirmative Action Requirements - Equal Employment Opportunity as amended and published by the U.S. Department of Labor Employment Standards Administration, Office of Federal Contract Compliance, shall be inserted verbatim for bidding specification for every non-exempt contract involving the use of Federal funds.
2. APPENDIX F: The Bid Conditions - Affirmative Action Requirements - Equal Employment Opportunity as published by the Department of Public Works, City and County of Denver, shall be inserted verbatim as bidding specifications for every non-exempt contract using City funds.

**CITY AND COUNTY OF DENVER**  
**DEPARTMENT OF PUBLIC WORKS**

**APPENDIX A**

**CITY AND COUNTY OF DENVER EQUAL OPPORTUNITY CLAUSE -  
ALL CONTRACTS**

1. The Contractor will not discriminate against any employee or applicant for employment because of race, creed, color, sex, age, national origin, religion, marital status, political opinion or affiliation, or mental or physical handicap. The Contractor will take affirmative action to ensure that applicants are employed, and that employees are treated during employment without regard to their race, creed, color, sex, age, national origin, religion, marital status, political opinion or affiliation, or mental or physical handicap. Such action shall include, but not be limited to the following: employment, upgrading, demotion, or transfer; recruitment or recruitment advertising; layoff or termination; rates of pay or other forms of compensation; and selection for training, including apprenticeship. The Contractor agrees to post in conspicuous places, available to employees and applicants for employment, notices to be provided setting forth the provisions of this nondiscrimination clause.
2. The Contractor will, in all solicitations or advertisements for employees placed by or on behalf of the contractor, state that all qualified applicants will receive consideration for employment without regard to race, creed, color, sex, age, national origin, religion, marital status, political opinion or affiliation, or mental or physical handicap.
3. The Contractor will send to each labor union or representative of workers with which he has a collective bargaining agreement or other contract or understanding, a notice to be provided, advising the said labor union or workers' representatives of the contractor's commitments under this section, and shall post copies of the notice in conspicuous places available to employees and applicants for employment.
4. Each Contractor will comply with all provisions of Article III, Division 2 of Chapter 28 of the Revised Municipal Code, and the rules, regulations, and relevant orders of the Manager and the Director.
5. The Contractor will furnish all information and reports required by Article III, Division 2 of Chapter 28 of the Revised Municipal Code, and by rules, regulations and orders of the Manager and Director or pursuant thereto, and will permit access to his books, records, and accounts by the Manager, Director, or their designee for purposes of investigation to ascertain compliance with such rules, regulations, and orders.
6. In the event of the Contractor's noncompliance with the nondiscrimination clauses of this contract or with any of the said rules, regulations or orders, this contract may be canceled, terminated, or suspended in whole or in part and the Contractor may be declared ineligible for further City contracts in accordance with procedures authorized in Article III, Division 2, Chapter 28 of the Revised Municipal Code, or by rules, regulations, or order of the Manager.
7. The Contractor will include Regulation 12, Paragraph 2 and the provisions of paragraphs (1) through (6) in every subcontract of purchase order unless exempted by rules, regulations, or orders of the Manager issued pursuant to Article III, Division 2, Chapter 28 of the Revised Municipal Code, so that such provisions will be binding on each subcontractor or supplier. The Contractor will take such action with respect to any subcontract or purchase order as the administering agency may direct as a means of enforcing such provisions, including sanctions for noncompliance.

The applicant further agrees to be bound by the above equal opportunity clauses with respect to its own employment practices when it participates in City contracts. The Contractor agrees to assist and cooperate actively with the Manager and the Director in obtaining compliance of subcontractors and suppliers with the equal opportunity clause and the rules, regulations and relevant orders of the Manager, and will furnish the Manager and the Director such information as they may require for the supervision of compliance, and will otherwise assist the Manager and Director in the discharge of the City's primary responsibility for securing compliance. The Contractor further agrees to refrain from entering into any contract or contract modification



subject to Article III, Division 2 of Chapter 28 of the Revised Municipal Code with a contractor debarred from, or who has not demonstrated eligibility for, City contracts.

The Contractor will carry out such sanctions and penalties for violation of the equal opportunity clause as may be imposed upon contractors and subcontractors by the Manager and Director. In addition, the Contractor agrees that failure or refusal to comply with these undertakings the Manager may take any or all of the following actions:

- A. Cancellation, termination, or suspension in whole or in part of this contract.
- B. Refrain from extending any further assistance to the applicant under the program with respect to which the failure occurred until satisfactory assurance of future compliance has been received from such applicant.
- C. Refer the case to the City Attorney for appropriate legal proceedings.

**SUBCONTRACTS:** Each prime Contractor or Subcontractor shall include the equal opportunity clause in each of its subcontracts.

**CITY AND COUNTY OF DENVER  
DEPARTMENT OF PUBLIC WORKS**

**APPENDIX F**

**AFFIRMATIVE ACTION REQUIREMENTS**

**EQUAL EMPLOYMENT OPPORTUNITY**

For All Non-Exempt Construction Contracts to Be Awarded by the  
City and County of Denver, Department of Public Works.

**NOTICE**

EACH BIDDER, CONTRACTOR OR SUBCONTRACTOR (HEREINAFTER THE CONTRACTOR) MUST FULLY COMPLY WITH THE REQUIREMENTS OF THESE BID CONDITIONS AS TO EACH CONSTRUCTION TRADE IT INTENDS TO USE ON THIS CONSTRUCTION CONTRACT, AND ALL OTHER CONSTRUCTION WORK (BOTH CITY AND NON-CITY) IN THE DENVER AREA DURING THE PERFORMANCE OF THIS CONTRACT OR SUBCONTRACT. THE CONTRACTOR COMMITS ITSELF TO THE GOALS FOR MINORITY MANPOWER UTILIZATION, AS APPLICABLE, AND ALL OTHER REQUIREMENTS, TERMS AND CONDITION OF THESE BID CONDITIONS BY SUBMITTING A PROPERLY SIGNED BID.

THE CONTRACTOR SHALL APPOINT A COMPANY EXECUTIVE TO ASSUME THE RESPONSIBILITY FOR THE IMPLEMENTATION OF THE REQUIREMENTS, TERMS AND CONDITIONS OF THESE BID CONDITIONS.

*/s/* \_\_\_\_\_

Manager of Public Works  
City and County of Denver

**A. REQUIREMENTS - AN AFFIRMATIVE ACTION PLAN:**

Contractors shall be subject to the provisions and requirements of these bid conditions including the goals and timetables for minority\* and female utilization, and specific affirmative action steps set forth by the Division of Small Business Opportunity (DSBO). The contractor's commitment to the goals for minority, and female utilization as required constitutes a commitment that it will make every good faith effort to meet such goals.

**1. GOALS AND TIMETABLES:**

The goals and timetables for minority and female participation, expressed in percentage terms for the contractor's aggregate workforce in each trade are as follows:

GOALS FOR MINORITY PARTICIPATION FOR EACH TRADE	GOALS FOR FEMALE PARTICIPATION FOR EACH TRADE
From January 1, 1982 to Until Further Notice	From January 1, 1982 to Until Further Notice
<b>21.7% - 23.5%</b>	<b>6.9%</b>

The goals for minority and female utilization above are expressed in terms of hours of training and employment as a proportion of the total number of hours to be worked by the contractor's aggregate workforce, which includes all supervisory personnel, in each trade, on all projects for the City and County of Denver during the performance of its contract (i.e., The period beginning with the first day of work on the City and County of Denver funded construction contract and ending with the last day of work).

The hours of minority and female employment and training must be substantially uniform throughout the length of the contract in each trade and minorities and females must be employed evenly on each of a contractor's projects. Therefore, the transfer of minority or female employees from contractor to contractor or from project to project for the purpose of meeting the contractor's goals shall be a violation of these Bid Conditions.

If the Contractor counts the nonworking hours of apprentices they must be employed by the Contractor during the training period; the Contractor must have made a commitment to employ apprentices at the completion of their training subject to the availability of employment opportunities; and the apprentices must be trained pursuant to training programs approved by the Bureau of Apprenticeship and Training.

\* "Minority" is defined as including, Blacks, Spanish Surname Americans, Asian Americans, and American Indians, and includes both men and minority women.

**2. SPECIFIC AFFIRMATIVE ACTION STEPS:**

No contractor shall be found to be in noncompliance solely on account of its failure to meet its goals, but will be given an opportunity to demonstrate that the contractor has instituted all the specific affirmative action steps specified and has made every good faith effort to make these steps work toward the attainment of its goals within the timetables, all to the purpose of expanding minority and female utilization in its aggregate workforce. A contractor, who fails to comply with its obligation under the Equal Opportunity Clause of its contract and fails to achieve its commitments to the goals for minority and female utilization has the burden of proving that it has engaged in an Affirmative Action Program directed at increasing minority and female utilization and that such efforts were at least as extensive and as specific as the following:

- a. The Contractor should have notified minority and female organizations when employment opportunities were available and should have maintained records of the organization's response.

- b. The Contractor should have maintained a file of the names and addresses of each minority and female referred to it by any individual or organization and what action was taken with respect to each such referred individual, and if the individual was not employed by the Contractor, the reasons. If such individual was sent to the union hiring hall for referral and not referred back by the union or if referred, not employed by the Contractor, the file should have documented this and their reasons.
- c. The Contractor should have promptly notified the Department of Public Works, and the Division of Small Business Opportunity when the union or unions with which the Contractor has collective bargaining agreements did not refer to the contractor a minority or female sent by the contractor, or when the Contractor has other information that the union referral process has impeded efforts to meet its goals.
- d. The Contractor should have disseminated its EEO policy within its organization by including it in any employee handbook or policy manual; by publicizing it in company newspapers and annual reports and by advertising such policy at reasonable intervals in union publications. The EEO policy should be further disseminated by conducting staff meetings to explain and discuss the policy; by posting of the policy; and by review of the policy with minority and female employees.
- e. The Contractor should have disseminated its EEO policy externally by informing and discussing it with all recruitment sources; by advertising in news media, specifically including minority and female news media; and by notifying and discussing it with all subcontractors.
- f. The Contractor should have made both specific and reasonably recurrent written and oral recruitment efforts. Such efforts should have been directed at minority and female organizations, schools with substantial minority and female enrollment, and minority and female recruitment and training organizations within the Contractor's recruitment area.
- g. The Contractor should have evidence available for inspection that all tests and other selection techniques used to select from among candidates for hire, transfer, promotion, training, or retention are being used in a manner that does not violate the OFCCP Testing Guidelines in 41 CFR Part 60-3.
- h. The Contractor should have made sure that seniority practices and job classifications do not have a discriminatory effect.
- i. The Contractor should have made certain that all facilities are not segregated by race.
- j. The Contractor should have continually monitored all personnel activities to ensure that its EEO policy was being carried out including the evaluation of minority and female employees for promotional opportunities on a quarterly basis and the encouragement of such employees to seek those opportunities.
- k. The Contractor should have solicited bids for subcontracts from available minority and female subcontractors engaged in the trades covered by these Bid Conditions, including circulation of minority and female contractor associations.

NOTE: The Director and the Division of Small Business Opportunity will provide technical assistance on questions pertaining to minority and female recruitment sources, minority and female community organizations, and minority and female news media upon receipt of a request for assistance from a contractor.

**3. NON - DISCRIMINATION:**

In no event may a contractor utilize the goals and affirmative action steps required in such a manner as to cause or result in discrimination against any person on account of race, color, religion, sex, marital status, national origin, age, mental or physical handicap, political opinion or affiliation.

**4. COMPLIANCE AND ENFORCEMENT:**

In all cases, the compliance of a contractor will be determined in accordance with its obligations under the terms of these Bid Conditions. All contractors performing or to perform work on projects subject to these Bid Conditions hereby agree to inform their subcontractors in writing of their respective obligations under the terms and requirements of these Bid Conditions, including the provisions relating to goals of minority and female employment and training.

**B. CONTRACTORS SUBJECT TO THESE BID CONDITIONS:**

In regard to these Bid Conditions, if the Contractor meets the goals set forth therein or can demonstrate that it has made every good faith effort to meet these goals, the Contractor shall be presumed to be in compliance with Article III, Division 2 of Chapter 28 of the Revised Municipal Code, the implementing regulations and its obligations under these Bid Conditions. In the event, no formal sanctions or proceedings leading toward sanctions shall be instituted unless the contracting or administering agency otherwise determines that the contractor is violating the Equal Opportunity Clause.

1. Where the Office of Contract Compliance finds that a contractor failed to comply with the requirements of Article III, Division 2 of Chapter 28 of the Revised Municipal Code or the implementing regulations and the obligations under these Bid Conditions, and so informs the Manager, the Manager shall take such action and impose such sanctions, which include suspension, termination, cancellation, and debarment, as may be appropriate under the Ordinance and its regulations. When the Manager proceeds with such formal action it has the burden of proving that the Contractor has not met the goals contained in these Bid Conditions. The Contractor's failure to meet its goals shall shift to it the requirement to come forward with evidence to show that it has met the good faith requirements of these Bid Conditions.
2. The pendency of such proceedings shall be taken into consideration by the Department of Public Works in determining whether such contractor can comply with the requirements of Article III, Division 2 of Chapter 28 of the Revised Municipal Code, and is therefore a "responsible prospective contractor".
3. The Division of Small Business Opportunity shall review the Contractor's employment practices during the performance of the contract. If the Division of Small Business Opportunity determines that the Contractor's Affirmative Action Plan is no longer an acceptable program, the Director shall notify the Manager.

**C. OBLIGATIONS APPLICABLE TO CONTRACTORS:**

It shall be no excuse that the union with which the Contractor has a collective bargaining agreement providing for exclusive referral failed to refer minority or female employees. Discrimination in referral for employment, even if pursuant to provisions of a collective bargaining agreement, is prohibited by the National Labor Relations Act, as amended, Title VI of the Civil Rights Act of 1964, as amended, and Article III, Division 2 of Chapter 28 of the Revised Municipal Code. It is the policy of the Department of Public Works that contractors have a responsibility to provide equal employment opportunity, if they wish to participate in City and County of Denver contracts. To the extent they have delegated the responsibility for some of their employment practices to a labor organization and, as a result, are prevented from meeting their obligations pursuant to Article III, Division 2, Chapter 28 of the Revised Municipal Code, such Contractors cannot be considered to be in compliance with Article III, Division 2, Chapter 28 of the Revised Municipal Code, or its implementing rules and regulations.

**D. GENERAL REQUIREMENTS:**

Contractors are responsible for informing their subcontractors in writing regardless of tier, as to their respective obligations. Whenever a Contractor subcontracts a portion of work in any trade covered by these Bid Conditions, **it shall include these Bid Conditions in such subcontracts and each subcontractor shall be bound by these Bid Conditions to the full extent as if it were the prime contractor.** The Contractor

shall not, however, be held accountable for the failure of its subcontractors to fulfill their obligations under these Bid Conditions. However, the prime contractor shall give notice to the Director of any refusal or failure of any subcontractor to fulfill the obligations under these Bid Conditions. A subcontractor's failure to comply will be treated in the same manner as such failure by a prime contractor.

1. Contractors hereby agree to refrain from entering into any contract or contract modification subject to Article III, Division 2, Chapter 28 of the Revised Municipal Code with a contractor debarred from, or who is determined not to be a "responsive" bidder for the City and County of Denver contracts pursuant to the Ordinance.
2. The Contractor shall carry out such sanctions and penalties for violation of these Bid Conditions and the Equal Opportunity Clause including suspension, termination and cancellation of existing subcontracts and debarment from future contracts as may be ordered by the Manager pursuant to Article III, Division 2, Chapter 28 of the Revised Municipal Code and its implementing regulations.
3. Nothing herein is intended to relieve any contractor during the term of its contract from compliance with Article III, Division 2, Chapter 28 of the Revised Municipal Code, and the Equal Opportunity Clause of its contract with respect to matters not covered in these Bid Conditions.
4. Contractors must keep such records and file such reports relating to the provisions of these Bid Conditions as shall be required by the Office of Contract Compliance.
5. Requests for exemptions from these Bid Conditions must be made in writing, with justification, to the Manager of Public Works, 201 W. Colfax, Dept. 608, Denver, Colorado 80202, and shall be forwarded through and with the endorsement of the Director.

**CITY AND COUNTY OF DENVER  
DEPARTMENT OF PUBLIC WORKS**

**CONTRACT NO. 201845779**

**2018 Citywide Bond Concrete Repair**

**CONTRACT**

**THIS CONTRACT AND AGREEMENT**, made and entered into by and between the City and County of Denver, a municipal corporation of the State of Colorado, hereinafter referred to as the "City," party of the first part, and, hereinafter referred to as the "Contractor," party of the second part,

**KEENE CONCRETE, INC.  
30263 WCR 8  
KEENESBURG, CO 80643**

**WITNESSETH**, Commencing on **November 16, 2018**, and for at least three (3) days the City advertised that sealed bids would be received for furnishing all labor, tools, supplies, equipment, materials, and everything necessary and required for the following:

**CONTRACT NO. 201845779**

**2018 Citywide Bond Concrete Repair**

**WHEREAS**, bids pursuant to said advertisement have been received by the Manager of Public Works, who has recommended that a Contract for said work be made and entered into with the above named Contractor who was the lowest, responsive, qualified bidder therefore, and

**WHEREAS**, said Contractor is now willing and able to perform all of said work in accordance with said advertisement and its bid.

**NOW THEREFORE**, in consideration of the compensation to be paid the Contractor, the mutual agreements hereinafter contained, and subject to the terms hereinafter stated, it is mutually agreed as follows:

**1. CONTRACT DOCUMENTS**

It is agreed by the parties hereto that the following list of documents, instruments, technical specifications, plans, drawings and other materials which are attached hereto and bound herewith, incorporated herein by reference or otherwise referenced in these documents constitute and shall be referred to either as the "Contract Documents" or the "Contract," and all of said documents, instruments, technical specifications, Plans, Drawings and other materials taken together as a whole constitute the Contract between the parties hereto, and they are as fully a part of this agreement as if they were set out verbatim and in full herein:

*Advertisement of Notice of Invitation for Bids  
Instructions to Bidders  
Commitment to M/WBE Participation  
Article III, Divisions 1, 2, and 3 of Chapter 28, D.R.M.C.  
Bid Bond  
Addenda (as applicable)*

*Equal Employment Opportunity Provisions (Appendix A and Appendix F)*  
*Bid Form*  
*Contract Form*  
*General Contract Conditions*  
*Special Contract Conditions*  
*Performance and Payment Bond*  
*Notice to Apparent Low Bidder*  
*Notice to Proceed*  
*Contractor's Certification of Payment Form*  
*Final/Partial Lien Release Form*  
*Certificate of Contract Release*  
*Change Orders (as applicable)*  
*Federal Requirements (as applicable)*  
*Prevailing Wage Rate Schedule(s)*  
*Technical Specifications*  
*Contract Drawings*  
*Accepted Shop Drawings*

**2. SCOPE OF WORK**

The Contractor agrees to and shall furnish all labor, tools, supplies, equipment, materials and everything necessary for and required to do, perform and complete all of the Work described, drawn, set forth, shown and included in said Contract Documents.

**3. TERMS OF PERFORMANCE**

The Contractor agrees to undertake the performance of the Work under this Contract within ten (10) days after being notified to commence work by issuance of a Notice to Proceed in substantially the form contained herein from the Manager and agrees to fully complete said Work within **180 (One Hundred Eighty Days)** consecutive calendar days from the effective date of said Notice, plus such extension or extensions of time as may be granted in accordance with the provisions of the General Contract Conditions and any applicable Special Contract Conditions.

**4. TERMS OF PAYMENT**

The City agrees to pay the Contractor for the performance of all of the Work required under this Contract, and the Contractor agrees to accept as the Contractor's full and only compensation therefore, such sum or sums of money as may be proper in accordance with the price or prices set forth in the Contractor's Bid Form hereto attached and made a part hereof for **58 bid items (fifty-eight) bid item numbers (202-00019 through 630-000 03)**, the total estimated cost thereof being **Two Million Four Hundred Sixty Eight Thousand Nine Hundred and Fifty Dollars and Zero Cents (\$2,468,950.00)**. Adjustments to said Contract Amount and payment of amounts due hereunder shall be made in accordance with the provisions of the General Contract Conditions and any applicable Special Contract Conditions.

**5. NO DISCRIMINATION IN EMPLOYMENT**

In connection with the performance of work under this contract, the Contractor may not refuse to hire, discharge, promote or demote, or discriminate in matters of compensation against any person otherwise qualified, solely because of race, color, religion, national origin, gender, age, military status, sexual orientation, gender identity or gender expression, marital status, or physical or mental disability. The Contractor shall insert the foregoing provision in all subcontracts.

**6. COMPLIANCE WITH M/WBE REQUIREMENT**

This Contract is subject to all applicable provisions of Divisions 1 and 3 of Article III, of Chapter 28, Denver Revised Municipal Code (D.R.M.C.), designated as Sections 28-31 – 28-36 and 28-52 – 28-90 D.R.M.C. and referred to in this Contract as the "M/WBE Ordinance". Without limiting the general applicability of the foregoing, the Contractor acknowledges its continuing duty, pursuant to Sections 28-72, 28-73 and 28-75 of the D.R.M.C., to maintain throughout the duration of this Contract, compliance with the level of minority and Woman business enterprise participation, upon which the City approved the award of this Contract to the Contractor and the Contractor further acknowledges that failure to maintain such participation commitments or otherwise comply with the requirements of the M/WBE Ordinance shall subject the



Contractor to sanctions in accordance with Section 28-77 of the D.R.M.C. Nothing contained in this provision or in the M/WBE Ordinance shall negate the City's right to prior approval of subcontractors, or substitutes therefore, under this Contract

**7. WAGE RATE REQUIREMENTS**

In performance of all Work hereunder, the Contractor agrees to comply with and be bound by all requirements and conditions of the City's Payment of Prevailing Wages Ordinance, Sections 20-76 through 20-79, D.R.M.C. and any determinations made by the City pursuant thereto.

**8. APPLICABILITY OF LAWS**

The Agreement between the Contractor and the City shall be deemed to have been made in the City and County of Denver, State of Colorado and shall be subject to, governed by, and interpreted and construed by or in accordance with the laws of the State of Colorado and the Charter, Revised Municipal Code, Rules, Regulations, Executive Orders and fiscal rules of the City. As such, the Contractor shall at all times comply with the provisions of the Charter, Revised Municipal Code, Rules, Regulations, Executive Orders and fiscal rules of the City, and those State of Colorado and Federal Laws, Rules and Regulations, which in any manner limit, control or apply to the actions or operations of the Contractor, any subcontractors, employees, agents or servants of the Contractor engaged in the Work or affecting the materials and equipment used in the performance of the Work, as the same may be, from time to time, promulgated, revised or amended. The Charter and Revised Municipal Code of the City and County of Denver, as the same may be amended from time to time, are hereby expressly incorporated into this Agreement as if fully set out herein by this reference.

**9. APPROPRIATION**

The amount of money, which has been appropriated and encumbered for the purpose of this contract, to date, is equal to or in excess of the Contract Amount. The Manager, upon reasonable written request, will advise the Contractor in writing of the total amount of appropriated and encumbered funds, which remain available for payment for all Work under the Contract.

The issuance of any change order or other form or order or directive by the City which would cause the aggregate payable under the contract to exceed the amount appropriated for the contract is expressly prohibited. In no event shall the issuance of any change order or other form of order or directive by the City be considered valid or binding if it requires additional compensable work to be performed, which work will cause the aggregate amount available under the Contract to exceed the amount appropriated and encumbered for this Contract, unless and until such time as the Contractor has been advised in writing by the Manager that a lawful appropriation, sufficient to cover the entire cost of such additional work, has been made.

It shall be the responsibility of the Contractor to verify that the amounts already appropriated for this Contract are sufficient to cover the entire cost of such work, and any work undertaken or performed in excess of the amount appropriated is undertaken or performed in violation of the terms of this contract, without the proper authorization for such work, and at the Contractor's own risk.

**10. APPROVALS**

In the event this Contract calls for the payment by the City of five hundred thousand dollars (\$500,000.00) or more, approval by the Board of Councilmen of the City and County of Denver, acting by ordinance, in accordance with Section 3.2.6 of the Charter of the City and County of Denver, is and shall be an express condition precedent to the lawful and binding execution and effect and performance of this contract.

**11. ASSIGNMENT**

The Contractor shall not assign any of its rights, benefits, obligations or duties under this Contract except upon the prior written consent and approval of the Manager to such assignment.

**12. DISPUTES RESOLUTION PROCESS**

It is the express intention of the parties to this Contract that all disputes of any nature whatsoever regarding the Contract including, but not limited to, any claims for compensation or damages arising out of breach or default under this Contract, shall be resolved by administrative hearing pursuant to the provisions of Section 56-106, D.R.M.C., or, as applicable, Section 28-33 D.R.M.C. for Minority and Woman Business Enterprise disputes. The Contractor expressly agrees that this dispute resolution process is the only dispute resolution mechanism that will be recognized by the parties for any claims put forward by the Contractor,

notwithstanding any other claimed theory of entitlement on the part of the Contractor or its subcontractors or suppliers.

**13. CONTRACT BINDING**

It is agreed that this Contract shall be binding on and inure to the benefit of the parties hereto, their heirs, executors, administrators, assigns and successors.

**14. PARAGRAPH HEADINGS**

The captions and headings set forth herein are for convenience of reference only and shall not be construed so as to define or limit the terms and provisions hereof.

**15. SEVERABILITY**

It is understood and agreed by the parties hereto that, if any part, term, or provision of this Contract, except for the provisions of this Contract requiring prior appropriation and limiting the total amount to be paid by the City, is by the courts held to be illegal or in conflict with any law of the State of Colorado, the validity of the remaining portions or provisions shall not be affected, and the rights and obligations of the parties shall be construed and enforced as if the Contract did not contain the particular part, term or provision held to be invalid.

**16. ELECTRONIC SIGNATURES AND ELECTRONIC RECORDS:**

Contractor consents to the use of electronic signatures by the City. The Agreement, and any other documents requiring a signature hereunder, may be signed electronically by the City in the manner specified by the City. The Parties agree not to deny the legal effect or enforceability of the Agreement solely because it is in electronic form or because an electronic record was used in its formation. The Parties agree not to object to the admissibility of the Agreement in the form of an electronic record, or a paper copy of an electronic document, or a paper copy of a document bearing an electronic signature, on the ground that it is an electronic record or electronic signature or that it is not in its original form or is not an original.

IN WITNESS WHEREOF, the parties have executed this agreement and affixed their seals at Denver, Colorado as of the day first above written.

**Contract Control Number:** 201845779

**Vendor Name:** KEENE CONCRETE, INC.

By: Chris Bailey

Name: Chris C Bailey  
(please print)

Title: President  
(please print)

**ATTEST: [if required]**

By: Gail Darnell

Name: Gail Darnell  
(please print)

Title: Sec/Treas  
(please print)



**Contract Control Number:**

IN WITNESS WHEREOF, the parties have set their hands and affixed their seals at Denver, Colorado as of

SEAL

**CITY AND COUNTY OF DENVER**

ATTEST:

By \_\_\_\_\_

\_\_\_\_\_

APPROVED AS TO FORM:

REGISTERED AND COUNTERSIGNED:

By \_\_\_\_\_

By \_\_\_\_\_

By \_\_\_\_\_



**CITY AND COUNTY OF DENVER  
DEPARTMENT OF PUBLIC WORKS**

**General Contract Conditions**

**INDEX**

<b>TITLE 1</b>		
<b>DEFINITIONS</b>		<b>1</b>
101	CITY	1
102	CONTRACT	1
103	CONTRACT AMOUNT	1
104	CONTRACT DOCUMENTS	1
105	CONTRACT TIME	1
106	CONTRACTOR	2
107	CONTRACTOR PERSONNEL	2
108	DAYS	2
109	DEPUTY MANAGER	2
110	DESIGNER	2
111	FINAL COMPLETION	2
112	MANAGER	3
113	PRODUCT DATA	3
114	PROJECT	3
115	PROJECT MANAGER	3
116	SAMPLES	3
117	SHOP DRAWINGS	3
118	SUBCONTRACTOR	3
119	SUBSTANTIAL COMPLETION	3
120	SUPPLIER	4
121	WORK	4
<b>TITLE 2</b>		
<b>CITY ADMINISTRATIVE ORGANIZATIONS; LINE OF AUTHORITY</b>		<b>5</b>
201	DEPARTMENT OF AVIATION	5
202	MANAGER OF AVIATION	5
203	DEPARTMENT OF PUBLIC WORKS	5
204	MANAGER OF PUBLIC WORKS	5
205	BUILDING INSPECTION	5
206	ZONING	5
207	DIVISION OF SMALL BUSINESS OPPORTUNITY	6
208	CITY AUDITOR	6
209	MANAGER OF FINANCE	6
210	CITY ATTORNEY	6
211	OFFICE OF RISK MANAGEMENT	6
212	CITY'S CONTRACT ADMINISTRATION LINE OF AUTHORITY	6
213	CITY'S COMMUNICATION WITH THE CONTRACTOR	7

<b>TITLE 3</b>		
<b>CONTRACTOR PERFORMANCE AND SERVICES.....</b>		<b>8</b>
301 CONSIDERATION		
(CONTRACTOR'S PROMISE OF PERFORMANCE).....		8
302 NOTICE TO PROCEED AND COMPLETION OF THE WORK .....		8
303 EXACT CONTRACTOR PERFORMANCE .....		8
304 SUBSTITUTED PERFORMANCE.....		8
305 WORK PERFORMED UNDER ADVERSE		
WEATHER CONDITIONS.....		9
306 WORKING HOURS AND SCHEDULE .....		9
307 CONTRACTOR'S SUPERINTENDENT .....		10
308 COMMUNICATIONS .....		10
309 CONTRACTOR SUBMITTALS		
AND OTHER WRITTEN COMMUNICATIONS TO THE CITY.....		10
310 COMPETENCE OF CONTRACTOR'S WORK FORCE .....		11
311 NO EMPLOYMENT OF ILLEGAL ALIENS		
TO PERFORM WORK UNDER THE CONTRACT .....		11
312 CONDUCT OF CONTRACTOR'S PERSONNEL .....		12
313 SUGGESTIONS TO CONTRACTOR.....		12
314 WORK FORCE .....		12
315 CONSTRUCTION MACHINES AND STANDBY EQUIPMENT .....		13
316 CUTTING AND PATCHING THE WORK .....		13
317 PERMITS AND LICENSES .....		13
318 CONSTRUCTION SURVEYS .....		14
319 PRESERVATION OF PERMANENT		
LAND SURVEY CONTROL MARKERS .....		14
320 TRADEMARKS, COPYRIGHTS AND PATENTED DEVICES,		
MATERIALS, AND PROCESSES .....		15
321 PROJECT SIGNS.....		15
322 PUBLICITY AND ADVERTISING.....		16
323 TAXES .....		16
324 DOCUMENTS AND SAMPLES AT THE SITE .....		17
325 CLEANUP DURING CONSTRUCTION.....		17
326 SANITARY FACILITIES.....		18
327 POWER, LIGHTING, HEATING, VENTILATING,		
AIR CONDITIONING AND WATER SERVICES .....		18
<b>TITLE 4</b>		
<b>CONTRACT DOCUMENTS (DRAWINGS AND TECHNICAL SPECIFICATIONS).....</b>		<b>19</b>
401 CONTRACT DOCUMENTS - REVIEW AND INTERPRETATION.....		19
402 OWNERSHIP OF CONTRACT DRAWINGS		
AND TECHNICAL SPECIFICATIONS.....		20
403 CONTRACT DRAWINGS AND TECHNICAL SPECIFICATIONS		
ISSUED TO THE CONTRACTOR .....		20
404 REQUESTS FOR INFORMATION OR CLARIFICATION .....		21
405 SHOP DRAWINGS, PRODUCT DATA AND SAMPLES .....		21
406 SUBSTITUTION OF MATERIALS AND EQUIPMENT .....		22
<b>TITLE 5</b>		
<b>SUBCONTRACTS .....</b>		<b>24</b>
501 SUBCONTRACTS.....		24
502 SUBCONTRACTOR ACCEPTANCE .....		24
<b>TITLE 6</b>		
<b>TIME OF COMMENCEMENT AND COMPLETION .....</b>		<b>27</b>
601 BEGINNING, PROGRESS AND TIME OF COMPLETION .....		27
602 LIQUIDATED DAMAGES; ADMINISTRATIVE COSTS;		
ACTUAL DAMAGES.....		27

603	DELAY DAMAGES .....	28
<b>TITLE 7</b>		
<b>COOPERATION, COORDINATION AND RATE OF PROGRESS .....</b>		<b>29</b>
701	COOPERATION WITH OTHER WORK FORCES .....	29
702	COORDINATION OF THE WORK.....	30
703	COORDINATION OF PUBLIC CONTACT.....	30
704	RATE OF PROGRESS .....	30
<b>TITLE 8</b>		
<b>PROTECTION OF PERSONS AND PROPERTY .....</b>		<b>32</b>
801	SAFETY OF PERSONS .....	32
802	PROTECTIVE DEVICES AND SAFETY PRECAUTIONS .....	33
803	PROTECTION OF PROPERTY AND WORK IN PROGRESS .....	33
804	PROTECTION OF MUNICIPAL, PUBLIC SERVICE OR PUBLIC UTILITY SYSTEMS .....	34
805	PROTECTION OF STREET AND ROAD SYSTEM .....	35
806	PROTECTION OF DRAINAGE WAYS.....	36
807	PROTECTION OF THE ENVIRONMENT .....	36
808	HAZARDOUS AND EXPLOSIVE MATERIALS OR SUBSTANCES.....	37
809	ARCHAEOLOGICAL AND HISTORICAL DISCOVERIES .....	37
<b>TITLE 9</b>		
<b>COMPENSATION .....</b>		<b>38</b>
901	CONSIDERATION (CITY'S PROMISE TO PAY).....	38
902	PAYMENT PROCEDURE .....	38
903	SCHEDULE OF VALUES IN LUMP SUM CONTRACTS .....	39
904	UNIT PRICE CONTRACTS.....	39
905	PROGRESS PERIOD.....	39
906	APPLICATIONS FOR PAYMENT .....	40
907	RELEASES AND CONTRACTORS CERTIFICATIONS OF PAYMENT .....	41
908	RETAINAGE .....	41
909	ADDITIONAL WITHHOLDING OF PROGRESS PAYMENTS .....	42
910	FINAL ESTIMATE AND PAYMENT .....	43
911	ACCOUNTING OF COSTS AND AUDIT .....	43
<b>TITLE 10</b>		
<b>WAGE .....</b>		<b>45</b>
1001	PREVAILING WAGE ORDINANCE .....	45
1002	POSTING OF THE APPLICABLE WAGE RATES .....	45
1003	RATE AND FREQUENCY OF WAGES PAID.....	45
1004	REPORTING WAGES PAID .....	45
1005	FAILURE TO PAY PREVAILING WAGES .....	46
<b>TITLE 11</b>		
<b>CHANGES IN THE WORK, CONTRACT PRICE OR CONTRACT TIME .....</b>		<b>47</b>
1101	CHANGE ORDER .....	47
1102	CITY INITIATED CHANGES .....	47
1103	CONTRACTOR CHANGE REQUEST.....	48
1104	ADJUSTMENT TO CONTRACT AMOUNT .....	51
1105	TIME EXTENSIONS.....	54
<b>TITLE 12</b>		
<b>CONTRACTOR CLAIMS FOR ADJUSTMENT AND DISPUTES.....</b>		<b>56</b>
1201	NOTICE OF INTENT TO CLAIM .....	56
1202	SUBMITTAL OF CLAIMS .....	56
1203	WAIVER OF CLAIMS .....	58

<b>TITLE 13</b>	
<b>DISPUTES</b>	<b>59</b>
1301 DISPUTES	59
<b>TITLE 14</b>	
<b>SITE CONDITIONS</b>	<b>60</b>
1401 DIFFERING SITE CONDITIONS	60
1402 SITE INSPECTIONS AND INVESTIGATIONS	60
<b>TITLE 15</b>	
<b>PERFORMANCE AND PAYMENT BONDS</b>	<b>62</b>
1501 SURETY BONDS	62
1502 PERFORMANCE BOND	62
1503 PAYMENT BOND	62
<b>TITLE 16</b>	
<b>INSURANCE AND INDEMNIFICATION</b>	<b>63</b>
1601 INSURANCE	63
1602 DEFENSE AND INDEMNIFICATION	63
<b>TITLE 17</b>	
<b>INSPECTION AND DEFECTS</b>	<b>64</b>
1701 CONSTRUCTION INSPECTION BY THE CITY	64
1702 AUTHORITY OF INSPECTORS	64
1703 OBSERVABLE DEFECTS	64
1704 DEFECTS - UNCOVERING WORK	64
1705 LATENT DEFECTS	65
1706 REMOVAL OF DEFECTIVE MATERIALS AND WORK	65
<b>TITLE 18</b>	
<b>WARRANTIES, GUARANTEES AND CORRECTIVE WORK</b>	<b>66</b>
1801 CONTRACTOR'S WARRANTIES, GUARANTEES AND CORRECTION OF WORK	66
1802 PERFORMANCE DURING WARRANTY PERIOD	67
<b>TITLE 19</b>	
<b>SUBSTANTIAL COMPLETION OF THE WORK</b>	<b>69</b>
1901 CONTRACTOR'S NOTICE OF SUBSTANTIAL COMPLETION	69
1902 INSPECTION AND PUNCH LIST	69
1903 CERTIFICATE OF SUBSTANTIAL COMPLETION	69
1904 RIGHT OF EARLY OCCUPANCY OR USE	69
<b>TITLE 20</b>	
<b>FINAL COMPLETION AND ACCEPTANCE OF THE WORK</b>	<b>71</b>
2001 CLEAN-UP UPON COMPLETION	71
2002 FINAL COMPLETION AND ACCEPTANCE OF THE WORK	71
2003 FINAL SETTLEMENT	71
<b>TITLE 21</b>	
<b>SUSPENSION OF WORK</b>	<b>74</b>
2101 SUSPENSION OF WORK	74
2102 SUSPENSION OF THE WORK FOR THE CITY'S CONVENIENCE	74
2103 SUSPENSION BECAUSE OF ORDER OF CITY, STATE OR FEDERAL COURT OR AGENCY	75
2104 SUSPENSION RESULTING FROM CONTRACTOR'S FAILURE TO PERFORM	75



<b>TITLE 22</b>	
<b>CITY'S RIGHT TO TERMINATE THE CONTRACT .....</b>	<b>76</b>
2201 TERMINATION OF CONTRACT FOR CAUSE .....	76
2202 TERMINATION OF CONTRACT FOR CONVENIENCE OF THE CITY .....	77
 <b>TITLE 23</b>	
<b>MISCELLANEOUS PROVISIONS .....</b>	<b>80</b>
2301 PARTIES TO THE CONTRACT.....	80
2302 FEDERAL AID PROVISIONS.....	80
2303 NO WAIVER OF RIGHTS .....	80
2304 NO THIRD PARTY BENEFICIARY .....	80
2305 GOVERNING LAW; VENUE.....	81
2306 ABBREVIATIONS .....	81
2307 STATUTE OF LIMITATIONS IN C.R.S. § 13-80-102(1)(h) .....	81

**CITY AND COUNTY OF DENVER**  
**DEPARTMENT OF PUBLIC WORKS**  
**SPECIAL CONTRACT CONDITIONS**

**SC-1 CONSTRUCTION SPECIFICATIONS**

Except as amended herein or in the attached Technical Specifications, all Work performed under the terms of this Contract shall be governed by the applicable provisions of the following latest editions:

City and County of Denver:

*Standard Specifications for Construction, GENERAL CONTRACT CONDITIONS,*  
2011 Edition.

*Transportation Standards and Details for the Engineering Division*

*City and County of Denver Traffic Standard Drawings*

Wastewater Management Division

– *Standard Detail Drawings*

– *Public Works Wastewater Capital Projects Management Standard Construction Specifications*

Colorado Department of Transportation:

*Standard Specifications for Road and Bridge Construction*  
(Sections 200 through 700 of the 2011 Edition)

Federal Highway Administration:

*Manual on Uniform Traffic Control Devices for Streets & Highways* (MUTCD)

Building & Fire Codes:

*Building Code of the City and County of Denver*

(International Building Code 2015 Series, City and County of Denver Amendments 2016)

*National Fire Protection Association Standards*

(As referenced in the Building Code of the City and County of Denver)

The aforementioned City and County of Denver documents are available for review at the Capital Projects Management Office, 201 W. Colfax Ave., Dept. 506, (5<sup>th</sup> floor), Denver, CO 80202. The *Standard Specifications for Construction, GENERAL CONTRACT CONDITIONS* is available at: <https://www.denvergov.org/content/denvergov/en/contract-administration/contractor-resources.html>. *Transportation Standards and Details for the Engineering Division* and the Wastewater Management Division – *Standard Detail Drawings*, are available at <http://www.denvergov.org>.

The “*Colorado Department of Transportation Standard Specifications for Road and Bridge Construction*” is available for review on CDOT’s website at <http://www.coloradodot.info/> and can be purchased from the Colorado Department of Transportation.

The *Manual on Uniform Traffic Control Devices for Streets & Highways* is available for review at the Federal Highway Administration Website at: [www.fhwa.dot.gov](http://www.fhwa.dot.gov), The FHWA website also contains purchasing information.

**SC-2 DEPUTY MANAGER / CITY ENGINEER**

General condition 109 DEPUTY MANAGER is hereby deleted in its entirety and replaced with the following:

The “Deputy Manager” means the official who reports directly to the Manager and exercises supervisory responsibility in the City agency defined in Title 2 herein that is responsible for the Project. The Manager hereby designates the City Engineer as the Deputy Manager for purposes of this Contract. The City Engineer shall have responsibility for this Project and shall undertake all duties, responsibilities, rights and authority, including specific actions and decisions, delegated to the Deputy Manager under the various terms and conditions of this Contract.

**SC-3 ENGINEERING DIVISION / CITY ENGINEER**

The Engineering Division is a unit of the Department of Public Works and is supervised by the City Engineer, who is subordinate to the Manager of Public Works. This Division is responsible for the planning, design, construction, operation and maintenance of all of the City's transportation facilities and the planning, design and construction of all of the City’s wastewater facilities, except for the City's Municipal Airport System. All other references to the Transportation Division or the Deputy Manager of Public Works for Transportation are deleted and replaced with references to the Engineering Division and City Engineer, respectively.

**SC-4 WASTEWATER MANAGEMENT DIVISION**

The Wastewater Management Division is a unit of the Department of Public Works and is supervised by the Deputy Manager of Public Works for Wastewater Management, who is subordinate to the Manager of Public Works. This Division is responsible for the operation and maintenance of the City's wastewater facilities.

**SC-5 CITY DELEGATION OF AUTHORITY**

With reference to General Contract Condition 109, DEPUTY MANAGER and General Contract Condition 212, CITY’S CONTRACT ADMINISTRATION LINE OF AUTHORITY, the Manager hereby designates the City Engineer as the City official responsible for those certain actions and decisions designated as the responsibility of the Deputy Manager under the General Conditions and delegates to the City Engineer the authority necessary to undertake those responsibilities under this Contract. The Director shall have supervisory responsibility over the Project Manager. Additionally, Contractor questions concerning the Plans and Technical Specifications shall be directed to:

**Denver Department of Public Works / Engineering Division,**

Project Manager  
City Project Manager

Lindsey Chieduko

Telephone  
(303) 446-3548

**SC-6 LIQUIDATED DAMAGES**

Should the Contractor fail to complete all Work within the Contract Time allocated under the Contract Form at Paragraph 3, TERMS OF PERFORMANCE, the Contractor shall become liable to the City and County of Denver for liquidated damages, and not as a penalty, at the rate of \$1,000.00 for each Day that the Contractor exceeds the time limits herein specified, all in accordance with provisions of General Contract Condition 602, LIQUIDATED DAMAGES; ADMINISTRATIVE COSTS; ACTUAL DAMAGES.

Representative hourly rates for the City administrative costs described in General Contract Condition 602.2 shall be as follows for this Project:

Project Manager	\$69 per hour
Project Engineer	\$63 per hour
Inspector	\$49 per hour
Surveying, if necessary	\$100 per hour

**SC-7 SUBCONTRACTS**

In accordance with General Contract Condition 501, SUBCONTRACTS, no limit shall apply to that percentage of the Work, which may be sublet providing that the subcontractors receive prior approval in accordance with General Contract Condition 502, SUBCONTRACTOR ACCEPTANCE.

**SC-8 RESERVED**

**SC-9 PAYMENTS TO CONTRACTORS**

The application for payment shall be submitted through Textura® Corporations Construction Management Website. Contractor recognizes and agrees that it shall be required to use the Textura Construction Payment Management System for this Project to request payment from the City and to pay subcontractors. All certified subcontractors or suppliers who are listed for participation towards any assigned program goal must be paid via Textura®. Contractor further agrees that, to the fullest extent possible within Textura, the City shall be entitled to all non-Confidential records, reports, data and other information related to the project that are available to Contractor through Textura, including, but not limited to, information related to Contractor and subcontractor billings. To that end, Contractor agrees it will activate any available settings within Textura necessary to grant the City access to such non-Confidential information related to the contract and the project. Applications for payment shall be based on the Contract Unit Prices or the approved Schedule of Values described in GC 903.1

In accordance with General Contract Condition 902, PAYMENT PROCEDURE, the party(ies) responsible for review of all Pay Applications shall be:

<u>Agency/Firm</u>	<u>Name</u>	<u>Telephone</u>
Public Works	Lindsey Chieduko	(303) 446-3548

In accordance with General Contract Condition 906, APPLICATIONS FOR PAYMENT, each Application submitted shall include the following:

1. The estimate of Work completed shall be based on the approved schedule of values or unit prices, as applicable, and the percent of the Work complete.
2. Each Application for Payment shall include each and every independent subcontractor's payroll information including pay dates and pay amounts.
3. The Contractor shall also submit to the Auditor and other appropriate officials of the City in a timely fashion, information required by General Contract Condition 1004, REPORTING WAGES PAID.
4. Applications for Payment must be accompanied by completed Partial or Final Claim Release Form, as appropriate, from EACH subcontractor and supplier, **AND** the Contractors' Certification of Payment Form (CCP), unless an exception is approved pursuant to General contract condition 907.

The forms, Final/Partial Release and Certificate of Payment (Subcontractor/Supplier) and the Contractor's Certification of Payment (CCP), both of which must be used are attached below. If subcontractor or supplier payments are disbursed via Textura® CPM, those systems generated Release and CCP forms are acceptable.

**DEPARTMENT OF PUBLIC WORKS  
Engineering Division**

**FINAL/PARTIAL RELEASE AND CERTIFICATE OF PAYMENT  
(SUBCONTRACTOR/SUPPLIER)**

(PROJECT NO. and NAME)	Date: _____, 20__.
(NAME OF CONTRACTOR)	Subcontract #: _____.
(NAME OF SUBCONTRACTOR/SUPPLIER)	Subcontract Value: \$ _____.
Check Applicable Box:	Last Progress Payment: \$ _____.
<input type="checkbox"/> MBE <input type="checkbox"/> WBE	Date: _____.
	Total Paid to Date: \$ _____.
	Date of Last Work: _____.

The Undersigned hereby certifies that all costs, charges or expenses incurred by the undersigned or on behalf of the undersigned for any work, labor or services performed and for any materials, supplies or equipment provided on the above referenced Project or used in connection with the above referenced Subcontract (the "Work Effort") have been duly paid in full.

The Undersigned further certifies that each of the undersigned's subcontractors and suppliers that incurred or caused to be incurred, on their behalf, costs, charges or expenses in connection with the undersigned's Work Effort on the above referenced Project have been duly paid in full.

In consideration of \$\_\_\_\_\_ representing the Last Progress Payment referenced above and in further consideration of the Total Paid to Date, also referenced above, and other good and valuable consideration received and accepted by the undersigned this \_\_\_\_ day of \_\_\_\_\_, 20\_\_, the Undersigned hereby releases and discharges the City and County of Denver (the "City"), the above referenced City Project, the City's premises and property and the above referenced Contractor from all claims, liens, rights, liabilities, demands and obligations, whether known or unknown, of every nature arising out of or in connection with the performance of the work effort.

As additional consideration for the payments referenced above, the undersigned agrees to defend, indemnify and save and hold harmless the City, its officers, employees, agents and assigns and the above-referenced Contractor from and against all costs, losses, damages, causes of action, judgments under the subcontract and expenses arising out of or in connection with any claim or claims against the City or the Contractor which arise out of the Undersigned's performance of the Work Effort and which may be asserted by the Undersigned or any of its suppliers or subcontractors of any tier or any of their representatives, officers, agents, or employees.

It is acknowledged that this release is for the benefit of and may be relied upon by the City and the referenced Contractor.

The foregoing shall not relieve the undersigned of any obligation under the provisions of the Undersigned's subcontract, as the subcontract may have been amended, which by their nature survive completion of the Undersigned's work effort including, without limitation, warranties, guarantees, insurance requirements and indemnities.

STATE OF COLORADO    ) ss. CITY OF _____)	_____ (Name of Subcontractor)
Signed and sworn before me this day of _____, 20__.	By: _____
_____ Notary Public/Commissioner of Oaths My Commission Expires	Title: _____





## Instructions for Completing the Contractor/Consultant Certification of Payment Form

Office of Economic Development  
Division of Small Business Opportunity  
Compliance Unit  
201 W. Colfax Ave. Dept. 907  
Denver, CO 80202  
Phone: 720-913-1999  
[DSBO@denvergov.org](mailto:DSBO@denvergov.org)

**Note:** The attached Contractor/Consultant Certification of Payment form must be completed by the Contractor/ Subconsultant and all subcontractors/subconsultant or suppliers used on the project at **any tier** and submitted with each pay application. The Contractor/Consultant is responsible for the accuracy of all information provided and is required to have each subcontractor/subconsultant or supplier fill out the appropriate forms. Please be sure to complete all information requested at the top of the form, including the name of the person who prepared this form.

If you reproduce this form, you must continue to list each of the originally listed firms, as well as any additional firms used during the performance period of the contract. Please complete an additional CCP if there is second tier-ing involved.

If you have any questions, please call the Compliance Unit of DSBO at 720.913.1999.

### Instructions for Completing the Contractor/Consultant Certification of Payment Form, per Column

**Contractor/Subcontractor or Subconsultant/Supplier Name:** In the space provided, list all subcontractors/ subconsultants and suppliers used on the project. For all M/W/S/E/DBEs use the exact name listed in the DSBO Directory.

**M/W/S/E/DBE/NON:** For each name listed, indicate whether the entity is a certified M/W/S/E/DBE.

**Column A:** Provide the contract amount, as listed at bid time, for the Contractor/Consultant and each subcontractor/subconsultant or supplier.

**Column B:** Provide the percentage portion of each listed subcontractor/subconsultant or supplier contract amount (Column A) compared to the total original contract amount in (I).

**Column C:** Provide the original contract amount (Column A) for each subcontractor/subconsultant or supplier plus any awarded alternate and/or change order amounts applicable. If an alternate/change order does not apply to the listed firm, re-enter the original contract amount (Column A).

**Column D:** Provide the percent portion of each listed subcontractor/subconsultant or supplier contract amount (Column C) compare to the current total contract amount in (II).

**Column E:** Provide the amount requested for work performed or materials supplied by each listed subcontractor/subconsultant or supplier for this pay application. The sum of the items in this column should equal the estimated amount requested for this pay application.

**Column F:** Provide the amount paid to each subcontractor/subconsultant or supplier on the previous pay application. Enter the previous pay application number in the column heading. The sum of the items listed in this column should equal the warrant amount paid to the Contractor/Consultant on the previous pay application. The amounts paid to the subcontractor/subcontractor or suppliers should be the actual amount of each check issued.

**Column G:** Provide the net paid to date for the Contractor/Subconsultant and each listed subcontractor/subconsultant or supplier.

**Column H:** Provide the percent portion of the net paid to date (Column G) for the Contractor/Subconsultant and each listed subcontractor/subconsultant or supplier of the current total contract amount in (II).

Rev 031816

## **SC-10 CONTRACT FORMS**

In accordance with the terms and conditions of the Contract Documents, the City requires the use of certain form documents in complying with or satisfying various obligations, notifications and conditions in contracting with the City or performing Work hereunder. These form documents are referenced by title throughout the Contract Documents for mandatory use as directed. The following are the forms that shall be detached and utilized in accordance with the Contract Documents:

1. Performance and Payment Bond
2. Performance and Payment Bond Surety Authorization Letter (Sample)
3. Final/Partial Lien Release.

The following are forms that will be issued by the City during construction:

1. Notice to Apparent Low Bidder (Sample)
2. Notice to Proceed (Sample)
3. Certificate of Contract Release (Sample)

## **SC-11 CONSTRUCTION INSPECTION BY THE CITY**

General Condition 1701, CONSTRUCTION INSPECTION BY THE CITY, is modified as follows:

**.1** Persons who are employees of the City or who are under contract to the City or the City as lessee will be assigned to inspect and test the Work. These persons may perform any tests and observe the Work to determine whether or not designs, materials used, manufacturing and construction processes and methods applied, and equipment installed satisfy the requirements of the drawings and specifications, accepted Shop Drawings, Product Data and Samples, and the General Contractor's warranties and guarantees. The General Contractor shall permit these inspectors unlimited access to the Work and provide means of safe access to the Work, which cost shall be included as a Cost of the Work without any increase to the Guaranteed Maximum Price. In addition, General Contractor shall provide whatever access and means of access are needed to off-site facilities used to store or manufacture materials and equipment to be incorporated into the Work and shall respond to any other reasonable request to further the inspector's ability to observe or complete any tests. Such inspections shall not relieve the General Contractor of any of its quality control responsibilities or any other obligations under the Contract. All inspections and all tests conducted by the City are for the convenience and benefit of the City. These inspections and tests do not constitute acceptance of the materials or Work tested or inspected, and the City may reject or accept any Work or materials at any time prior to the inspections pursuant to G.C. 2002, whether or not previous inspections or tests were conducted by the inspector or a City representative.

**.2** Building Inspection will perform building code compliance inspections for structures designed for human occupancy. It is the General Contractor's responsibility to schedule and obtain these inspections. If a code compliance inspection results in identification of a condition which will be at variance to the Contract Documents, the General Contractor shall immediately notify the Project Manager and confirm such notification with formal correspondence no later than forty-eight (48) hours after the occurrence.

**.3** When any unit of government or political subdivision, utility or Railroad Corporation is to pay a portion of the cost of the Work, its respective representatives shall have the right to inspect the Work. This inspection shall not make any unit of government or political subdivision, utility or Railroad Corporation a party to the Contract, and shall not interfere with the rights of either party.

## **SC-12 DISPOSAL OF NON-HAZARDOUS WASTE AT DADS**

In accordance with the Landfill Agreement made between the City and Waste Management of Colorado, Inc., bidders will be required to haul dedicated loads (non-hazardous entire loads of waste) to the Denver-Arapahoe Disposal Site ("DADS") for disposal. DADS is located at Highway 30 and Hampden Avenue in Arapahoe County, Colorado. The City will pay all fees associated with such disposal but the bidder shall be responsible for the costs of transporting the loads. Non-hazardous waste is defined as those substances and materials not defined or classified as hazardous by the Colorado Hazardous Waste Commission pursuant to C.R.S. §25-15-101(6), as amended from time to time, and includes construction debris, soil and asbestos. Bidders shall not use Gun Club Road between I-70 and Mississippi Avenue as a means of access to DADS.



### SC-13 PROHIBITION ON USE OF CCA-TREATED WOOD PRODUCTS

The use of any wood products pressure-treated with chromated copper arsenate (CCA) is prohibited. Examples of CCA-treated wood products include wood used in play structures, decks, picnic tables, landscaping timbers, fencing, patios, walkways and boardwalks.

### SC-14 WAIVER OF: PART 8 OF ARTICLE 20 OF TITLE 13, COLORADO REVISED STATUTES.

The Contractor specifically waives all the provisions of Part 8 of Article 20 of Title 13, Colorado Revised Statutes regarding defects in the Work under this Construction Contract.

### SC-15 ATTORNEY'S FEES

Colorado Revised Statute 38-26-107 requires that in the event any person or company files a verified statement of amounts due and unpaid in connection with a claim for labor and materials supplied on this project, the City shall withhold from payments to the Contractor sufficient funds to insure the payment of any such claims. Should the City and County of Denver be made a party to any lawsuit to enforce such unpaid claims or any lawsuit arising out of or relating to such withheld funds, the Contractor agrees to pay to the City its costs and a reasonable attorney's fee which cost shall be included as a Cost of the Work.

Because the City Attorney Staff does not bill the City for legal services on an hourly basis, the Contractor agrees a reasonable fee shall be computed at the rate of one hundred dollars per hour of City Attorney time.

### SC-16 INSURANCE

General Condition 1601 is hereby deleted in its entirety and replaced with the following:

(1) **General Conditions:** Contractor agrees to secure, at or before the time of execution of this Agreement, the following insurance covering all operations, goods or services provided pursuant to this Agreement. Contractor shall keep the required insurance coverage in force at all times during the term of the Agreement, or any extension thereof, during any warranty period, and for eight (8) years after termination of the Agreement. The required insurance shall be underwritten by an insurer licensed or authorized to do business in Colorado and rated by A.M. Best Company as "A-"VIII or better. Each policy shall contain a valid provision or endorsement requiring notification to the City in the event any of the required policies be canceled or non-renewed before the expiration date thereof. Such written notice shall be sent to the parties identified in the Notices section of this Agreement. Such notice shall reference the City contract number listed on the signature page of this Agreement. Said notice shall be sent thirty (30) days prior to such cancellation or non-renewal unless due to non-payment of premiums for which notice shall be sent ten (10) days prior. If such written notice is unavailable from the insurer, contractor shall provide written notice of cancellation, non-renewal and any reduction in coverage to the parties identified in the Notices section by certified mail, return receipt requested within three (3) business days of such notice by its insurer(s) and referencing the City's contract number. If any policy is in excess of a deductible or self-insured retention, the City must be notified by the Contractor. Contractor shall be responsible for the payment of any deductible or self-insured retention. The insurance coverages specified in this Agreement are the minimum requirements, and these requirements do not lessen or limit the liability of the Contractor. The Contractor shall maintain, at its own expense, any additional kinds or amounts of insurance that it may deem necessary to cover its obligations and liabilities under this Agreement.

(2) **Proof of Insurance:** Contractor shall provide a copy of this Agreement to its insurance agent or broker. Contractor may not commence services or work relating to the Agreement prior to placement of coverage. Contractor certifies that the certificate of insurance attached as part of the Contract Documents, preferably an ACORD certificate, complies with all insurance requirements of this Agreement. The City requests that the City's contract number be referenced on the Certificate. The City's acceptance of a certificate of insurance or other proof of insurance that does not comply with all insurance requirements set forth in this Agreement shall not act as a waiver of Contractor's breach of this Agreement or of any of the City's rights or remedies under this Agreement. The City's Risk Management Office may require additional proof of insurance, including but not limited to policies and endorsements.

(3) **Additional Insureds:** For Commercial General Liability and Auto Liability, Contractor and subcontractor's insurer(s) shall name the City and County of Denver, its elected and appointed officials, employees and volunteers as additional insured.

(4) **Waiver of Subrogation:** For all coverages, Contractor's insurer shall waive subrogation rights against the City.

(5) **Subcontractors and Subconsultants:** All subcontractors and subconsultants (including independent contractors, suppliers or other entities providing goods or services required by this Agreement) shall be subject to all of the requirements herein and shall procure and maintain the same coverages required of the Contractor. Contractor shall include all such subcontractors as additional insured under its policies (with the exception of

Workers' Compensation) or shall ensure that all such subcontractors and subconsultants maintain the required coverages. Contractor agrees to provide proof of insurance for all such subcontractors and subconsultants upon request by the City.

(6) **Workers' Compensation/Employer's Liability Insurance:** Contractor shall maintain the coverage as required by statute for each work location and shall maintain Employer's Liability insurance with limits of \$100,000 per occurrence for each bodily injury claim, \$100,000 per occurrence for each bodily injury caused by disease claim, and \$500,000 aggregate for all bodily injuries caused by disease claims. Contractor expressly represents to the City, as a material representation upon which the City is relying in entering into this Agreement, that none of the Contractor's officers or employees who may be eligible under any statute or law to reject Workers' Compensation Insurance shall effect such rejection during any part of the term of this Agreement, and that any such rejections previously effected, have been revoked as of the date Contractor executes this Agreement.

(7) **Commercial General Liability:** Contractor shall maintain a Commercial General Liability insurance policy with limits of \$1,000,000 for each occurrence, \$1,000,000 for each personal and advertising injury claim, \$2,000,000 products and completed operations aggregate, and \$2,000,000 policy aggregate.

(8) **Business Automobile Liability:** Contractor shall maintain Business Automobile Liability with limits of \$1,000,000 combined single limit applicable to all owned, hired and non-owned vehicles used in performing services under this Agreement

(9) **Additional Provisions:**

- (a) For Commercial General Liability, the policies must provide the following:
  - (i) That this Agreement is an Insured Contract under the policy;
  - (ii) Defense costs in excess of policy limits;
  - (iii) A severability of interests or separation of insureds provision (no insured vs. insured exclusion); and
  - (iv) A provision that coverage is primary and non-contributory with other coverage or self-insurance maintained by the City.
- (b) For claims-made coverage:
  - (i) The retroactive date must be on or before the contract date or the first date when any goods or services were provided to the City, whichever is earlier
- (c) Contractor shall advise the City in the event any general aggregate or other aggregate limits are reduced below the required per occurrence limits. At their own expense, and where such general aggregate or other aggregate limits have been reduced below the required per occurrence limit, the Contractor will procure such per occurrence limits and furnish a new certificate of insurance showing such coverage is in force.

## SC-17 GREENPRINT DENVER REQUIREMENTS

In accordance with the City and County of Denver Executive Order 123: Greenprint Denver Office and Sustainability Policy, as amended, Contractor shall adhere to sections of Executive Order 123 pertinent to the construction of the built environment. This includes but is not limited to: all construction and renovation of buildings shall follow instructions and memorandum for high performance buildings; horizontal projects shall include the use of fly ash concrete and recycled aggregate where possible; and, all projects shall recycle construction and demolition waste, and install materials that contain recycled content whenever possible using the U.S. Green Building Council Leadership in Energy and Environmental Design (LEED) as guidance. Non-hazardous solid waste that is eligible for reuse or recycling is not subject to the DADS disposal requirement defined in SC-12.

A completed "Greenprint Denver Closeout Form for Construction Projects" shall be delivered to the Project Manager as a submittal requirement of Final Acceptance.

<http://www.denvergov.org/constructioncontracts/Home/ContractorResources/tabid/443154/Default.aspx>

**CITY AND COUNTY OF DENVER**  
**DEPARTMENT OF PUBLIC WORKS**

**PERFORMANCE AND PAYMENT BOND**

KNOW ALL MEN BY THESE PRESENTS, that we, the undersigned **KEENE CONCRETE, INC.**, a corporation organized and existing under and by virtue of the laws of the State of **COLORADO**, hereafter referred to as the "Contractor", and **The Ohio Casualty Insurance Company, 62 Maple Ave., Keene, NH 03431**, a corporation organized and existing under and by virtue of the laws of the State of **New Hampshire**, and authorized to transact business in the State of Colorado, as Surety, are held and firmly bound unto the CITY AND COUNTY OF DENVER, a municipal corporation of the State of Colorado, hereinafter referred to as the "City", in the penal sum of **Two Million Four Hundred Sixty Eight Thousand Nine Hundred and Fifty Dollars and Zero Cents (\$2,468,950.00)**, lawful money of the United States of America, for the payment of which sum, well and truly to be made, we bind ourselves and our heirs, executors, administrators, successors and assigns, jointly and severally, firmly by these presents;

THE CONDITION OF THE FOREGOING OBLIGATION IS SUCH THAT:

WHEREAS, the above bounden Contractor has entered into a written contract with the aforesaid City for furnishing all labor and tools, supplies, equipment, superintendence, materials and everything necessary for and required to do, perform and complete the construction of **CONTRACT NO. 201845779 2018 CITYWIDE BOND CONCRETE REPAIR**, Denver, Colorado, and has bound itself to complete the project within the time or times specified or pay liquidated damages, all as designated, defined and described in the said Contract and Conditions thereof, and in accordance with the Plans and Technical Specifications therefore, a copy of said Contract being made a part hereof;

NOW, THEREFORE, if the said Contractor shall and will, in all particulars well and truly and faithfully observe, perform and abide by each and every Covenant, Condition and part of said Contract, and the Conditions, Technical Specifications, Plans, and other Contract Documents thereto attached, or by reference made a part thereof and any alterations in and additions thereto, according to the true intent and meaning in such case, then this obligation shall be and become null and void; otherwise, it shall remain in full force and effect;

PROVIDED FURTHER, that if the said Contractor shall satisfy all claims and demands incurred by the Contractor in the performance of said Contract, and shall fully indemnify and save harmless the City from all damages, claims, demands, expense and charge of every kind (including claims of patent infringement) arising from any act, omission, or neglect of said Contractor, its agents, or employees with relation to said work; and shall fully reimburse and repay to the City all costs, damages, and expenses which it may incur in making good any default based upon the failure of the Contractor to fulfill its obligation to furnish maintenance, repairs or replacements for the full guarantee period provided in the Contract Documents, then this obligation shall be null and void; otherwise it shall remain in full force and effect;

PROVIDED FURTHER, that if said Contractor shall at all times promptly make payments of all amounts lawfully due to all persons supplying or furnishing it or its subcontractors with labor and materials, rental machinery, tools or equipment used or performed in the prosecution of work provided for in the above Contract and that if the Contractor will indemnify and save harmless the City for the extent of any and all payments in connection with the carrying out of such Contract, then this obligation shall be null and void; otherwise it shall remain in full force and effect;

PROVIDED FURTHER, that if the said Contractor fails to duly pay for any labor, materials, team hire, sustenance, provisions, provender, gasoline, lubricating oils, fuel oils, grease, coal, or any other supplies or materials used or consumed by said Contractor or its subcontractors in performance of the work contracted to be done, or fails to pay any person who supplies rental machinery, tools or equipment, all amounts due as the result of the use of such machinery, tools or equipment in the prosecution of the work, the Surety will pay the same in any amount not exceeding the amount of this obligation, together with interest as provided by law;

PROVIDED FURTHER, that the said Surety, for value received, hereby stipulates and agrees that no change, extension of time, alteration or addition to the terms of the Contract, or to contracts with others in connection with this project, or the work to be performed thereunder, or the Technical Specifications and Plans accompanying the same, shall in any way affect its obligation on this bond and it does hereby waive notice of any change, extension of time, alteration or addition to the terms of the Contract, or contracts, or to the work, or to the Technical Specifications and Plans.

IN WITNESS WHEREOF, said Contractor and said Surety have executed these presents as of this 8th day of February, 2019.

Attest:

Gail Darnell  
Secretary Gail Darnell

Keene Concrete, Inc.

Contractor

By:

Chris C. Bailey  
President Chris C. Bailey

The Ohio Casualty Insurance Company

Surety

By:

Tristin Rosen  
Attorney-In-Fact Tristin Rosen

(Accompany this bond with Attorney-in-Fact's authority from the Surety to execute bond, certified to include the date of the bond).

APPROVED AS TO FORM:  
Attorney for the City and County of  
Denver

By:

Jill Ferguson  
Jill Ferguson  
Assistant City Attorney

APPROVED FOR THE CITY AND COUNTY OF  
DENVER

By:

[Signature]  
MAYOR

By:

[Signature]  
EXECUTIVE DIRECTOR OF PUBLIC WORKS



This Power of Attorney limits the acts of those named herein, and they have no authority to bind the Company except in the manner and to the extent herein stated.

Liberty Mutual Insurance Company
The Ohio Casualty Insurance Company
West American Insurance Company

Certificate No: 8200136

POWER OF ATTORNEY

KNOWN ALL PERSONS BY THESE PRESENTS: That The Ohio Casualty Insurance Company is a corporation duly organized under the laws of the State of New Hampshire, that Liberty Mutual Insurance Company is a corporation duly organized under the laws of the State of Massachusetts, and West American Insurance Company is a corporation duly organized under the laws of the State of Indiana (herein collectively called the "Companies"), pursuant to and by authority herein set forth, does hereby name, constitute and appoint, Annette M. Campbell, Janine Darling, Carolyn Evans, Mary E. Ficken, Loren B. Mahoney, Judith Miller, Thomas W. Patton, Tristin Rosen, Virginia Shaw

all of the city of Greenwood Village state of CO each individually if there be more than one named, its true and lawful attorney-in-fact to make, execute, seal, acknowledge and deliver, for and on its behalf as surety and as its act and deed, any and all undertakings, bonds, recognizances and other surety obligations, in pursuance of these presents and shall be as binding upon the Companies as if they have been duly signed by the president and attested by the secretary of the Companies in their own proper persons.

IN WITNESS WHEREOF, this Power of Attorney has been subscribed by an authorized officer or official of the Companies and the corporate seals of the Companies have been affixed thereto this 17th day of December, 2018.



Liberty Mutual Insurance Company
The Ohio Casualty Insurance Company
West American Insurance Company

By: David M. Carey, Assistant Secretary

State of PENNSYLVANIA ss
County of MONTGOMERY

On this 17th day of December, 2018 before me personally appeared David M. Carey, who acknowledged himself to be the Assistant Secretary of Liberty Mutual Insurance Company, The Ohio Casualty Company, and West American Insurance Company, and that he, as such, being authorized so to do, execute the foregoing instrument for the purposes therein contained by signing on behalf of the corporations by himself as a duly authorized officer.

IN WITNESS WHEREOF, I have hereunto subscribed my name and affixed my notarial seal at King of Prussia, Pennsylvania, on the day and year first above written.



COMMONWEALTH OF PENNSYLVANIA
Notarial Seal
Teresa Pastella, Notary Public
Upper Merion Twp., Montgomery County
My Commission Expires March 28, 2021
Member, Pennsylvania Association of Notaries

By: Teresa Pastella, Notary Public

This Power of Attorney is made and executed pursuant to and by authority of the following By-laws and Authorizations of The Ohio Casualty Insurance Company, Liberty Mutual Insurance Company, and West American Insurance Company which resolutions are now in full force and effect reading as follows:

ARTICLE IV - OFFICERS: Section 12. Power of Attorney.

Any officer or other official of the Corporation authorized for that purpose in writing by the Chairman or the President, and subject to such limitation as the Chairman or the President may prescribe, shall appoint such attorneys-in-fact, as may be necessary to act in behalf of the Corporation to make, execute, seal, acknowledge and deliver as surety any and all undertakings, bonds, recognizances and other surety obligations. Such attorneys-in-fact, subject to the limitations set forth in their respective powers of attorney, shall have full power to bind the Corporation by their signature and execution of any such instruments and to attach thereto the seal of the Corporation. When so executed, such instruments shall be as binding as if signed by the President and attested to by the Secretary. Any power or authority granted to any representative or attorney-in-fact under the provisions of this article may be revoked at any time by the Board, the Chairman, the President or by the officer or officers granting such power or authority.

ARTICLE XIII - Execution of Contracts: Section 5. Surety Bonds and Undertakings.

Any officer of the Company authorized for that purpose in writing by the chairman or the president, and subject to such limitations as the chairman or the president may prescribe, shall appoint such attorneys-in-fact, as may be necessary to act in behalf of the Company to make, execute, seal, acknowledge and deliver as surety any and all undertakings, bonds, recognizances and other surety obligations. Such attorneys-in-fact subject to the limitations set forth in their respective powers of attorney, shall have full power to bind the Company by their signature and execution of any such instruments and to attach thereto the seal of the Company. When so executed such instruments shall be as binding as if signed by the president and attested by the secretary.

Certificate of Designation - The President of the Company, acting pursuant to the Bylaws of the Company, authorizes David M. Carey, Assistant Secretary to appoint such attorneys-in-fact as may be necessary to act on behalf of the Company to make, execute, seal, acknowledge and deliver as surety any and all undertakings, bonds, recognizances and other surety obligations.

Authorization - By unanimous consent of the Company's Board of Directors, the Company consents that facsimile or mechanically reproduced signature of any assistant secretary of the Company, wherever appearing upon a certified copy of any power of attorney issued by the Company in connection with surety bonds, shall be valid and binding upon the Company with the same force and effect as though manually affixed.

I, Renee C. Llewellyn, the undersigned, Assistant Secretary, The Ohio Casualty Insurance Company, Liberty Mutual Insurance Company, and West American Insurance Company do hereby certify that the original power of attorney of which the foregoing is a full, true and correct copy of the Power of Attorney executed by said Companies, is in full force and effect and has not been revoked.

IN TESTIMONY WHEREOF, I have hereunto set my hand and affixed the seals of said Companies this \_\_\_ day of \_\_\_\_\_, \_\_\_\_\_.



By: Renee C. Llewellyn, Assistant Secretary

Not valid for mortgage, note, loan, letter of credit, currency rate, interest rate or residual value guarantees.

To confirm the validity of this Power of Attorney call 1-610-832-8240 between 9:00 am and 4:30 pm EST on any business day.



**CCIG**  
INSURANCE · BENEFITS

5660 Greenwood Plaza Blvd, Ste 500  
Greenwood Village, CO 80111

P ■ 303 799 0110  
800 777 5035  
F ■ 303 799 0156

**PERFORMANCE AND PAYMENT BOND  
SURETY AUTHORIZATION**

FAX NUMBER: 720-913-3183  
TELEPHONE NUMBER: 720-913-3267

Assistant City Attorney  
201 W. Colfax Ave. Dept 1207  
Denver, Colorado 80202

RE: Keene Concrete, Inc.

Contract No:	201845779
Project Name:	2018 Citywide Bond Concrete Repair
Contract Amount:	\$2,468,950.00
Performance and Payment Bond No.:	906222311

Dear Assistant City Attorney,

The Performance and Payment Bonds covering the above captioned project were executed by this agency, through The Ohio Casualty Insurance Company, on January 25th, 2019.

We hereby authorize the City and County of Denver, Department of Public Works, to date all bonds and powers of attorney to coincide with the date of the contract.

If you should have any additional questions or concerns, please don't hesitate to give me a call at 720-330-7922

Thank you.

Sincerely,

Thomas W. Patton  
Attorney-in-fact



KEENCON-01

HANNAHA

# CERTIFICATE OF LIABILITY INSURANCE

DATE (MM/DD/YYYY)  
1/25/2019

THIS CERTIFICATE IS ISSUED AS A MATTER OF INFORMATION ONLY AND CONFERS NO RIGHTS UPON THE CERTIFICATE HOLDER. THIS CERTIFICATE DOES NOT AFFIRMATIVELY OR NEGATIVELY AMEND, EXTEND OR ALTER THE COVERAGE AFFORDED BY THE POLICIES BELOW. THIS CERTIFICATE OF INSURANCE DOES NOT CONSTITUTE A CONTRACT BETWEEN THE ISSUING INSURER(S), AUTHORIZED REPRESENTATIVE OR PRODUCER, AND THE CERTIFICATE HOLDER.

**IMPORTANT:** If the certificate holder is an ADDITIONAL INSURED, the policy(ies) must have ADDITIONAL INSURED provisions or be endorsed. If SUBROGATION IS WAIVED, subject to the terms and conditions of the policy, certain policies may require an endorsement. A statement on this certificate does not confer rights to the certificate holder in lieu of such endorsement(s).

<b>PRODUCER</b> <b>CCIG</b> 5660 Greenwood Plaza Blvd. Suite 500 Greenwood Village, CO 80111	<b>CONTACT NAME:</b> Analisa Murphy, CIC, ARM <b>PHONE (A/C, No, Ext):</b> (720) 330-7141 <b>FAX (A/C, No):</b> (303) 799-0156 <b>E-MAIL ADDRESS:</b> AnalisaM@thinkccig.com													
	<table border="1"> <tr> <th>INSURER(S) AFFORDING COVERAGE</th> <th>NAIC #</th> </tr> <tr> <td>INSURER A : BITCO General Insurance Corporation</td> <td>20095</td> </tr> <tr> <td>INSURER B : Pinnacol Assurance</td> <td>41190</td> </tr> <tr> <td>INSURER C :</td> <td></td> </tr> <tr> <td>INSURER D :</td> <td></td> </tr> <tr> <td>INSURER E :</td> <td></td> </tr> <tr> <td>INSURER F :</td> <td></td> </tr> </table>	INSURER(S) AFFORDING COVERAGE	NAIC #	INSURER A : BITCO General Insurance Corporation	20095	INSURER B : Pinnacol Assurance	41190	INSURER C :		INSURER D :		INSURER E :		INSURER F :
INSURER(S) AFFORDING COVERAGE	NAIC #													
INSURER A : BITCO General Insurance Corporation	20095													
INSURER B : Pinnacol Assurance	41190													
INSURER C :														
INSURER D :														
INSURER E :														
INSURER F :														
<b>INSURED</b>  Keene Concrete, Inc. 30263 Weld Co. Road 8 Keenesburg, CO 80643														

**COVERAGES**                      **CERTIFICATE NUMBER:**                      **REVISION NUMBER:**


THIS IS TO CERTIFY THAT THE POLICIES OF INSURANCE LISTED BELOW HAVE BEEN ISSUED TO THE INSURED NAMED ABOVE FOR THE POLICY PERIOD INDICATED. NOTWITHSTANDING ANY REQUIREMENT, TERM OR CONDITION OF ANY CONTRACT OR OTHER DOCUMENT WITH RESPECT TO WHICH THIS CERTIFICATE MAY BE ISSUED OR MAY PERTAIN, THE INSURANCE AFFORDED BY THE POLICIES DESCRIBED HEREIN IS SUBJECT TO ALL THE TERMS, EXCLUSIONS AND CONDITIONS OF SUCH POLICIES. LIMITS SHOWN MAY HAVE BEEN REDUCED BY PAID CLAIMS.

INSR LTR	TYPE OF INSURANCE	ADDL INSD	SUBR WVD	POLICY NUMBER	POLICY EFF (MM/DD/YYYY)	POLICY EXP (MM/DD/YYYY)	LIMITS
<b>A</b>	<input checked="" type="checkbox"/> <b>COMMERCIAL GENERAL LIABILITY</b> <input type="checkbox"/> CLAIMS-MADE <input checked="" type="checkbox"/> OCCUR  GEN'L AGGREGATE LIMIT APPLIES PER: <input type="checkbox"/> POLICY <input checked="" type="checkbox"/> PROJECT <input type="checkbox"/> LOC OTHER:	<input checked="" type="checkbox"/>		CLP3668596	6/1/2018	6/1/2019	EACH OCCURRENCE \$ 1,000,000 DAMAGE TO RENTED PREMISES (Ea occurrence) \$ 300,000 MED EXP (Any one person) \$ 10,000 PERSONAL & ADV INJURY \$ 1,000,000 GENERAL AGGREGATE \$ 2,000,000 PRODUCTS - COMP/OP AGG \$ 2,000,000 \$
<b>A</b>	<input checked="" type="checkbox"/> <b>AUTOMOBILE LIABILITY</b> <input type="checkbox"/> ANY AUTO OWNED AUTOS ONLY <input type="checkbox"/> HIRED AUTOS ONLY <input type="checkbox"/> SCHEDULED AUTOS <input type="checkbox"/> NON-OWNED AUTOS ONLY	<input checked="" type="checkbox"/>		CAP3668597	6/1/2018	6/1/2019	COMBINED SINGLE LIMIT (Ea accident) \$ 1,000,000 BODILY INJURY (Per person) \$ BODILY INJURY (Per accident) \$ PROPERTY DAMAGE (Per accident) \$ \$ \$
	<input type="checkbox"/> <b>UMBRELLA LIAB</b> <input type="checkbox"/> OCCUR <input type="checkbox"/> <b>EXCESS LIAB</b> <input type="checkbox"/> CLAIMS-MADE DED      RETENTION \$						EACH OCCURRENCE \$ AGGREGATE \$ \$
<b>B</b>	<b>WORKERS COMPENSATION AND EMPLOYERS' LIABILITY</b> ANY PROPRIETOR/PARTNER/EXECUTIVE OFFICER/MEMBER EXCLUDED? (Mandatory in NH) <input checked="" type="checkbox"/> Y <input type="checkbox"/> N If yes, describe under DESCRIPTION OF OPERATIONS below		N/A	4030100	6/1/2018	6/1/2019	<input checked="" type="checkbox"/> PER STATUTE <input type="checkbox"/> OTH-ER E.L. EACH ACCIDENT \$ 1,000,000 E.L. DISEASE - EA EMPLOYEE \$ 1,000,000 E.L. DISEASE - POLICY LIMIT \$ 1,000,000

DESCRIPTION OF OPERATIONS / LOCATIONS / VEHICLES (ACORD 101, Additional Remarks Schedule, may be attached if more space is required)

re: Contract #: 201845779  
Project Name: 2018 Citywide Bond Concrete Repair

As required by written contract or written agreement, the City and County of Denver, its Elected and Appointed Officials, Employees and Volunteers are included as Additional Insured for ongoing operations under General Liability and Auto Liability.

<b>CERTIFICATE HOLDER</b>  City and County of Denver 201 W. Colfax Ave. Dept. 614 Denver, CO 80202	<b>CANCELLATION</b>  SHOULD ANY OF THE ABOVE DESCRIBED POLICIES BE CANCELLED BEFORE THE EXPIRATION DATE THEREOF, NOTICE WILL BE DELIVERED IN ACCORDANCE WITH THE POLICY PROVISIONS.  AUTHORIZED REPRESENTATIVE 
--	--



**PERFORMANCE AND PAYMENT BOND  
SURETY AUTHORIZATION  
(SAMPLE)**

FAX NUMBER: 720-913-3183  
TELEPHONE NUMBER: 720-913-3267

Assistant City Attorney  
201 W. Colfax Ave. Dept 1207  
Denver, Colorado 80202

RE: (Company name)

Contract No: 201845779  
Project Name: 2018 Citywide Bond Concrete Repair  
Contract Amount:  
Performance and Payment Bond No.:

Dear Assistant City Attorney,

The Performance and Payment Bonds covering the above captioned project were executed by this agency, through \_\_\_\_\_ insurance company, on \_\_\_\_\_, 20\_\_.

We hereby authorize the City and County of Denver, Department of Public Works, to date all bonds and powers of attorney to coincide with the date of the contract.

If you should have any additional questions or concerns, please don't hesitate to give me a call at \_\_\_\_\_.

Thank you.

Sincerely,

Denver Public Works/Office of the Executive Director  
201 West Colfax Avenue, Dept 608 | Denver, CO 80202  
[www.denvergov.org/dpw](http://www.denvergov.org/dpw)  
p. 720.865.8630 | f. 720.865.8795

**311 | POCKETGOV.COM | DENVERGOV.ORG | DENVER 8 TV**





**NOTICE OF APPARENT LOW BIDDER**  
**(SAMPLE)**

Current Date

To:

Gentlemen:

The MANAGER OF PUBLIC WORKS has considered the Bids submitted on December 20, 2018 for work to be done and materials to be furnished in and for:

**CONTRACT No. 201845779 2018 CITYWIDE BOND CONCRETE REPAIR**

as set forth in detail in the Contract Documents for the City and County of Denver, Colorado. It appears that your Bid is fair, equitable, and to the best interest of the City and County; therefore, said Bid is hereby accepted at the bid price contained herein, subject to execution of the Contract Documents and your furnishing the items specified below, the total cost thereof (Contract Amount Written), (Contract Amount Numeric).

It will be necessary for you to appear forthwith at the office of the Department of Public Works, Finance and Administration, 201 W. Colfax Ave. Dept 614, Denver, Colorado 80202, to receive the said Contract Documents, execute the same and return them to the Department of Public Works, Finance and Administration, within the time limit set forth in the Bid Proposal.

In accordance with the requirements set forth in the Contract Documents, you are required to furnish the following documents:

- a. Insurance Certificates: General Liability and Automotive Liability, Workman's Compensation and Employer Liability; or any other coverage required by the contract; and
- b. One original plus four copies of the Power of Attorney relative to Performance and/or Payment Bond;

All construction Contracts made and entered into by the City and County of Denver are subject to Affirmative Action and Equal Opportunity Rules and Regulations, as adopted by the Manager of Public Works, and each contract requiring payment by the City of one-half million dollars (\$500,000.00) or more shall first be approved by the City Council acting by ordinance and in accordance with Section 3.2.6 of the Charter of the City and County of Denver.

Prior to issuance of Notice to Proceed, all Equal Opportunity requirements must be completed. Additional information may be obtained by contacting the Director of Contract Compliance at (720-913-1700).

**NOTICE OF APPARENT LOW BIDDER  
(SAMPLE)**

CONTRACT NO. 201845779

Page 2

The Bid Security submitted with your Bid, will be returned upon execution of the Contract and furnishing of the Performance Bond. In the event you should fail to execute the Contract and to furnish the performance Bond within the time limit specified, said Bid Security will be retained by the City and County of Denver as liquidated damages, and not as a penalty for the delay and extra work caused thereby.

Dated at Denver, Colorado this \_\_\_\_\_ day of \_\_\_\_\_ 20\_\_\_\_.

CITY AND COUNTY OF DENVER

By \_\_\_\_\_  
Manager of Public Works

Denver Public Works/Office of the Executive Director  
201 West Colfax Avenue, Dept 608 | Denver, CO 80202  
[www.denvergov.org/dpw](http://www.denvergov.org/dpw)  
p. 720.865.8630 | f. 720.865.8795

**311 | POCKETGOV.COM | DENVERGOV.ORG | DENVER 8 TV**



Current Date

**NOTICE TO PROCEED  
(SAMPLE)**

Name  
Company  
Street  
City/State/Zip

**CONTRACT NO. 201845779, 2018 CITYWIDE BOND CONCRETE REPAIR**

In accordance with General Contract Condition 302 of the Standard Specifications for Construction, General Contract Conditions, 2011 Edition, you are hereby authorized and directed to proceed on \_\_\_\_\_ with the work of constructing contract number 201845779, as set forth in detail in the contract documents for the City and County of Denver.

With a contract time of \_\_\_\_\_ calendar days, the project must be complete on or before \_\_\_\_\_.

If you have not already done so, you must submit your construction schedule, in accordance with General Contract Condition 306.2.B, to the Project Manager within 10 days. Additionally, you must submit your tax exempt certificate, and copies of your subcontractors' certificates, in accordance with General Contract Condition 323.5, to the Project Manager as soon as possible. Failure to submit these certificates will delay processing of payment applications.

Sincerely,

Lesley B. Thomas  
City Engineer

cc:

Denver Public Works/Office of the Executive Director  
201 West Colfax Avenue, Dept 608 | Denver, CO 80202  
[www.denvergov.org/dpw](http://www.denvergov.org/dpw)  
p. 720.865.8630 | f. 720.865.8795

**311 | POCKETGOV.COM | DENVERGOV.ORG | DENVER 8 TV**



Certificate of Contract Release  
(SAMPLE)

Date

Name  
Company  
Street  
City/State/Zip

RE: Certificate of Contract Release for  
**201845779, 2018 CITYWIDE BOND CONCRETE REPAIR**

Received this date of the City and County of Denver, as full and final payment of the cost of the improvements provided for in the foregoing contract, \_\_\_\_\_ dollars and \_\_\_\_\_ cents (\$\_\_\_\_\_), in cash, being the remainder of the full amount accruing to the undersigned by virtue of said contract; said cash also covering and including full payment for the cost of all extra work and material furnished by the undersigned in the construction of said improvements, and all incidentals thereto, and the undersigned hereby releases said City and County of Denver from any and all claims or demands whatsoever, regardless of how denominated, growing out of said contract.

And these presents are to certify that all persons performing work upon or furnishing materials for said improvements under the foregoing contract have been paid in full and this payment to be made is the last or final payment.

\_\_\_\_\_  
Contractor's Signature

\_\_\_\_\_  
Date Signed

If there are any questions, please contact me by telephone at (720) 913-XXXX. Please return this document via facsimile at (720) 913-1805 and mail to original to the above address.

Denver Public Works/Office of the Executive Director  
201 West Colfax Avenue, Dept 608 | Denver, CO 80202  
[www.denvergov.org/dpw](http://www.denvergov.org/dpw)  
p. 720.865.8630 | f. 720.865.8795

**311 | POCKETGOV.COM | DENVERGOV.ORG | DENVER 8 TV**

# **CITY AND COUNTY OF DENVER**

**STATE OF COLORADO**



**DENVER**  
THE MILE HIGH CITY

## **DEPARTMENT OF PUBLIC WORKS**

### **Addendum**

**Contract Number: 201845779**



**2018 Citywide Bond Concrete Repair**

**November 16, 2018**

CITY AND COUNTY OF DENVER  
DEPARTMENT OF PUBLIC WORKS  
Engineering Division

CONTRACT NO. 201845779  
PROJECT NAME: 2018 Citywide Bond Concrete Repair

ADDENDUM NO. 1 TO CONTRACT DOCUMENTS

Bidders are hereby instructed that the drawings, specifications, and other contract documents are modified, corrected, supplemented and/or superseded for the above mentioned project as hereinafter described in the following attachments:

Question and Answers


1. *The HBP Patch/Overlay and we looked through the bid docs and did not find a mix design. Do you have one other than "City and County of Denver approved mix".*

No specific mix design is specified. CDOT approved mix designs for patching will be accepted.

2. *In the pre-bid it says the City will do the concrete testing but there is a line item on the bid schedule for material testing. Please confirm who is to pay for testing.*

The line item for testing will be used to pay for the concrete testing required of the Contractor (air, slump, strength), typically once a week unless concrete does not meet specifications or High Early Concrete is used and further testing is required. The City also has a third party tester on call to verify results. This is paid by the City with a separate contract, not the testing line item.

This ADDENDUM shall be attached to, become a part of, and be returned with the Bid Proposal.

  
\_\_\_\_\_  
Lesley B. Thomas  
City Engineer  
12.13.18  
\_\_\_\_\_  
Date

The undersigned bidder acknowledges receipt of this Addendum. The Proposal submitted herewith is in accordance with the stipulations set forth herein.

\_\_\_\_\_  
Contractor

ADDENDUM NO. 1

DATE: \_\_\_\_\_

CITY AND COUNTY OF DENVER

STATE OF COLORADO



**DENVER**  
THE MILE HIGH CITY

DEPARTMENT OF PUBLIC WORKS

Prevailing Wage

Contract Number: 201845779



2018 Citywide Bond Concrete Repair

November 16, 2018



**DENVER**  
THE MILE HIGH CITY

**Office of Human Resources**

201 W. Colfax, Department 412

Denver, CO 80202

p: 720.913.5751

f: 720.913.5720

[www.denvergov.org/csa](http://www.denvergov.org/csa)

TO: All Users of the City of Denver Prevailing Wage Schedules

FROM: Susan Keller, Human Resources Technician, Classification & Compensation

DATE: Monday, July 16, 2018

SUBJECT: Latest Change to Prevailing Wage Schedules

Please be advised, prevailing wage rates for some building, heavy, highway, and residential construction trades have not been updated by the United States Department of Labor (DOL) since March 1, 2002. The Career Service Board, in their meeting held on April 21, 2011, approved the use of the attached supplemental wage rates until prevailing wage rates for these classifications of work are again published by the United States Department of Labor in accordance with the Davis-Bacon Act.

The effective date for this publication is **Friday, July 13, 2018** and applies to the City and County of Denver for **HIGHWAY CONSTRUCTION PROJECTS** in accordance with the Denver Revised Municipal Code, Section 20-76(c).

General Wage Decision No. CO180019  
Superseded General Decision No. CO20170019  
Modification No. 1  
Publication Date: 07/13/2018  
(5 pages)

Unless otherwise specified in this document, apprentices shall be permitted only if they are employed pursuant to, and individually registered in, a bona fide apprenticeship program registered with the U.S. Department of Labor (DOL). The employer and the individual apprentice must be registered in a program, which has received prior approval, by the DOL. Any employer, who employs an apprentice and is found to be in violation of this provision, shall be required to pay said apprentice the full journeyman scale.

Attachments as listed above.



General Decision Number: CO180019 07/13/2018 CO19

Superseded General Decision Number: CO20170019

State: Colorado

Construction Type: Highway

Counties: Denver and Douglas Counties in Colorado.

HIGHWAY CONSTRUCTION PROJECTS

Note: Under Executive Order (EO) 13658, an hourly minimum wage of \$10.35 for calendar year 2018 applies to all contracts subject to the Davis-Bacon Act for which the contract is awarded (and any solicitation was issued) on or after January 1, 2015. If this contract is covered by the EO, the contractor must pay all workers in any classification listed on this wage determination at least \$10.35 per hour (or the applicable wage rate listed on this wage determination, if it is higher) for all hours spent performing on the contract in calendar year 2018. The EO minimum wage rate will be adjusted annually. Please note that this EO applies to the above-mentioned types of contracts entered into by the federal government that are subject to the Davis-Bacon Act itself, but it does not apply to contracts subject only to the Davis-Bacon Related Acts, including those set forth at 29 CFR 5.1(a)(2)-(60). Additional information on contractor requirements and worker protections under the EO is available at www.dol.gov/whd/govcontracts.

Modification Number	Publication Date
0	01/05/2018
1	07/13/2018

\* CARP9901-008 05/01/2018

	Rates	Fringes
CARPENTER (Form Work Only).....	\$ 25.50	9.47
-----		
ELEC0068-016 03/01/2011		

	Rates	Fringes
TRAFFIC SIGNALIZATION:		
Traffic Signal Installation		
Zone 1.....	\$ 26.42	4.75%+8.68
Zone 2.....	\$ 29.42	4.75%+8.68

TRAFFIC SIGNAL INSTALLER ZONE DEFINITIONS

Zone 1 shall be a 35 mile radius, measured from the following addresses in each of the following cities:  
Colorado Springs - Nevada & Bijou  
Denver - Ellsworth Avenue & Broadway  
Ft. Collins - Prospect & College  
Grand Junction - 12th & North Avenue  
Pueblo - I-25 & Highway 50  
All work outside of these areas shall be paid Zone 2 rates.

-----  
ENGI0009-008 05/01/2017

	Rates	Fringes
POWER EQUIPMENT OPERATOR:		
(3)-Hydraulic Backhoe (Wheel Mounted, under 3/4 yds), Hydraulic Backhoe (Backhoe/Loader combination), Drill Rig Caisson (smaller than Watson 2500 and similar), Loader (up to and including 6 cu. yd.).....	\$ 27.60	10.10
(3)-Loader (under 6 cu. yd.) Denver County.....	\$ 27.60	10.10
(3)-Motor Grader (blade- rough) Douglas County.....	\$ 27.60	10.10
(4)-Crane (50 tons and under), Scraper (single bowl, under 40 cu. yd).....	\$ 27.75	10.10
(4)-Loader (over 6 cu. yd) Denver County.....	\$ 27.75	10.10
(5)-Drill Rig Caisson (Watson 2500 similar or larger), Crane (51-90 tons), Scraper (40 cu.yd and over),.....	\$ 27.92	10.10
(5)-Motor Grader (blade- finish) Douglas County.....	\$ 27.92	10.10
(6)-Crane (91-140 tons).....	\$ 28.55	10.10

-----  
SUCO2011-004 09/15/2011

	Rates	Fringes
CARPENTER (Excludes Form Work)...	\$ 19.27	5.08
CEMENT MASON/CONCRETE FINISHER		
Denver.....	\$ 20.18	5.75
Douglas.....	\$ 18.75	3.00
ELECTRICIAN (Excludes Traffic Signal Installation).....	\$ 35.13	6.83
FENCE ERECTOR (Excludes Link/Cyclone Fence Erection).....	\$ 13.02	3.20
GUARDRAIL INSTALLER.....	\$ 12.89	3.20
HIGHWAY/PARKING LOT STRIPING:Painter		
Denver.....	\$ 12.62	3.21
Douglas.....	\$ 13.89	3.21
IRONWORKER, REINFORCING (Excludes Guardrail		

Installation).....\$	16.69	5.45
IRONWORKER, STRUCTURAL		
(Includes Link/Cyclone Fence		
Erection, Excludes Guardrail		
Installation).....\$	18.22	6.01
LABORER		
Asphalt Raker.....\$	16.29	4.25
Asphalt Shoveler.....\$	21.21	4.25
Asphalt Spreader.....\$	18.58	4.65
Common or General		
Denver.....\$	16.76	6.77
Douglas.....\$	16.29	4.25
Concrete Saw (Hand Held)....\$	16.29	6.14
Landscape and Irrigation....\$	12.26	3.16
Mason Tender-		
Cement/Concrete		
Denver.....\$	16.96	4.04
Douglas.....\$	16.29	4.25
Pipelayer		
Denver.....\$	13.55	2.41
Douglas.....\$	16.30	2.18
Traffic Control (Flagger)....\$	9.55	3.05
Traffic Control (Sets		
Up/Moves Barrels, Cones,		
Install Signs, Arrow		
Boards and Place		
Stationary Flags)(Excludes		
Flaggers).....\$	12.43	3.22
PAINTER (Spray Only).....\$	16.99	2.87
POWER EQUIPMENT OPERATOR:		
Asphalt Laydown		
Denver.....\$	22.67	8.72
Douglas.....\$	23.67	8.47
Asphalt Paver		
Denver.....\$	24.97	6.13
Douglas.....\$	25.44	3.50
Asphalt Roller		
Denver.....\$	23.13	7.55
Douglas.....\$	23.63	6.43
Asphalt Spreader.....\$	22.67	8.72
Backhoe/Trackhoe		
Douglas.....\$	23.82	6.00
Bobcat/Skid Loader.....\$	15.37	4.28
Boom.....\$	22.67	8.72
Broom/Sweeper		
Denver.....\$	22.47	8.72
Douglas.....\$	22.96	8.22
Bulldozer.....\$	26.90	5.59
Concrete Pump.....\$	21.60	5.21
Drill		
Denver.....\$	20.48	4.71
Douglas.....\$	20.71	2.66
Forklift.....\$	15.91	4.68
Grader/Blade		
Denver.....\$	22.67	8.72
Guardrail/Post Driver.....\$	16.07	4.41
Loader (Front End)		

Douglas.....	\$ 21.67	8.22
Mechanic		
Denver.....	\$ 22.89	8.72
Douglas.....	\$ 23.88	8.22
Oiler		
Denver.....	\$ 23.73	8.41
Douglas.....	\$ 24.90	7.67
Roller/Compactor (Dirt and Grade Compaction)		
Denver.....	\$ 20.30	5.51
Douglas.....	\$ 22.78	4.86
Rotomill.....	\$ 16.22	4.41
Screed		
Denver.....	\$ 22.67	8.38
Douglas.....	\$ 29.99	1.40
Tractor.....	\$ 13.13	2.95

TRAFFIC SIGNALIZATION:

Groundsman		
Denver.....	\$ 17.90	3.41
Douglas.....	\$ 18.67	7.17

TRUCK DRIVER

Distributor		
Denver.....	\$ 17.81	5.82
Douglas.....	\$ 16.98	5.27
Dump Truck		
Denver.....	\$ 15.27	5.27
Douglas.....	\$ 16.39	5.27
Lowboy Truck.....	\$ 17.25	5.27
Mechanic.....	\$ 26.48	3.50
Multi-Purpose Specialty & Hoisting Truck		
Denver.....	\$ 17.49	3.17
Douglas.....	\$ 20.05	2.88
Pickup and Pilot Car		
Denver.....	\$ 14.24	3.77
Douglas.....	\$ 16.43	3.68
Semi/Trailer Truck.....	\$ 18.39	4.13
Truck Mounted Attenuator....	\$ 12.43	3.22
Water Truck		
Denver.....	\$ 26.27	5.27
Douglas.....	\$ 19.46	2.58

-----

WELDERS - Receive rate prescribed for craft performing operation to which welding is incidental.

**Office of Human Resources  
Supplemental rates  
(Specific to the Denver Projects)  
Revised 4/11/2017)**

<b>Classification</b>		<b>Base</b>	<b>Fringe</b>
Ironworker (Ornamental)		\$26.05	\$12.00
Laborer	Removal of Asbestos	\$21.03	\$8.55
Line Construction	Lineman, Gas Fitter/Welder	\$36.88	\$9.55
	Line Eq Operator/Line Truck Crew	\$25.74	\$8.09
Millwright		\$28.00	\$10.00
Pipefitter		\$30.45	\$12.85
Plumber		\$30.19	\$13.55
Power Equipment Operator (Tunnels Above and Below Ground, shafts and raises):	Group 1	\$25.12	\$10.81
	Group 2	\$25.47	\$10.85
	Group 3	\$25.57	\$10.86
	Group 4	\$25.82	\$10.88
	Group 5	\$25.97	\$10.90
	Group 6	\$26.12	\$10.91
	Group 7	\$26.37	\$10.94
Power Equipment Operator	Group 1	\$22.97	\$10.60
	Group 2	\$23.32	\$10.63
	Group 3	\$23.67	\$10.67
	Group 4	\$23.82	\$10.68
	Group 5	\$23.97	\$10.70
	Group 6	\$24.12	\$10.71
	Group 7	\$24.88	\$10.79
Truck Driver	Group 1	\$18.42	\$10.00
	Group 2	\$19.14	\$10.07
	Group 3	\$19.48	\$10.11
	Group 4	\$20.01	\$10.16
	Group 5	\$20.66	\$10.23
	Group 6	\$21.46	\$10.31

Go to <http://www.denvergov.org/Auditor> to view the Prevailing Wage Clarification Document for a list of complete classifications used.

# **CITY AND COUNTY OF DENVER**

**STATE OF COLORADO**



**DENVER**  
THE MILE HIGH CITY

## **DEPARTMENT OF PUBLIC WORKS**

**Technical Specifications**

**Contract Number: 201845779**



**2018 Citywide Bond Concrete Repair**

**November 16, 2018**



**STREET MAINTENANCE DIVISION**

**SPECIAL PROVISIONS**

**STANDARD CONCRETE CONSTRUCTION DETAILS AND TECHNICAL SPECIFICATIONS**

It is the intent of the City to use the City of Denver Public Works “Transportation Standards and Details for the Engineering Division” 2017 edition, the Wastewater Management Division Standard Details and Drawings (when applicable) and the Contractor shall additionally abide by all rules and guidelines as required by:

City and County of Denver Right of Way Street Occupancy Permit.

It is further the intent of the City to use applicable specifications from the Colorado Department of Transportation “Standard Specifications for Road and Bridge” 2017 edition with revisions listed in the “Index of Revisions to the 2017 Colorado Department of Transportation Standard Specifications for Road and Bridge Construction.”

**INDEX OF REVISIONS TO THE**

**2017 CDOT Standard Specifications for Road and Bridge Construction**

<u>Item</u>	<u>Description</u>	<u>Page</u>
201	CLEARING AND GRUBBING	TS-2
202	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	TS-3
203	EXCAVATION AND EMBANKMENT	TS-9
206	EXCAVATION AND BACKFILL FOR STRUCTURES	TS-11
208	EROSION CONTROL	TS-12
209	WATERING AND DUST PALLIATIVES	TS-26
210	RESET STRUCTURES	TS-27
212	SEEDING, FERTILIZER AND SODDING	TS-29
304	AGGREGATE BASE COURSE	TS-31
306	RECONDITIONING	TS-33
401 & 403	PLANT MIX PAVEMENTS	TS-34
412	PORTLAND CEMENT CONCRETE PAVEMENT	TS-36
413	CONCRETE PATCHING AND CURB HEAD REPLACEMENT	TS-43
601	STRUCTURAL CONCRETE	TS-46
603	CULVERTS AND SEWERS	TS-48
604	MANHOLES, INLETS AND METER VAULTS	TS-51
608	SIDEWALKS AND BIKEWAYS	TS-53
609	CURB AND GUTTER	TS-57
613	LIGHTING	TS-60
614	TRAFFIC CONTROL DEVICES	TS-61
623	IRRIGATION SYSTEM	TS-62
625	CONSTRUCTION SURVEYING	TS-64
626	MOBILIZATION	TS-65
627	PAVEMENT MARKING	TS-66
630	CONSTRUCTION ZONE TRAFFIC CONTROL	TS-67
631	PUBLIC INFORMATION SERVICES	TS-70
705	JOINT, WATERPROOFING AND BEARING MATERIALS	TS-71
711	CONCRETE CURING MATERIALS AND ADMIXTURES	TS-72

**APPENDICES**

- A. Potential Work Locations Map
- B. Potential Spot Repairs
- C. Annotated Revisions

**REVISION OF SECTION 201  
CLEARING AND GRUBBING**

Section 201.01 of the Standard Specifications is hereby revised as follows:

The Contractor shall only perform work consisting of clearing, grubbing, removing, and disposing of vegetation and debris within 12” of the proposed concrete repair and only as needed to set forms and complete the required concrete construction or repairs unless otherwise directed by the Project Inspector/Manager.

Section 201.03 of the Standard Specifications shall be deleted and replaced with:

Clearing and Grubbing shall not be measured separately and all costs associated with Clearing and Grubbing shall be included in the related concrete construction or repair work.

Section 201.04 of the Standard Specifications shall be deleted and replaced with:

Clearing and Grubbing shall not be paid separately and all costs associated with Clearing and Grubbing shall be included in the related concrete construction or repair work.

When the Contract does not include pay items in Section 201, “Clearing and Grubbing”, the removal will not be paid for separately but shall be included in the work.

**END OF REVISION OF SECTION 201**



**REVISION OF SECTION 202  
REMOVAL OF STRUCTURES AND OBSTRUCTIONS**

Section 202 of the Standard Specifications is hereby revised as follows:

All equipment, labor, hauling, sorting, removal, delivery and documentation of recyclable materials as per SC-20 "Greenprint Denver Requirements" will not be paid separately; all costs incurred by the Contractor to meet the requirements of SC-20 shall be included in the removal of the related appurtenance. All non-hazardous waste is to be hauled to Denver Arapahoe Disposal Site (DADS) as per "SC-12 DISPOSAL OF NON-HAZARDOUS WASTE AT DADS" of the Contract. All costs of removal, loading, hauling and disposal of all excavations, unsuitable and excess materials and removal items are included in the related Removal Pay Item and will not be paid separately.

Subsection 202.02 shall be revised to include the following:

The Project Inspector will mark the limits of removals in the field. Removals in the vicinity of trees to remain shall conform to applicable provisions of the Tree Retention and Protection specification, as prepared by Denver Forestry. It shall be the responsibility of the Contractor to notify the City of Denver Forestry and coordinate with the Construction Project Manager and the adjacent property owner for any damages to the tree, its roots and/or the need to coordinate with City of Denver Forestry to remove the tree.

Subsection 202.03 is hereby replaced as follows:

All salvageable material shown on the plans shall be removed, without unnecessary damage, in sections or pieces that may be readily transported, and delivered by the Contractor to the location noted on the plans, or as directed by the Project Manager. The Contractor shall be held responsible for the safekeeping of all salvageable materials during the period of the Contract until they are delivered to the City. The Contractor shall make good or replace at the contractor's own expense any such materials damaged, stolen or otherwise lost prior to receipt by the City. All salvageable materials, as designated on the plans, shall remain the property of the City. The bid item "Removal and Reset Flagstone (Includes Salvage and Storage) shall include all costs associated with the means and method required to carefully remove, handle, palletize, and salvage existing flagstone, store the flagstone material, transport as needed, prep subgrade as needed and reset flagstone at locations designated by the Project Inspector/Manager.

Subsection 202.07 is hereby replaced as follows:

All concrete pavement, sidewalks, structures, curbs, gutters, asphalt pavement, etc., designated for removal, shall be broken into pieces and disposed of outside the limits of the project at a concrete recycling site if possible, unless otherwise designated on the plans, or as directed by the Project Manager.

Old concrete construction which abuts new construction, edges of pavement, sidewalks, curbs, etc., to be left in place shall be saw-cut at the nearest joint to true line with a vertical face.

Where old asphalt construction abuts new construction, edges of asphalt pavement, patching, etc., asphalt to be left in place shall be saw-cut to a neat vertical face with minimal jagged edges to the satisfaction of the Project Manager.

Removal of stone curb shall include the complete removal of the curb head and concrete foundation. No payment will be made for sprinkler relocation, utility relocation, etc., beyond the limits of construction as shown on the plans. Stone curb designated for salvage shall be carefully removed to prevent damage and delivered to the location indicated in the plans or specifications, or as directed by the Project Manager.

Subsection 202.08 shall be revised to include the following:

All trip hazards will be saw cut to fulfill the requirements of the Americans with Disabilities Act. Each offset will be tapered at a minimum 1:12 slope and shall have a smooth uniform appearance and texture. Method of trip hazard removal shall entail precise saw cutting of the concrete only. Grinding and/or pulverization of the concrete are not acceptable or allowed. Saw work shall be done with hand-held electrical powered equipment, capable of cutting at any angle and able to remove the concrete completely from all edges of the trip hazard and around obstacles that may be encountered. Saw cutting shall be taken to an absolute zero point of differential to the adjacent opposing side, and to both edges of the sidewalk to eliminate the trip hazard in its entirety over the full width of the sidewalk. The adjacent stone, along with any wall and/or obstacles abutting up to the sidewalk, shall not be cut into or marked in any way when saw cutting the trip hazard. Cutting into any landscaping, grass, rocks, walls, etc.; will not be permitted. Should damage occur to adjacent structures/landscaping the contractor shall repair the structure/landscaping at no cost to the project. Fugitive dust shall be collected using a high-powered dust control system that will prevent fugitive dust from going into the air. The suction device shall be attached to hand-held electrical powered cutting equipment to assure the maximum amount of fugitive dust will be collected before it has a chance to be released into the atmosphere. All debris and concrete dust that remains on the sidewalk shall be completely cleaned from the surface as well as the surrounding area, i.e. landscaping, walls, etc. and be hauled off and disposed of at an approved site. All costs incurred for disposal of waste material shall be included in unit cost and will not be paid for separately. Temporary asphalt ramps at trip hazards shall be removed at the time of cutting. No additional payment shall be made for removal of asphalt ramps. The maximum average vertical cut allowed for repair is 1 ½ inches. It is the Contractor's responsibility to adhere to the grades required (minimum of 1:12 slopes). Inspection and approval of work shall not relieve the Contractor from achieving all requirements set forth in these specifications. The Contractor shall be responsible to repair any work improperly performed. There will be no additional payment for these repairs, if required.

Subsection 202.09 shall be revised to include the following:

Removal of asphalt mat from gutters shall be accomplished by planing, and/or scraping. If the existing gutter is to remain, the gutter shall be cleaned by sandblasting until the pan is completely clean of residue. Fugitive dust shall be collected using a high-powered dust

control system that will prevent fugitive dust from going into the air. Gutters which are excessively (greater than one-quarter inch in depth) planed or damaged shall be removed and replaced by the Contractor at the Contractor's expense. If gutter is designated for removal, no separate payment shall be made for asphalt removal.

Subsection 202.11 shall be revised to include the following:

All quantities to be submitted for payment must be measured in person by the Contractor with the Project Inspector and recorded by location in tabular form and summarized utilizing the Field Measurement Report (FMR), see FMR sample in APPENDICES at the end of the Technical Specifications, in manner acceptable to the Project Manager and be submitted for review and acceptance in advance of each pay application.

Removal of concrete paving, crosspans, curb ramps, driveways will be measured by area in square yards, regardless of thickness and includes re-grading.

Removal of asphalt mat will be measured by square yard. If the existing asphalt mat is over 9" asphalt mat will be paid at twice the unit price. If the asphalt mat is more than 5" and is over concrete pavement, both asphalt removal and concrete pavement removal will be paid. If the asphalt mat is less than 5" and is over concrete pavement, only concrete pavement removal will be paid.

Removal of asphalt mat (planning or milling) will be measured by the square yard, regardless of thickness.

Removal of trolley tracks will be measured by centerline lineal track foot, and shall include the removal of rails, ties, connections, cobblestones and concrete runners.

Removal of asphalt mat from concrete gutter and other concrete designated to remain shall be measured by the square yard. Removal of asphalt mat from gutter shall include sandblasting and compressed air cleaning as part of that pay item. Fugitive dust shall be collected using a high-powered dust control system that will prevent fugitive dust from going into the air.

Remove Siphon will be measured as a lump sum for each siphon and shall include: removing the connector pipe, two (2) inlets, grates and frames, any related materials, concrete, metal, sealant, debris, excavation and suitable backfill placed and compacted, all materials, labor equipment, hauling and disposal needed to complete this item.

Subsection 202.12 is hereby deleted and replaced as follows:

The accepted quantities will be paid for at the contract unit price for each of the pay items listed below that appear in the Contract bid schedule. Payment shall be full compensation for all labor, equipment, time and materials for each unit bid item complete in place including saw cutting, scraping, sandblasting, removal, hauling and disposal of such items, excavation of subgrade material reconditioning or installation of aggregate base course and subsequent backfill, grading and compaction (with moisture/density control per the Revision of Subsection 203.07) to proposed subgrade elevation. The price shall also include salvageable materials removed, their custody, preservation, storage, hauling and disposal as provided herein.


Clearing and grubbing includes any and all excavation, removal and hauling to DADS of all

PWSTM Standard Concrete Construction Details & Technical Specifications


existing landscape materials including soil, sodding, plants, shrubs, landscape rock of any size or gradation, brick, stone pavers, stacked block wall, edging material, landscape fabric and fencing is included in the cost of the related work and is included in the cost of the related work and will not be paid separately unless otherwise noted under "PAY ITEMS".

Trip Hazard Sawing repairs performed shall be measured by INCH-FEET of repair made. This will be calculated by measuring the width of the sidewalk to the nearest 0.5 feet in width and multiplying by the average height in inches of the cut to be performed. The vertical cut to be made will be measured by averaging the height of the offset at the two corners of the sidewalk (or other concrete flatwork) to be cut to the nearest 0.25 inches in height as compared to the finished surface. The vertical cut (in inches) shall be multiplied by the concrete width in feet and the resulting product is INCH-FEET. Field measurements will be submitted in neat tabular form by physical address or intersection of completed work items shall be done jointly by the City Inspector and the Contractor. All invoices shall list work by each specific physical street address.

**See Trip Hazard Sawing measurement example next page:**



**Typical Plan View**  
Not to Scale



**Cross Section A - A**  
Not to Scale

**Pay Quantity Calculation Example:**

$$\text{End Area} = \frac{1'' + 0''}{2} \times 4' = 2 \text{ Inch Feet}$$

Pay quantity is based on "End Area", in units of inch feet, for trip hazard cut.

Payment will be made under:

**PAY ITEMS**

- Remove Inlet
- Remove Siphon
- Removal of Sidewalk
- Removal of Curbhead
- Removal of Curb and Gutter
- Removal of Combination Curb, Gutter and Sidewalk
- Removal and Reset Flagstone (Includes Salvage and Storage)

**PAY UNIT**

- EA
- EA
- LF
- LF
- LF
- LF
- SY

Removal of Concrete Pavement	SY
Removal of Asphalt Mat	SY
Removal of Fence	LF
Trip Hazard Sawing (>5 locations) (1 Week Completion)	IN-FT
Trip Hazard Sawing (<=5 locations) (1 Month Completion)	IN-FT

When the Contract does not include pay items in Section 202, "Removal of Structures and Obstructions", the removal will not be paid for separately but shall be included in the work.

**END OF REVISION OF SECTION 202**

**REVISION OF SECTION 203  
EXCAVATION AND EMBANKMENT**

Section 203 of the Standard Specifications is hereby revised as follows:

Subsection 203.04 shall include the following:

The Contractor shall protect and promptly dewater and recondition all excavations from water regardless of source.

Subsection 203.05 (c), first paragraph, shall include the following:

Approved backfill material shall be Aggregate Base Course (Class 6) or other material approved by the Project Manager.

Subsection 203.07 shall include the following:

Unless otherwise indicated on the plans, the density requirements for embankment material shall be: clay soils – 95% of the maximum density determined in accordance with AASHTO T-99; granular soils – 90% of the maximum density determined in accordance with AASHTO T-180. Proof rolling of the subgrade shall be required. Proof rolling shall be done after specified compaction has been obtained. Proof rolling shall be conducted with a double tandem ten-wheel end-dump truck, loaded to a minimum gross weight of 45,000 pounds, or other equipment as approved by the Project Manager. Areas found to be weak and those areas which failed shall be ripped, scarified, dried or wetted as necessary and re-compacted to the requirements for density and moisture at the Contractor's expense.

Where unsuitable material is encountered below proposed subgrade, the Project Manager may require the Contractor to remove the unsuitable materials and backfill to the finished grade with Class 6 aggregate base course, or other approved material. The Project Manager may designate as unsuitable those soils that are detrimental to the finished roadway. All unsuitable material shall be disposed of as directed. Excavation including unsuitable material, hauling and disposal of unsuitable material and concrete or any debris related to infrastructure removal (except asbestos or radioactive material), installation of aggregate base course, grading and compaction of suitable material or aggregate base course to proposed subgrade elevation will not be paid for separately but shall be included in the work associated with Section 202, Removal of Structures and Obstructions.

Subsection 203.11 is hereby deleted and replaced as follows:

Muck Excavation, Barrow, Embankment Material, Stripping, Blading and Dozing will not be paid separately but shall be included in the cost of the related work.

Proof rolling, blading, wetting, drying, dozing and sub-grade reconditioning, will not be measured and paid for separately, but shall be included in the cost of the work.

Haul and disposal will not be measured and paid for separately but shall be included in the cost of the work.

Unclassified Excavation will only be measured for payment at work locations where new ADA ramps are constructed replacing sidewalk or existing landscaped areas and new crossspan installations. The measurement for Unclassified Excavation shall be equal to the newly constructed ADA Ramp/crossspan area in square yards multiplied by the depth of soil removed and converted to cubic yards for example; Take the area of the ADA ramp/crossspan measured in

square yards then multiply by 1/3 for a quantity that is one foot of depth per square yard and convert that volume to cubic yards of Unclassified Excavation.

3-Man Labor Crew will be measured as the actual number of hours worked and shall include with each application for payment the name, date and hours worked agreed to daily as directed by the City's Construction Project Manager.

Payment will be made under:

<b><u>PAY ITEMS</u></b>	<b><u>PAY UNIT</u></b>
Unclassified Excavation	CY
3-Man Labor Crew	HR

When the contract does not include pay items for Unclassified Excavation and Embankment Material, these items will not be paid for separately but shall be included in the work.

**END OF REVISION OF SECTION 203**



**REVISION OF SECTION 206  
EXCAVATION AND BACKFILL FOR STRUCTURES**

Section 206 of the Standard Specifications is hereby revised as follows:

Subsection 206.02 shall include the following:

For areas between the flowline and property lines the Contractor shall only use Structural Backfill Class 1, crushed concrete materials are not allowed between the flowline and property lines. Only Structural Backfill Class 1 or existing native sub-grade material will be allowed for fill or fine grading between the flowline and property line.

Flow fill may only be used between the flowlines in the street and only if approved by the Project Manager.

Subsection 206.03 is hereby deleted and replaced as follows:

The Contractor is required to provide submittals for approval for both Structural Backfill Class 1 and Structural Backfill (Flow Fill).

No additional payment will be made for Structural Backfill Class 1 or reused excavated material and retempering and compacting of existing/native material used between the flowline and property line if needed for fill or fine grading. Concrete Roadbase will not be allowed between the flowline and property line.

Only Structural Backfill (Flow fill) will be considered for payment and shall be measured by cubic yards delivered. For acceptance and payment, the Contractor must provide copies of load tickets with a summary in tabular form to the Project Manager for review with each pay application for which payment for this item is requested.

Payment will be made under:

<u><b>PAY ITEM</b></u>	<u><b>PAY UNIT</b></u>
Structural Back Fill (Flow Fill)	CY

When the contract does not include pay items for Excavation and Backfill for Structures these items will not be paid for separately but shall be included in the work.

**END OF REVISION OF SECTION 206**

## REVISION OF SECTION 208 EROSION CONTROL

Section 208 of the Standard Construction Specifications is hereby removed in its entirety and replaced with the following:

### PART I: DEFINITIONS

Definitions used for this Section shall consist of those listed in Title 1 of the City and County of Denver "Standard Specifications for Construction, General Contract Conditions", 2011 edition.

Definitions used for this Section hereby incorporate those identified within the City and County of Denver Construction Activities Stormwater Manual (CASM).

Additional Definitions applicable to this Section are listed heretofore:

**Basis of Payment:** The terms under which "Work" is paid, as a designated "Pay Item" in accordance with the quantity measured and the "Pay Unit."

**Best Management Practices (BMPs):** Schedules of activities, prohibitions of practices, installation of devices, maintenance procedures, and other management practices deployed to stabilize the construction site to prevent or reduce the pollution of State Waters (see definition below). Stormwater BMPs can be classified as "structural" (i.e., devices installed or constructed on a site) or "non-structural" (procedures, such as modified landscaping practices).

**Colorado Department of Health and Environment (CDPHE):** State of Colorado, Water Quality Control Division responsible for issuance of State Construction Stormwater Permit.

**Construction Activities Stormwater Discharge Permit (CASDP):** Permit issued by the City for compliance with City & County of Denver Revised Municipal Code and Department of Public Works Rules & Regulations concerning the discharge of pollutants in storm generated runoff from construction sites to Municipal Separate Storm Sewer System (MS4, see definition below) or State Waters, via the Municipal Separate Storm Sewer System (MS4).

**Construction Activities Stormwater Manual (CASM):** City and County of Denver Construction Activities Stormwater Manual (CASM), 2010 edition.

**Colorado Department of Transportation (CDOT):** State agency that has published standards for Erosion Control with accompanying Erosion Control Supervisor certification courses.

**Erosion Control Supervisor (ECS):** The Erosion Control Supervisor is assigned by the Contractor to perform duties as described in this Section. The ECS shall be properly trained in BMPs per requirements of Part V below, and shall be under the direction of a Professional Engineer licensed in the State of Colorado when performing any modifications to the Project Stormwater Management Plan (SWMP), as

required by CDPHE.

**Final Stabilization:** Point of construction when all ground surface disturbing activities at the site have been completed and uniform vegetative cover has reached 70% of pre-disturbance vegetative cover (as judged by comparison to nearest fallow vegetation), or equivalent permanent features have been employed. At this point, all temporary BMPs can be removed, all construction and equipment maintenance wastes have been disposed of properly; and all elements of the Stormwater Management Plan have been completed.

**Major SWMP Modification:** Changes to the original SWMP that removes or adds additional area to the Project, or modifies the hydrology or drainage of the Project. A Major SWMP Modification requires the submission of revised Stormwater Management Plan (SWMP) elements to the Permit Authority for review and approval. Any adjustments to a SWMP must be performed either by or under the direction of a Professional Engineer licensed in the State of Colorado.

**Minor SWMP Modification:** Modification to the SWMP that does NOT increase the scope or change hydrology of the Project but: modifies/improves specific BMPs in use at site, indicates progression in phasing of the Project, or specifies relocation of previously approved BMPs within the Project. Any adjustments to a SWMP must be performed either by or under the direction of a Professional Engineer licensed in the State of Colorado.

**Municipal Separate Storm Sewer System (MS4):** A conveyance or system of conveyances (including roads with drainage systems, municipal streets, catch basins, curbs, gutters, ditches, man-made channels, or storm drains):

- a) owned or operated by a State, city, town, county, district, association, or other public body (created by or pursuant to State law) having jurisdiction over disposal of stormwater or other wastes, including special districts under State law such as a sewer district, flood control district or drainage district, or similar entity, or a designated and approved management agency under Section 208 of the Federal Clean Water Act that discharges to State Waters;
- b) designed or used for collecting or conveying stormwater;
- c) which is not a combined sewer; and
- d) which is not part of a Publicly Owned Treatment Works (POTW).

**Permit Authority:** The Department authorized by the City to review and process CASDP Applications for Capital and/ or governmental sponsored Projects. The responsible City department serving as the Permit Authority is the Engineering, Regulatory and Analytics Office. As a clarification, the Denver Department of Development Services is the single intake point for all permits

**Permit Enforcement Authority:** The Department authorized by the City to inspect and enforce CASDP Rules and Conditions for all construction Projects within the City's MS4 Boundary. The responsible City department serving as the Permit Enforcement Authority is the Wastewater Management Division of the Department of Public Works.

**State Construction Stormwater Permit:** Colorado Revised Statutes require that all construction sites/development Projects, which by definition, disturb one or more acres in area, shall be covered by a State issued general permit for construction activities. Information on the application requirements for the State permit can be obtained by phone at 303-692-3500; or by visiting their offices located at 4300 Cherry Creek Drive South, Denver, CO 80246 – 1530 or on the Web at: <https://www.colorado.gov/pacific/cdphe/news/water-quality-permits>

**State Waters:** Any and all surface waters which are contained in or flow in or through this State, not to include waters in sewage systems, waters in treatment works of disposal systems, waters in potable water distribution systems, and all water withdrawn for use until use and treatment have been completed.

Examples of State Waters include, but are not limited to, perennial streams, intermittent or ephemeral gulches and arroyos, ponds, lakes, reservoirs, irrigation canals or ditches, wetlands, stormwater conveyances (when they discharge to a surface water), and groundwater.

**Stormwater Management Plan (SWMP):** The Stormwater Management Plan contains the requirements necessary to accomplish all the following:

The SWMP establishes a minimum standard to construct, install, maintain, and remove required BMPs during the life of the Contract to prevent or minimize pollution of stormwater due to erosion, sediment transport, and construction related pollutant generated during all phases of the Project. A SWMP consists of the following elements:

- (i) CASDP Narrative Worksheet with Narrative Report. The Narrative Report and supporting documents should fully address the methods to be used to prevent sediment, debris, and other pollutants from entering the MS4 and/ or State Waters in and around the Project area. Proposed structural and non-structural BMPs should be described with sufficient implementation detail to ensure that the logical phases of the proposed construction Project meet the performance standards listed in the CASM.
- (ii) Proposed site drawings and Best Management Practice (BMP) installation details as they apply to the site conforming to the Urban Storm Drainage Criteria Manual, Vol. 3, "Best Management Practices", most current version as issued by the Urban Drainage and Flood Control District (UDFCD), or those established by the City's Department of Public Works. If erosion control drawings were included within the bid documents for the Project, they shall be used for bid purposes and initial planning/ deployment of BMPs on the Project. If provided drawings are signed/ sealed by a Professional Engineer, they have been pre-approved by the Permit Authority and may be used without revision for purposes of submitting for CASDP. If provided drawings do not have signature/ seal of Professional Engineer licensed by the State of Colorado, they will require revision by the Contractor with Professional Engineer signature/ seal prior to submission to the City and County of Denver for CASDP.
- (iii) Supporting documentation related to proposed BMPs that are not currently identified in PWSTM Standard Concrete Construction Details & Technical Specifications

UDFCD Vol. 3 or as otherwise published by the City.

Any preparation of or adjustments to a SWMP must be performed either by or under the supervision of a Professional Engineer licensed in the State of Colorado. SWMP elements submitted to the City shall also meet currently established criteria of the CDPHE as the SWMP must meet all local, State and Federal requirements.

**Substantial Completion of Erosion Control:** Point of construction when permanent BMPs have been installed, initial growth is in place, and the site is waiting for vegetative cover to reach 70% of pre-disturbance vegetative cover.

## **PART II: DESCRIPTION**

This Work shall consist of constructing, installing, maintaining, and removing when required, BMPs during the life of the Contract until Final Stabilization to prevent or minimize erosion, sedimentation, and pollution of any waters including storm, drainage-ways, MS4, State Waters, and/ or wetlands. Work under this Section includes the Contractor obtaining required Permits, utilizing SWMP elements provided in the Contract, and/ or SWMP elements specifically prepared by the Contractor as defined herein. The work shall also consist of providing on-going maintenance and monitoring of the SWMP as may be necessary due to the specific and/or dynamic needs of the Project as well as meet all requirements set forth within the CASM.

The Contractor shall coordinate the construction of temporary BMPs with the construction of permanent BMPs to assure economical, effective, and continuous erosion and sediment control and water pollution prevention throughout the construction period until Final Stabilization is achieved

When a provision of this Section or an order by the Permit Enforcement Authority requires that an action be immediate or taken immediately, it shall be understood that the Contractor shall at once begin effecting completion of the action and pursue it to completion in a manner acceptable to the Permit Enforcement Authority, and in accordance with applicable Permitting requirements.

## **PART III: MATERIALS**

The materials to be used for BMPs shall conform to each specific detail as set forth within the Project SWMP or as noted on the Contract Drawings.

## **PART IV: EROSION CONTROL PERMIT STATUS**

The current SWMP status for the Project is as follows:

A SWMP is currently not required for this project as the proposed disturbed area and/ or proximity to stream does not meet the minimum criteria for requiring a CASDP. However, the responsibilities for

minimizing sediment pollution from the Project have not been waived, and as such, the City hereby requires the Contractor to perform as specified in the following notes. Because a SWMP and CASDP are not necessary for the Project, all cost for performance of the following notes shall not be paid for separately, but shall be included in the work.

“A CASDP Permit will not be required for this project, however, the Contractor and/or their authorized agents shall ensure that all potential pollutants generated during demolition, excavation, trenching, boring, grading, or other construction Work associated with this permit, be prevented from discharge to stormwater conveyance systems in the vicinity of the Project.

The Contractor and/or their authorized agents shall remove all sediment, mud, construction debris, or other potential pollutants that may have been discharged to or, accumulate in the flow lines of storm drainage appurtenances and public rights of ways of the City and County of Denver as a result of construction activities associated with this Project. All removals shall be conducted in a timely manner.

The Contractor shall be held responsible for remediation of any adverse impacts to the MS4, State Waters, waterways, wetlands, and or other public or private properties, resulting from work done as part of this Project.

The Contractor and/or their authorized agents shall insure that all loads of cut and fill material imported to or exported from the Project shall be properly covered to prevent loss of the material during transport on public rights of way.” (Sec.49-552; Denver Revised Municipal Code)

Approved erosion and sediment control ‘Best Management Practices’ shall be maintained and kept in good repair for the duration of the Project. All necessary maintenance and repair shall be completed immediately upon discovery of any deficiency or defect.

The Contractor and/or their authorized agents shall implement the following Best Management Practices (BMPs) on site during construction. Best Management Practice (BMP) installation details and maintenance shall conform to the Urban Storm Drainage Criteria Manual, Vol. 3, "Best Management Practices", most current version as issued by the Urban Drainage and Flood Control District (UDFCD), or those established by the City’s Department of Public Works.

1. VEHICLE TRACKING CONTROL: This BMP is required at all access points to a construction site that are used by vehicular traffic or construction equipment.
2. INLET PROTECTION: This BMP is required on all existing or proposed storm sewer inlets in the vicinity of the construction site that may receive site runoff. The BMP must be appropriate to the type of storm inlet and appropriate for the ground surface at the inlet.
3. INTERIM SITE STABILIZATION: This BMP is required to provide a measure for preventing the discharge of sediment from construction sites where overlot grading or

PWSTM Standard Concrete Construction Details & Technical Specifications

other site disturbance has occurred. This BMP is particularly necessary on sites where construction activities/disturbance will be limited to small areas of the project site.

Acceptable BMPs include:

- a. Preserving existing vegetation
  - b. Seeding and planting
  - c. Mulching
  - d. Mulching and seeding
  - e. Temporary/Permanent re-vegetation operations
  - f. Chemical soil stabilizer application (requires Permit Enforcement Authority approval)
4. **WASTE MANAGEMENT/CONTAINMENT:** This BMP requires that all construction wastes, fuels, lubricants, chemical wastes, trash, sanitary wastes, contaminated soils or debris shall be contained on site, protected from contact with precipitation or surface runoff, periodically removed from the construction site, and properly disposed of.
  5. **SPILL PREVENTION /CONTAINMENT:** This BMP defines the measures proposed for preventing, controlling, or containing spills of fuel, lubricants, or other pollutants; and protecting potential pollutants from contact with precipitation or runoff.
  6. **CHUTE WASHOUT CONTAINMENT:** Water used in the cleaning of ready mixed concrete truck delivery chutes shall be discharged into a predefined, bermed containment area on the job site. The required containment area is to be bermed so that wash water is totally contained. Wash water discharged into the containment area shall be allowed to infiltrate or evaporate. Dried concrete waste shall be removed from the containment area and properly disposed of.  
The direct or indirect discharge of water containing waste concrete to the storm sewer system is prohibited (Sec.56-102a, c; Denver Revised Municipal Code).
  7. **STREET SWEEPING:** This BMP requires that paved surfaces which are adjacent to construction sites be swept in a timely manner when sediment and other materials are tracked or discharged on to them. Either sweeping by hand or use of street sweepers is acceptable. Street sweepers using water while sweeping is preferred in order to minimize dust. Flushing off paved surfaces with water is prohibited.
  8. **PERIMETER CONTROL:** This BMP requires that a construction site install a perimeter control measure along the edge of the construction site, to prevent, or filter the discharge of surface runoff from the construction site. The type of perimeter control used shall be determined based on site conditions and location. Maintenance and repair of the control measure shall occur as needed, in a timely manner.
  9. **STOCK PILES:** Soils that will be stockpiled for more than thirty (30) days shall be protected from wind and water erosion within fourteen (14) days of stockpile construction. Stabilization of stockpiles located within 100 feet of an MS4 or State Waters, or with slopes 3 to 1 or greater shall be completed within seven (7) days following stockpile construction. Stabilization and protection of the stockpile may be accomplished by any of the following: Mulching, Temporary/Permanent Revegetation Operations, Chemical Soil Stabilizer Application (requires Permit Enforcement Authority approval), or erosion control matting/Geotextiles. If stockpiles are located within 100 feet of top of bank of an MS4 or State Waters, a drainage-way or the site

PWSTM Standard Concrete Construction Details & Technical Specifications

perimeter, additional sediment controls shall be required.

10. SAW CUTTING OPERATIONS: The Contractor shall protect all storm sewer facilities adjacent to any location where pavement cutting operations involving wheel cutting, saw cutting, or abrasive water jet cutting are to occur. The Contractor shall remove and properly dispose of all waste products generated by said cutting operations on a daily basis or as needed throughout the work day. The discharge of any water contaminated by waste products from cutting operations to the storm sewer system is prohibited. (Sec.56-102a, c; Denver Revised Municipal Code).

## **PART V: CONSTRUCTION REQUIREMENTS**

### **A) SCHEDULES:**

At least 10 working days prior to the beginning of any construction work, the Contractor shall submit for approval a schedule for accomplishment of temporary and permanent BMPs shown in the SWMP. This schedule shall specifically indicate the sequence of clearing and grubbing, earthwork operations, and construction of temporary and permanent BMPs. The schedule shall include BMPs for all areas within the Project boundaries, including but not limited to, haul roads, borrow pits, and storage and other staging sites. Work shall not be started until the BMP schedule has been approved in writing by the Project Manager, and on-site pre-construction inspection is performed and approved by CCD's NPDES inspector. Once the work has started, and during the active construction period, the Contractor shall update the schedule for all BMPs on a regular basis, and as required to keep the SWMP in compliance.

**B) CONSTRUCTION IMPLEMENTATION:** The Contractor shall incorporate into the Project all BMPs that are appropriate for the current phase of work, as outlined in the accepted schedule.

**C) UNFORSEEN CONDITIONS:** The Contractor shall direct the ECS (under the supervision of a Professional Engineer licensed in the State of Colorado) to design and implement BMPs for correcting conditions unforeseen during design of the Project, or as possible for emergency situations, which arise during construction. The Project's SWMP, UDFCD Vol 3 standards and details, and CDOTs "Erosion Control and Storm-Water Quality Guide," and any approved modification to these documents as proposed by the Contractor, shall be used as reference documents for the purpose of designing appropriate BMPs. Measures and methods proposed by the Contractor to deal with unforeseen conditions shall be reviewed and approved in writing by the Permit Enforcement Authority and the Project Manager prior to implementation and construction.

In an emergency situation, the Contractor shall use best judgment for immediately responding to the emergency situation as it arises, and shall notify the Permit Enforcement Authority and ECS of the emergency situation and BMPs employed in response as soon as practical after installation.

### **D) PERMITS:**

The Contractor shall obtain all required permits for the Project including those required by federal, state, and local agencies. The Contractor shall obtain (or transfer from the City when specified) required erosion control and water quality permits and shall be responsible for compliance with all requirements under any such permits.



E) EROSION CONTROL SUPERVISOR:

Contractor shall assign to the Project an employee or subcontractor to serve as Erosion Control Supervisor (ECS). The ECS shall be a person other than the Contractor's superintendent, foreman, or equivalent supervisory position. The ECS shall be experienced in aspects of BMP construction and have satisfactorily completed a Colorado DOT or equivalent ECS training program authorized by the City. Proof that this requirement has been met shall be submitted to the Project Manager at least ten working days prior to the beginning of any soil disturbance work. A list of authorized ECS training programs is available from the City upon request. Additionally, per definition, the ECS shall be under the direction of a Professional Engineer licensed in the State of Colorado when performing any modifications to the Project Stormwater Management Plan (SWMP).

The ECS shall be responsible for oversight of the implementation, maintenance, and revision of the SWMP for the duration of the Project. CCD requires the ECS to fulfill responsibilities as outlined by CDPS such as having financial control and authority to implement BMPs. The ECS's responsibilities shall be as follows:

- 1) Ensure compliance with all water quality permits or certifications in effect during the construction work.
- 2) Supervise the installation, construction, and maintenance of all BMPs specified in the Contract and coordinate the construction of BMPs with all other construction operations.
- 3) Direct the implementation of suitable BMPs as necessary to correct unforeseen conditions or emergency situations. Direct the dismantling of those features when their purpose has been fulfilled due to completion of each Project phase unless the Permit Enforcement Authority agrees that the features be left in place.
- 4) Attend the preconstruction conference, erosion control preconstruction inspection, Project scheduling meetings, weekly construction/ field meetings, substantial completion and final stabilization inspections, and other meetings regarding construction that could impact water quality.
- 5) Evaluate all non-stormwater coming onto the site, such as springs, seeps, and landscape irrigation return flow. If such flow is identified, the ECS shall propose appropriate SWMP modifications to the Contractor to protect off-site water from becoming contaminated with sediment or other pollutants.
- 6) Coordinate with the Contractor to implement necessary actions to reduce anticipated or presently existing water quality or erosion problems resulting from construction activities.
- 7) Coordinate with the Contractor to ensure all labor, material, and equipment deployed to meet SWMP requirements is judged appropriately.
- 8) During construction, update and record the following items in the SWMP as changes occur:
  - (i) Construction boundaries (may require Major SWMP Modification)
  - (ii) Areas of disturbance (may require Major SWMP Modification)
  - (iii) Areas used for storage of construction materials, equipment, soils, or wastes.
  - (iv) Location of any dedicated asphalt or concrete batch plants.
  - (v) Location of construction offices and staging areas.
  - (vi) Location of work access routes during construction.

PWSTM Standard Concrete Construction Details & Technical Specifications

- (vii) Location of borrow and waste.
- (viii) Location of temporary and permanent stabilization

The ECS shall start a new site map before the current one becomes illegible. All site maps shall remain with the SWMP paperwork.

- 9) Amend the SWMP whenever there are: additions, deletions, or changes in locations of BMPs SWMP revisions shall be recorded immediately. Items shall be dated and signed at time of occurrence. Specifically, amendments shall include the following:
- (i) A change in design, construction, operation, or maintenance of the site which would require the implementation of new or revised BMPs; or
  - (ii) Changes when the SWMP proves to be ineffective in achieving the general objectives of controlling pollutants in stormwater discharges associated with construction activity.
  - (iii) Changes when temporary BMPs are no longer necessary from changes in Project phase and are removed. All inspection and maintenance activities or other repairs shall be documented.

All inspection and maintenance activities or other repairs shall be documented. The SWMP and documentation shall be kept on the Project site at all times.

- 10) Modify the site map with arrows to indicate direction of surface and storm water flowing across the Project site.
- 11) When adding, or revising BMPs in the SWMP, amend the narrative to explain what, when, where, why, and how the BMP is being used, and add a detail to the SWMP.
- 12) If using existing topography, vegetation, etc. as a BMP, label it as such in the SWMP site map; amend the Narrative to explain when, why, and how the BMP is being used in the SWMP.
- 13) Record on the SWMP, and implement the approved plan for concrete and asphalt saw cutting, grinding, and milling containment and removal.
- 14) Update the potential pollutants list in the SWMP throughout construction meeting CASDP requirements.
- 15) Spills, leaks, or overflows that result in the discharge of pollutants shall be documented on the inspection form. The ECS shall record the time and date, weather conditions, reasons for spill, and how it was remediated. The ECS shall immediately report to the Contractor and Project Manager the following instances of noncompliance:
- (i) Noncompliance which may endanger health or environment.
  - (ii) Spills or discharge of hazardous substance or oil which may cause pollution of the City MS4 or State Waters.
  - (iii) Discharge of stormwater which may cause an exceedance of a water quality standard.

- 16) Perform a thorough inspection of the stormwater management system at least every seven (7) days and within 24 hours after any precipitation or snowmelt event with the potential to cause surface erosion. If no land disturbing construction activities are present during a storm event, post-storm event inspections shall be conducted prior to commencing any new land disturbing construction activities, but no later than seventy-two (72) hours following the storm event. The inspection records shall be kept on-site in a written or previously approved format. Inspections shall be conducted during the progress of the work, during work suspensions, or until Final Stabilization of all disturbed areas is approved by Permit

PWSTM Standard Concrete Construction Details & Technical Specifications

Enforcement Authority and shall include the following services at a minimum:

- (i) The construction site perimeter, disturbed areas, and areas used for material storage that are exposed to precipitation shall be inspected for evidence of, or the potential for, pollutants entering the drainage system. BMPs identified in the SWMP shall be observed to ensure that they are operating correctly.
- (ii) The description of potential pollutant sources, and the BMPs identified in the SWMP, shall be revised and modified as appropriate based on the results of the inspection as soon as practicable after such inspection. Modification to the SWMP shall be implemented in a timely manner and in accordance with applicable Permit requirements.
- (iii) The operator shall keep a record of inspections. Uncontrolled releases of sediment or polluted storm water or measurable quantities of sediment found off the site shall be recorded with a brief explanation as to the measures taken to prevent future releases as well as any measures taken to clean up the sediment that has left the site. Inspection records shall be made available to the City upon request. Note: documentation of uncontrolled releases at site DOES NOT alleviate any State or Federal requirements for reporting of discharges or upset conditions. Care shall be taken to ensure compliance with all regulatory requirements at site.
- (iv) Seven (7) day inspections are required during construction and at all times until Final Stabilization has been achieved. Seeding and mulching of disturbed areas does NOT count as final stabilization until such time as 70% pre-disturbed vegetative cover has been achieved. Sites with growth in place sufficient to deter erosion that have not yet achieved final stabilization may petition the City to grant an alternative inspection schedule while awaiting additional growth for final stabilization. These inspections must be conducted in accordance with the above paragraphs.

**F) APPLYING BMPs TO STABILIZE SITE:**

The duration of the exposure of incomplete construction to the effects of weather shall be as short as practicable. BMPs such as: seeding, surface roughening, mulching, applying tackifier, use of geotextiles and matting, permanent landscaping, or other selected BMPs shall be applied within fourteen (14) calendar days of completion of grading/soil disturbance activities to stabilize the construction site unless disturbed area is within 100 feet of an MS4 or State Waters or has slopes of 3 to 1 or greater in which case BMPs shall be implemented within seven (7) calendar days of completion of grading activities. Disturbed areas where work is temporarily halted shall be temporarily stabilized within seven (7) days after the activity ceased unless work is to be resumed within thirty (30) calendar days after the activity ceased.

Clearing and grubbing operations shall be scheduled and performed to minimize both the area of the Project disturbed at a given time and the amount of time that disturbed areas remain open. BMPs, such as temporary seeding, are required between successive construction stages when disturbed areas will not be stable or active for thirty (30) calendar days or more. No payment will be made for additional work required because the Contractor has failed to properly coordinate the BMP schedule, thus causing previously stabilized areas to be disturbed by operations that could have been performed prior to the stabilization. Upon failure of the Contractor to coordinate the

permanent BMPs with the grading operations in a manner to effectively control erosion and prevent water pollution, the Permit Enforcement Authority can suspend the Contractor's grading operations and the Project Manager can withhold monies due to the Contractor on current estimates until such time that all aspects of the work are coordinated in an acceptable manner.

G) WORK OUTSIDE LIMITS OF CONSTRUCTION: Non-contiguous areas outside the limits of construction that are used by the Contractor that include, but are not limited to, borrow pits, haul routes, storage and disposal areas, field offices, maintenance, batching areas, etc., shall have appropriate BMPs implemented by the Contractor at the Contractor's expense. Should said areas meet applicable CASDP Permit criteria, the Contractor shall obtain a separate CASDP or amend existing CASDP for each area as applicable at no additional expense to the City.

H) MAINTENANCE: The Contractor shall continuously maintain erosion and sediment control BMPs on a daily basis or as directed by the ECS so that they function properly during and after construction (including work suspensions) until Final Stabilization has been approved by the Permit Enforcement Authority Maintenance includes, but is not limited to, the following items:

- (i) From the time seeding and mulching work begins until the date the Project has reached Substantial Completion of Erosion Control, the Contractor shall keep all seeded areas stabilized at all times. Any damage to seeded areas or to mulch materials shall be promptly repaired.
- (ii) All inspection sediment removal, and BMP maintenance activities to comply with all Federal, State & Local erosion control permit requirements until Final Stabilization is reached.
- (iii) All removal and replacement of existing BMPs due to damage to same suffered either by the contractor, outside agencies, the public, or acts of God.
- (iv) All required mechanical and/ or manual street sweeping.
- (v) Discretionary changes required of any regulatory enforcement officer.

If the Contractor fails to maintain the BMPs in accordance with the Contract, or as directed, the City may at the expiration of a period of 48 hours, after having given the Contractor written notice, proceed to maintain BMPs as deemed necessary. The cost thereof will be deducted from any compensation due, or which may become due to the Contractor under this Contract.

I) MINOR SWMP MODIFICATIONS: Shall be made in the field by the Contractor and thoroughly documented in the Contractor's SWMP narrative and drawings. Should the Permit Enforcement Authority deem minor field modifications inadequate, the Contractor may be required to a) make specific modifications as requested by the Permit Enforcement Authority or b) Return to the original approved design specifications. Minor SWMP Modifications are allowed, covered under the original CASDP, and required as part of standard maintenance and operation.

J) MAJOR SWMP MODIFICATION: The City reserves the right to require changes in the Work or Project Limits that may require a Major Modification to the SWMP and/ or CASDP due to unforeseen circumstances. Should this occur, the Contractor will be responsible for the following (as applicable) and applying for CASDP amendment:

- (i) Make required revisions to comply with changing Federal or State rulemaking if it PWSTM Standard Concrete Construction Details & Technical Specifications

occurs within timeframe of the Project

- (ii) Make required revisions due to unforeseen or unplanned conditions leading to deficient Drawings/ SWMP (hazardous materials encountered, landfills, expansion of work limits, etc.)
- (iii) Prepare revised SWMP elements endorsed by a Professional Engineer licensed in the State of Colorado.

K) SUBSTANTIAL COMPLETION OF EROSION CONTROL: When a CASDP is required for the Project, Substantial Completion of the Project as defined by the City and County of Denver General Contract Conditions cannot be reached until Substantial Completion of Erosion Control has been granted. Granting of Substantial Completion of Erosion Control must be requested by the Contractor and be approved by the Permit Enforcement Authority in the form of a "Certificate of Substantial Completion of Erosion Control".

L) FINAL STABILIZATION: Granting of Final Stabilization must be requested by the Contractor and be approved by the Permit Enforcement Authority. Other permanent soil stabilization techniques may be proposed, in writing, by the Contractor and used upon approval, in writing, by the Project Manager and Permit Enforcement Authority.

The Contractor shall follow the following procedures for approval of Final Stabilization:

- (i) The Contractor shall file Inactivation Request for Construction Activities Stormwater Discharge Permit (available within CASDP guidance documents) with the Permit Enforcement Authority.
- (ii) The Contractor shall coordinate with the Permit Enforcement Authority to hold a Final Inactivation Inspection.
- (iii) If passing, the Permit Enforcement Authority transmits a letter of approval for Final Stabilization.
- (iv) If not passing, the Permit Enforcement Authority transmits a letter of denial for Final Stabilization with associated inspection report to Contractor.
- (v) Stabilization, inspection and maintenance requirements shall continue until confirmation of having met final closure requirements have been granted in writing by the Permit Enforcement Authority.

When Final Stabilization has been reached, the Permit Enforcement Authority shall issue a "Certificate of Final Stabilization".

- (vi) Once the Inactivation request is approved by the City and County of Denver, the contractor can apply to close the State Stormwater Permit.

M) FINAL ACCEPTANCE:

CASDP obligations (including reaching Final Stabilization) may hinder the ability to reach Final Acceptance for the overall Project as defined in the City General Contract Conditions.

## **PART VI: CONSTRUCTION OF BMPs**

BMPs shall be constructed so that they conform to all requirements as set forth within the Project SWMP. They shall meet all requirements set forth within each BMP detail and shall be installed and maintained so that they function in an effective and operable manner.

## **PART VI: METHOD OF MEASUREMENT**

Because a SWMP and CASDP are not necessary for the Project, all cost for performance of the Best Management Practices, with the exception of inlet protection, shall not be paid for separately but shall be included in the work. Inlet protection shall be paid on a per unit basis.

Removal of sediment & trash that is or is not generated by construction activities will not be measured separately but shall be included in the work.

Any excavation required for the removal of sediment from traps, basins, areas adjacent to silt fences and erosion bales, and any other cleanout excavation of accumulated sediment, and removal of check dams or storm drain inlet protection will not be measured separately but shall be included in the work.

## **PART VII: BASIS OF PAYMENT**

Because a SWMP and CASDP are not necessary for the Project, all cost for performance of the Work to furnish, install, maintain, replace (if not due to contractor negligence), remove, and dispose of BMPs specified in the Contract shall not be paid for separately, but shall be included in the work. Only Storm Drainage Inlet Protection will be measured and each Bid Item unit includes all materials, equipment and labor necessary to protect each inlet regardless of the size, type or timeframe as per the current City of Denver Stormwater Management Plans / (SWMP) requirements. The cost for any corrective actions required by the State or City due to contractor's failure to obtain or comply with applicable Permits will be borne by the Contractor, including fines and penalties. In the case of failures on the part of the Contractor in controlling erosion, sedimentation, and/or water pollution, the City may provide the necessary corrective actions. All corrective action costs, including Project Managing costs, will be charged to the Contractor, and appropriate deduction will be made from the Contractor's monthly pay estimate.

The sole remedy for additional costs associated with installation of BMPs as required by regulatory agencies to ensure compliance with local and State requirements shall be included in the cost of the adjacent concrete repair work as provided in the Bid Schedule of this Contract. The Contractor however may submit a separate itemized Change Order for any required Major SWMP Modification proposed by the City during the course of the Project.

All other work required as set forth in this Revised Section 208–Erosion Control including all materials, equipment and labor, to permit, set-up, maintain, document, remove and clean-up all erosion control BMP's as per current City of Denver Stormwater Management Plans/ (SWMP) requirements will not be paid separately; all costs incurred by the Contractor to meet the requirements of this Section regarding Erosion Control unless provided for in the Bid shall be included in the related appurtenance.

Payment will be made under:

<b><u>PAY ITEM</u></b>	<b><u>PAY UNIT</u></b>
Storm Drainage Inlet Protection	EA

Only Storm Drainage Inlet Protection will be measured for payment and each Bid Item unit includes all materials, equipment and labor necessary to protect each inlet regardless of the size or type as per the current City of Denver Stormwater Management Plans / (SWMP) requirements. All other work required as set forth in this Revised Section 208 –Erosion Control including all materials, equipment and labor, to permit, set-up, maintain, document, remove and clean-up all erosion control BMP's as per current City of Denver Stormwater Management Plans / (SWMP) requirements will not be paid separately; all costs incurred by the Contractor to meet the requirements of this Section regarding Erosion Control unless provided for in the Bid shall be included in the related appurtenance. When the contract does not include pay items for Erosion Control, these items will not be paid for separately but shall be included in the work.

Payment for each BMP item will be full compensation for all work, materials and equipment required to furnish, install, maintain, remove, and dispose of it. BMPs as deployed per the SWMP requiring replacement due to Contractor negligence and or carelessness shall be provided at the Contactor's expense.

Temporary BMPs required due to the Contractor's negligence, carelessness, or failure to install permanent controls as a part of the work as scheduled or for the Contractor's convenience, shall be performed at the Contractor's expense.

If the Contractor fails to complete construction within the approved contract time, payment will not be made for Section 208 pay items for the period of time after expiration of the approved contract time. These items shall be provided at the Contractor's expense.

The cost for any corrective actions required by the State or City due to contractor's failure to obtain or comply with applicable Permits will be borne by the Contractor, including fines and penalties. In the case of failures on the part of the Contractor in controlling erosion, sedimentation, and/or water pollution, the City may provide the necessary corrective actions. All corrective action costs, including Project engineering costs, will be charged to the Contractor, and appropriate deduction will be made from the Contractor's monthly pay estimate.

The sole remedy for additional costs associated with installation of BMPs as required by regulatory agencies to ensure compliance with local and State requirements shall be per unit BMP as provided in the Bid Schedule of this Contract. The Contractor however may submit a separate itemized Change Order for any required Major SWMP Modification proposed by the City during the course of the Project.

When the contract does not include pay items for Erosion Control these items will not be paid for separately but shall be included in the work.

#### **END OF REVISION OF SECTION 208**

PWSTM Standard Concrete Construction Details & Technical Specifications

**REVISION OF SECTION 209  
WATERING AND DUST PALLIATIVES**

Section 209 of the Standard Specifications is hereby revised as follows:

Subsections 209.07 and 209.08 shall be revised as follows:

Watering and Dust Palliatives will not be measured and paid for separately but shall be included in the cost of the work.

**END OF REVISION OF SECTION 209**



## **REVISION OF SECTION 210 RESET STRUCTURES**

Section 210 of the Standard Specifications is hereby revised as follows:

Subsection 210.09 shall include the following:

Signs and traffic signals shall be reset in accordance with the City and County of Denver Transportation Engineering Services requirements needed to remove and restore existing signage and at locations indicated on the plans, or as directed by the Project Manager. It will be the Contractor's responsibility to supply and install any new materials needed to restore the signs and traffic signals to service at the new location.

Subsection 210.10 shall include the following:

Manholes, water meters, inlet castings, valve boxes and pull boxes shall be adjusted in accordance with the applicable standards of the Utility Owner. The Contractor shall be responsible for determining the proper Utility Owner and coordinating these adjustments. Survey range boxes shall be adjusted as directed by the Project Manager. Bid Item "Reset Inlet Grate, Frame and Adjustable Curbhead with new castings" will include for each existing single inlet all materials, equipment and labor, to remove and dispose of the existing castings and provide and place new castings with mounting hardware, grout and up to 1 course of standard brick riser as per Wastewater Standard Details DRWG NO. S-716 and all other labor, equipment, materials and hauling and disposal necessary to complete the work. Both Bid Items; "Adjust Inlet Frame" and "Adjustable Curbhead and reset Inlet Frame, Grate and Adjustable Curbhead" shall include all related work required to construct the rebar reinforced 8" x 12" x inlet width concrete Curb Head Beam as per Wastewater Standard Details Drawings 616.1-3. Restoration of landscaping beyond 12" limits outlined on the plans and/or as marked in the field by the Project Manager will not be paid for.

Subsection 210.12 shall include the following:

All quantities to be submitted for payment must be measured in person by the Contractor with the Project Inspector and recorded by location in tabular form and summarized utilizing the Field Measurement Report (FMR), see FMR sample in APPENDICES at the end of the Technical Specifications, in manner acceptable to the Project Manager and be submitted for review and acceptance in advance of each pay application.

Subsection 210.13 shall be revised to include the following:

The accepted quantities will be paid for at the contract unit price for each of the pay items listed below that appear in the Contract bid schedule. Payment shall be full compensation for all labor, equipment, time and materials for each unit bid item complete in place including saw cutting, scraping, sandblasting, removal, hauling and disposal of such items, excavation of subgrade material reconditioning or installation of aggregate base course and subsequent backfill, grading and compaction (with moisture/density control per the Revision of Subsection 203.07) to proposed subgrade elevation. The price shall also include salvageable materials removed, their custody, preservation, storage.

**PAY ITEMS**

**PAY UNIT**

Reset Ground Sign	EA
Adjust Manhole, Meter, Valve Box, Pull Box	EA
Adjust Inlet Frame and Adjustable Curb Head	EA
Reset Inlet Grate, Frame and Adjustable Curbbox (New Castings)	EA

When the contract does not include pay items for Reset Structures, these items will not be paid for separately but shall be included in the work.

**END OF REVISION OF SECTION 210**

## **REVISION OF SECTION 212 SEEDING, FERTILIZER AND SODDING**

Section 212 of the Standard Specifications is hereby revised as follows:

All landscape restoration will be completed and accepted prior to consideration of the reduction of retainage. Normally landscape restoration will start as soon as possible after concrete construction has been completed but landscape restoration shall be completed within 7 calendar days after the date the adjacent concrete was poured. Minor exceptions may be requested by the Contractor in writing for consideration by the Project Manager during cold weather months when landscape work is not practical.

Subsection 212.01 shall include the following:

This work shall include restoring all existing landscaping that is within twelve inches (12") of the concrete repair reconstruction areas that are damaged as a result of the reconstruction activity. The bid item "Restore Landscaping, In Kind" item shall apply to all landscaping within the limits of construction unless agreed upon in writing by the Project Manager in advance of the related concrete repair work. Materials used to restore landscaping shall be replaced "in-kind" unless otherwise approved by the Project Manager. All landscaped area to be restored shall be backfilled and compacted with native soil so that they may have a minimum of 4" and a maximum of 6" of amended topsoil or planter's mix placed in lieu of existing backfill material in the top 4" cross sectional vertical area below finish grade that is hand tamped and topped off to avoid settlement. Amended topsoil or planter's mix shall be 70% top soil with 30% compost and the source must be submitted and approved by the Project Manager prior to use. Seeding areas larger than twelve inches must include hydraulic mulching with all costs to be included in the square foot price of "Restore Landscaping, In-Kind". Only at the direction of the Project Manager will seeding be accepted in lieu of sodding. Amended Top Soil and Planter's Mix samples and mix design and supplier must be submitted for approval prior to use.

"Restore Landscaping, In Kind" shall include restoring all landscaping that is disturbed within the limits of construction. This includes any and all landscape plants, trees, shrubs, or other materials including concrete, asphalt, pavers or blocks (concrete or brick), landscape rock, sodding, flowers, shrubs and landscape timbers or statuary. The Contractor shall be required to maintain the landscaping planting in accordance with Section 214.

Subsection 212.01 shall include the following:

Work performed in areas under the jurisdiction of Denver Parks and Recreation Department shall conform to the standards of that Department. All costs related to acquiring the Denver Parks ROW permit are included in the Restore Landscaping, In-Kind Pay Item and will not be paid separately.

Subsection 212.07 is hereby revised to include the following:

Only the work restoring existing landscaping that is within twelve inches (12") of the concrete repair reconstruction areas that are damaged as a result of the reconstruction activity will be measured for payment. Any areas beyond twelve inches (12") that are damaged by the Contractor will not be measured for payment and will be repaired by the Contractor at no

expense to the City. Copies of Top Soil load tickets including a summary sheet shall be submitted for review and acceptance in advance of each pay application.

All quantities to be submitted for payment must be measured in person by the Contractor with the Project Inspector and recorded by location in tabular form and summarized utilizing the Field Measurement Report (FMR), see FMR sample in APPENDICES at the end of the Technical Specifications, in manner acceptable to the Project Manager and be submitted for review and acceptance in advance of each pay application.

**PAY ITEMS**

**PAY UNIT**

Sodding	SF
Restore Landscaping, In-Kind	SF
Amended Top Soil or Landscape Planter's Soil Mix	CY

When the contract does not include pay items for landscape repair, top soil, fertilizer, seeding or sodding, these items will not be paid for separately but shall be included in the work.

**END OF REVISION OF SECTION 212**

**REVISION OF SECTION 304  
AGGREGATE BASE COURSE**

Section 304 of the Standard Specifications is hereby revised as follows:

Subsection 304.01 is revised as follows:

This work includes any type of removal or excavation of in-fill material, loading, removal, hauling and disposal of unsuitable materials and consists of furnishing and placing aggregate base course, only if required or at the direction of the Project Inspector or Project Manager on prepared sub-grade. The Contractor shall work to minimize the removal of suitable undisturbed existing subgrade when performing the removal of existing concrete or asphalt infrastructure or grading existing soil.

Subsection 304.02 is revised as follows:

The use of Aggregate Road Base made from recycled concrete is prohibited between the flowline and property line and in any work areas adjacent to landscaped areas.

Subsection 304.06 is revised as follows:

All material within the street section shall be compacted to 95% of maximum density as determined in accordance with AASHTO T-99; all areas outside the street section shall be compacted to 90% of the maximum density determined in accordance with AASHTO T-180. It is the Contractor's responsibility to provide Quality Control for material density and strength testing and provide test results in a testing frequency, method and report as per Pre-construction submittal approved by the City Project Manager. Quality Control testing, reports and submittals will not be paid for separately but shall be included in the work.

Subsection 304.07 is hereby revised as follows:

Aggregate Base Course will be measured by the ton. All quantities to be submitted for payment must include copies of the load tickets, delivered to the project location, accompanied by a summary including the load ticket number supplier, date and weight in tabular form and summarized utilizing the Field Measurement Report (FMR), see FMR sample in APPENDICES at the end of the Technical Specifications, in manner acceptable to the Project Manager and must be submitted for review and acceptance in advance of each pay application.

Subsection 304.08 is hereby revised as follows:

Payment for the accepted quantities of Aggregate Base Course measured per ton shall be full compensation for all labor, equipment, time and materials for each unit bid item complete in place including excavation, removal, hauling and disposal of removal items, excavation of subgrade material, installation of aggregate base course and subsequent backfill, grading and compaction (with moisture/density control per the Revision of Subsection 203.07) to proposed subgrade elevation.

**PAY ITEM**

**PAY UNIT**

Aggregate Base Course (Class 6) (Complete in-Place)

TN

When the contract does not include pay items for Aggregate Base Course, these items will not be paid for separately but shall be included in the work.

**END OF REVISION OF SECTION 304**

**REVISION OF SECTION 306  
RECONDITIONING**

Section 306 of the Standard Specifications is hereby revised as follows:

Subsection 306.01 shall be revised to include the following:

All existing subgrade on alleys and streets from back of curb to back of curb shall be reconditioned.

Subsection 306.02 shall be revised to include:

Unless otherwise indicated on the plans, the density requirements for reconditioning shall be:

- Clay Soils - 95% of the maximum density determined in accordance with AASHTO T-99
- Granular Soils - 90% of the maximum density determined in accordance with AASHTO T-180

It is the Contractor's responsibility to provide Quality Control for material density and strength testing and provide test results in a testing frequency, method and compile comprehensive reports as per Pre-construction submittal approved by the City Project Manager. Quality Control material testing, reports and submittals will not be paid for separately but shall be included in the work.

The Quality Control Plan (QCP) is a required submittal that is Contract Specific and states how the process controls of materials, material testing, equipment, personnel and operations shall be maintained. As a minimum, the QCP shall include the following:

1. Project Contract Control Number and Name. Date of the NTP and subsequent close out date with respect to allotted calendar days.
2. The company name, personnel names and duties, telephone number(s), of all quality control personnel to be utilized from a certified lab including current copies of their certification letter.
3. Sub-grade compaction and concrete tests will be once weekly or additionally as needed for Quality Control in critical conditions. Additional concrete tests are required for each instance High Early Strength Concrete is used.
4. Written test reports including all pertinent information in a form acceptable to the Project Manager. Test reports must be submitted in a timely fashion, as a minimum test reports must be submitted within 30 days of the test and acceptance of the related materials or product is contingent upon receipt of acceptable reports.

Subsection 306.04 is revised as follows:

Reconditioning will not be measured and paid for separately but shall be included in the work.

**END OF REVISION OF SECTION 306**

PWSTM Standard Concrete Construction Details & Technical Specifications

## **REVISION OF SECTION 401 AND 403 PLANT MIX PAVEMENTS**

Sections 401 and 403 of the Standard Specifications for Road and Bridge Construction are hereby deleted and replaced with the Comprehensive Specifications for the Metropolitan Government Pavement Project Managers Council (MGPEC), included herein. Section 9.16 and section 9.17 of the MGPEC Specifications is hereby deleted and replaced as follows:

HMAP patching or overlay shall be paid by the ton by batch ticket. Tack Coat will not be measured and paid for separately but shall be included in the cost of the work.

All Asphalt Mix Designs are a required submittal and must be approved prior to use in the City and County of Denver.

It is the Contractor's responsibility to provide Quality Control testing for material density and strength testing and provide test results in a testing frequency, method and report as per Pre-construction submittal Quality Control Plan (QCP) that must be approved by the City Project Manager prior to starting work. Quality Control material testing, reports and submittals will not be paid for separately but shall be included in the work.

The Quality Control Plan (QCP) is a required submittal that is Contract Specific and states how the process controls of materials, material testing, equipment, personnel and operations shall be maintained. As a minimum, the QCP shall include the following:

1. Project Contract Control Number and Name. Date of the NTP and subsequent close out date with respect to allotted calendar days.
2. The company name, personnel names and duties, telephone number(s), of all quality control personnel to be utilized from a certified lab including current copies of their certification letter.
3. Sub-grade compaction and concrete tests will be once weekly or additionally as needed for Quality Control in critical conditions. Additional concrete tests are required for each instance High Early Strength Concrete is used.
4. Written test reports including all pertinent information in a form acceptable to the Project Manager. Test reports must be submitted in a timely fashion, as a minimum test reports must be submitted within 30 days of the test and acceptance of the related materials or product is contingent upon receipt of acceptable reports.

### **METHOD OF MEASUREMENT**

Subsection 401.22 and 403.04 of the Standard Specifications is hereby revised as follows:

All work performed will be measured by the ton based on copies of the approved supplier's asphalt load tickets provided with a summary table with each Application for Payment.



Payment will be made under:

**PAY ITEM**

**PAY UNIT**

HBP Patch/Overlay

TON

When the contract does not include pay items for Plant Mix Pavements, these items will not be paid for separately but shall be included in the work.

**END OF REVISION OF SECTION 401 / 403**

**REVISION OF SECTION 412  
PORTLAND CEMENT CONCRETE PAVEMENT**

Section 412 of the Standard Specifications is hereby revised as follows:

Subsection 412.01 shall be revised to include the following:

This work shall also include concrete streets, driveways, crosspans, valley gutter, bus pads and alley paving.

Subsection 412.03 shall be revised to include the following:

All Portland Cement Concrete Pavement used on this Contract shall be a minimum 4500 psi 28-day design with 10% maximum fly ash and shall be reinforced with polypropylene fibers. Polypropylene fibers shall be FIBERMESH® or APPROVED EQUIVALENT. Length of fibers shall be as recommended by the manufacturer. Add 1.5 pounds FIBERMESH® or APPROVED EQUIVALENT per cubic yard of concrete. The Contractor is required to submit copies of all concrete batch tickets for loads delivered during the previous pay period with each Application for Payment to the Project Manager on the Contract. All Portland Concrete Cement All Asphalt Mix Designs are a required submittal and must be approved prior to use in the City and County of Denver.

It is the Contractor's responsibility to provide Quality Control for material density and strength testing and provide test results in a testing frequency, method and report as per Pre-construction submittal Quality Control Plan (QCP) that must be approved by the City Project Manager prior to starting work. Quality Control material testing, reports and submittals will not be paid for separately but shall be included in the work.

The Quality Control Plan (QCP) is a required submittal that is Contract Specific and states how the process controls of materials, material testing, equipment, personnel and operations shall be maintained. As a minimum, the QCP shall include the following:

1. Project Contract Control Number and Name. Date of the NTP and subsequent close out date with respect to allotted calendar days.
2. The company name, personnel names and duties, telephone number(s), of all quality control personnel to be utilized from a certified lab including current copies of their certification letter.
3. Sub-grade compaction, HBP asphalt patch and concrete tests will be once weekly or additionally as needed for Quality Control in critical conditions. Additional concrete tests are required for each instance High Early Strength Concrete is used. For Concrete Strength Cylinder test a minimum of 1 set of four cylinders taken in the first 100CY then again in the second hundred cubic yards then every 500CY thereafter provided all tests exceed minimum strength requirements except as noted above for additional high early concrete tests.
4. Written test reports including all pertinent information in a form acceptable to the Project Manager. Test reports must be submitted in a timely fashion, as a minimum test reports must be submitted within 30 days of the test and acceptance of the related materials or product is contingent upon receipt of acceptable reports.

PWSTM Standard Concrete Construction Details & Technical Specifications

Subsection 412.04 shall be deleted and replaced with Subsection 601.05, with the following revisions:  
Calcium chloride (up to 1 percent by weight of cement) or Type C or E accelerators may be used under the following conditions:

- a) The median daily temperature is less than 55 degrees (Average of previous three days).
- b) The date of placement is between September 30th and May 30th.
- c) The concrete temperature may not exceed 80 degrees F prior to placement.

Difficulties encountered as a result of use of accelerators, the costs of associated delays, and corrective action costs shall be borne by the Contractor.

When High Early Strength Concrete is requested by the City's Project Manager for the convenience of the City the concrete mix designs shall be submitted to the Project Manager for approval for High Early strength concrete that shall be a 7-sack mix with a minimum of 660 pounds of cementitious material that develops field strength of 3000 psi (minimum required for additional payment) achieved in 24 hours or less and developing 6000 psi in 28 days. The additional charge per cubic yard will be paid for high early concrete will be compensation only for the difference in concrete cost per cubic yard and extra labor per yard for all work performed using High Early Strength Concrete when directed to be used by the Project Manager. If high early concrete is placed by the contractor without the request of the City the entire additional cost will be borne by the contractor. When directed by the Project Manager, a maturity meter (James Instrument Model No. 3006) shall be used to monitor on-site maturity of pavement concrete. The Contractor shall provide the Project Manger data outlining an established maturity versus strength relationship for the concrete mixture being used. This correlation may be achieved by casting and curing cylinders on site, monitoring temperature and maturity of cylinders and paving concrete versus time, and testing cylinders at time intervals to establish the correlation.

When High Early Strength Concrete is requested by the City's Project Manager for the convenience of the City, a field strength of 3000 psi shall be achieved within 24 hours and a field strength of 6000 psi (minimum required for additional payment) shall be achieved in 28 days or less. The additional charge per cubic yard will be paid for High Early Strength Concrete will be compensation only for the difference in concrete cost per cubic yard and extra labor per yard for all work performed using High Strength Concrete when directed to be used by the Project Manager. If High Early Strength Concrete is placed by the contractor without the request of the City the entire additional cost will be borne by the contractor.

Subsection 412.10 shall be revised to include the following:

The Contractor is required to submit a detailed breakdown of paving equipment, vibratory devices, finishing tools, and provisions for protection from or avoidance of damage from weather impacts. This information shall be submitted for approval by the Project Manager prior to commencing any construction activities.

Subsection 412.12 shall be revised to include the following:

The Contractor shall insure that new concrete items built under this contract drain properly and, as such, there are no areas of standing water on new concrete items.

The Contractor shall protect all new concrete items built under this Contract against defacement, or other injury, from any cause. If said damage cannot be adequately repaired to the satisfaction of the Project Manager or if there are any areas of standing water, the Contractor shall remove and replace the unacceptable items at Contractor's expense.

Subsection 412.13(a) 1, shall be deleted and replaced with the following:

*Longitudinal Construction Joints.*

Deformed steel tie bars of specified length, size, spacing, and material shall be placed perpendicular to the longitudinal joints by an approved method. When adjacent lanes of pavement are constructed separately, Grade 40 (not Grade 60) tie bars may be bent at right angles against the form of the first lane constructed and straightened into final position before the concrete of the adjacent lane is placed. If epoxy-coated steel tie bars are bent and then straightened into final position, at the Project Manager's discretion the bars shall be repainted with epoxy coating prior to placement of the adjacent concrete. The tie bars shall be inserted into the plastic state concrete between the auger and the vibrators. Other methods of the bar placement may be acceptable if the Contractor can demonstrate satisfactory performance of his alternate method. Proposals of alternate methods or additional costs associated with other methods shall be at the Contractor's expense.

Subsection 412.13(b), delete the first sentence and replace it with the following:

Weakened plane joints shall be formed by sawing to the depth specified on the drawings, in accordance with the requirements of this subsection or as otherwise approved by the Project Manager, except as follows: The contractor shall adhere to the City and County of Denver Noise Control Ordinance (D.R.M.C. Chapter 36), joints shall be formed initially by deep tooling or "soft-cut" methods, followed by sawing at the first available time within the ordinance.

Subsection 412.13(b) 2, delete the first and second paragraphs and replace with the following:

Transverse weakened plane joints shall be formed by sawing a groove in hardened concrete in accordance with City of Denver Transportation Standards and Details for the Engineering Division as per STD. DWG. NO. 11.3 Concrete Pavement Joint Sealant plan details.

The Contractor shall cut the transverse and longitudinal joints to the width and depth required in accordance with City of Denver Transportation Standards and Details for the Engineering Division. The cut shall be made with a power-driven saw. Any damage to the concrete pavement such as spalling or fracturing shall be repaired by the Contractor as directed by the Project Manager at no cost to the project. The joints shall be immediately flushed with water to remove any sawing residue from the joint and pavement surface.

If concrete approaches or any widening beyond the width of the initial pass is constructed subsequent to the driving lanes, transverse weakened plane joints shall immediately be formed in the approaches extending from any joints in the driving lanes.

Subsection 412.13(b) 2, shall be revised to include the following:

The time schedule for sawing weakened plane joints shall be as follows: Every second joint shall be sawed 2 to 12 hours after pavement placement, provided the concrete has sufficiently set so as to preclude the dislodging of aggregate particles by the saw. Unless otherwise directed by the Project Manager, the exact time of sawing shall be determined by the Contractor and will be dependent on weather conditions, ambient temperature, mix characteristics and other factors that may affect the setting time of the concrete. Every effort shall be made to saw early enough to control or limit random cracking. The intermediate joints shall be sawed prior to opening to traffic, but in no case, longer than 48 hours after placement of the concrete.

The Contractor shall adhere to the City and County of Denver Noise Control Ordinance (D.R.M.C. Chapter 36). In the event that the need for saw cutting is anticipated during restricted time periods, a "soft-cut" saw shall be used before restricted hours, or deep tooling of joints shall be performed on plastic concrete, followed by saw cutting of the concrete as soon as possible during unrestricted hours. At the discretion of the Project Manager, saw cutting will be prohibited between 10:00 p.m. and 7:00 a.m.

Subsection 412.14 and referenced Section 711.01 Concrete Curing Materials shall be modified, allowable curing compound types and specification for all Portland Cement Concrete Pavement placed on this Contract shall be a combination cure-sealer that meets or exceeds ASTM-1315 Type I, Class A (clear, non-yellowing). The compound must be an acrylic copolymer type, non-freezing solvent based, with a minimum of 25% solids content. Compound must be VOC compliant in accordance with EPA 40 CFR Part 59. The final gloss appearance will serve as proof of application.

The Contractor shall use the cure-sealer according to the manufacturers recommendations so that when applied it will not adversely affect the skid resistance of the pavement.

Subsection 412.18 shall be deleted and replaced with the following:

This work shall consist of sawing, cleaning and sealing Portland cement concrete pavement joints for new pavements. All Joint Sealing methods and products must be submitted to and approved by the Project Manager in advance of scheduling the work.

Cleaning, repairing and proper curing of any spalls, fractures, breaks or voids in the concrete surface of the joints shall be accomplished at least 4 days prior to installing the backer rod material or joint sealant. Joint sealing or resealing shall be performed only when the ambient and pavement temperatures are 50 degrees F or higher, unless otherwise approved by the Project Manager. The pavement surface and joints shall be dry and the sealant shall not be placed unless the weather conditions are dry. The sealant shall be placed a minimum of 4 days after joints are washed clean.

The Contractor shall thoroughly clean the joint and adjacent pavement for a width of not less than one inch on each side of the joint of all scale, dirt, dust, residue, or any foreign material that will impair bonding of the joint sealant. Immediately prior to the placement of backer rod material and the sealant, the joints shall be cleansed using a minimum of 100 psi compressed air.

Work shall be stopped when and if it is found that there is oil or moisture in the compressed air. Work shall not resume until suitable adjustments are made. The Contractor is to check for such oil or moisture at the start of every work cycle and periodically during the cycle using a Project Manager approved method. The backer rod shall be placed in such a manner that the grade for the proper depth of the sealant material is maintained. Under no conditions shall the Contractor place the backer rod material or the sealant if there is dust, moisture, oil or any foreign material on that portion of the concrete that is to receive the backer rod material or joint sealant.

A copy of the manufacturer's recommendations pertaining to the heating and application of the sealant shall be submitted to the Project Manager prior to the beginning of work, and these recommendations shall be adhered to by the Contractor, with such exceptions as this specification may require.

The sealant material shall be hot applied into the joint using equipment and techniques recommended by the joint sealant manufacturer. The surface of the finished joint seal shall have a flat level surface that is  $3/16 \pm 1/16$  inch below the surface of the concrete pavement. Sealant not placed within these tolerances will not be measured and paid for, and the Contractor shall remove the joint sealant material and clean and reseal these joints in accordance with the criteria outlined in the special provision at no additional cost to the project. If, in the opinion of the Project Manager, the Contractor shows an inconsistency in his ability to fill the joints to the required dimensions, the Contractor shall cease his operations until such time as he can comply with the required criteria in a consistent manner.

In addition, the Project Manager may elect to check for bonding or adherence to the sides of the joint. Material shall conform to Subsection 705.01(a).

The joint material must withstand a 20 pound pull force applied perpendicular to the joint as indicated in "COLORADO PROCEDURE 67-90".

Subsection 412.22 shall be deleted and replaced with the following:

The pavement shall be cleaned and opened to traffic in accordance with the time requirements shown on the plans or in the specifications.

Pavement shall not be opened until it has reached a compressive strength of 2500 psi in-place, regardless of the curing time required by the Traffic Control Plan. The TCP may necessitate the required compressive strength to be attained within 72 hours or less.

Subsection 412.23 shall be revised to include the following:

Payment under Concrete Pavement shall be full compensation for all materials and labor required to complete the various pavement sections, including the areas of thickened edges, driveways, bus pads and alley paving.

New curb and gutter that is adjacent to new concrete pavement will not be measured and paid for separately but included in the square yard measurement for concrete pavement. Measurement and payment will be to back of curb except where curb ramp limits overlap.

This work shall also include concrete streets, driveways, crosspans, bus pads and alley paving with the finished area measured by the square yard and paid by their respective thickness as Concrete Pavement.

Geo-Tech Material Testing Concrete quantities to be measured will include all equipment, materials and labor to sample concrete at the site of the pour, perform air and slump test, batch weight, make cylinders, transport to lab and perform cylinder strength compression break tests (at 7, 14 and two at 28 days unless otherwise specified for high early strength concrete by the Project Inspector/Manager) for 4 cylinders for each test including report as outlined in Subsection 412.03 all to be completed by a Certified Laboratory/Personnel. Concrete strength test reports submitted to the Project Manager in advance of each Pay Application to be considered for payment.

The accepted quantities for "Concrete Pavement (-") will be paid for at the contract unit price for each of the pay items listed below that appear in the Contract bid schedule. Payment shall be full compensation for all labor, equipment, time and materials for each unit bid item complete in place including saw cutting, joint sealing, scraping, sandblasting, removal, hauling and disposal of such items, excavation of subgrade material reconditioning or installation of aggregate base course and subsequent backfill, grading and compaction (with moisture/density control per the Revision of Subsection 203.07) to proposed subgrade elevation. The price shall also include salvageable materials removed, their custody, preservation, storage, hauling and disposal as provided herein.

When authorized for use by the Project Manager/Inspector the accepted quantities for "High Early Strength Concrete" and "Concrete Class D (Colored)" will be compensation only for the difference in concrete cost per cubic yard and extra labor per yard for all work performed using "High Early Strength Concrete" and Concrete Class D (Colored) will be measured by the cubic yard based on copies of the approved supplier's concrete load tickets provided with a summary in tabular form and summarized utilizing the Field Measurement Report (FMR), see FMR sample in APPENDICES at the end of the Technical Specifications, with each Application for Payment. Copies of all concrete tickets are required for concrete used during that pay period; a separate summary is required for the Quantity of High Early Strength Concrete and includes the ticket number, date and address where it was poured.

**PAY ITEMS**

**PAY UNIT**

24-Hour High Early Strength Concrete	CY
Concrete Class D (Colored)	CY
Geo-Tech Material Testing Concrete	EA
( _") Concrete Pavement	SY

Payment shall be full compensation for labor and materials including, but not limited to, reconditioning, grading, backfill including topsoil and soil amendments, compaction, quality control material testing, curing compound, control and expansion joint and sealant as required to complete these Pay Items.

When the contract does not include pay items for FIBERMESH® or APPROVED EQUIVALENT reinforcement additive, cure-sealer, curing compound, saw cut for construction, control or expansion joints and sealant will not be paid for separately but shall be included in the related concrete work.

Saw-cut Expansion Joint only includes those areas where existing pavement must be cut for the sole purpose of installing an expansion joint. Payment shall be full compensation for "soft cutting" and tooling necessitated by City and County of Denver Noise Control Ordinance (D.R.M.C. Chapter 36), saw cutting hardened concrete, cleaning out the saw cut, expansion material and sealant.

When the contract does not include pay items for Portland Cement Concrete Pavement, these items will not be paid for separately but shall be included in the work.

**END OF REVISION OF SECTION 412**



**SECTION 413  
CONCRETE PATCHING AND CURB HEAD REPLACEMENT**

**DESCRIPTION**

413.01 This work consists of patching and curb head replacement on existing concrete pavement.

**MATERIALS**

413.02 Concrete patching material must be a one component system that requires an exact addition of water. They must meet the following performance requirements at maximum water.

A.	Bond Strength:	1 Day	1500 psi.	
	ASTM C-882	7 Days	2500 psi.	
B.	Length Change:	28 Days Dry	-0.05%	
	ASTM C-157	28 Days Wet	+0.05%	
C.	Compressive Strength:	2 Hours	2500 psi.	
		ASTM C-109	1 Day	5000 psi.
			7 Days	7000 psi.

Aggregate shall consist of 3/8" clean, washed and dried gravel or crushed stone of reasonably uniform quality throughout.

Fushion-Crete®, Transpo T-17 Methyl Methacrylate Polymer Concrete Patching Material, Five Star® Highway Patch, U.S. Grout Corporation® Cementitious Grout, Catch Pavemend®, HD-50 Horizontal Repair Mortar by Dayton® Superior® Corporation are all approved concrete patching material. Concrete patching material brand and technical specifications shall be submitted for approval.

**CONSTRUCTION REQUIREMENTS**

413.03 Preparation of Concrete Surface:

Remove all grease, oil, dirt, curing compounds, laitance and other deleterious materials from the concrete. Roughen the surfaces by sand blasting and provide a near vertical face on the edges of existing concrete to ensure bond. Loose or broken concrete shall be removed. If any existing rebar reinforcing is exposed, it shall be sandblasted. All surfaces shall be thoroughly saturated, and free standing excess water shall be removed with clean compressed air before applying the structural repair material. Minimum depth of patching is 1/2 inches.

413.04 Placing Concrete Patch Material:

Carefully read and understand the manufacturer's instructions as printed on the container. The PWSTM Standard Concrete Construction Details & Technical Specifications

mixing operation should be close to the repair area. A mortar mixer is recommended. For small quantities, an electric drill and paddle mixer is recommended. The mixing order for mortar type mixer shall be as follows:

1. Clean water shall be placed in the mixer at the rate specified on the container instructions. Water content is critical; do not deviate from the amount specified.
2. When temperatures exceed 90° F, a prepackaged set retarder shall be used as recommended by the manufacturer. Add retarder to mixing water, maximizing dispersion in the mix.
3. For pours with greatest depth exceeding 3", 3/8-inch clean washed pea gravel shall be added to the mix at a rate not to exceed 25 lbs. per 50 lb. pail.
4. Add the repair material. This sequence is important in order to produce a consistent mix and to reduce mixing time. Allow approximately 3 minutes mixing time.
5. When pouring large volumes of material, special consideration should be given to maintaining a continuous flow of material producing a wet leading edge. More than one mixer may be necessary to deliver enough material to insure no cold joints.

Place the mixed material into the prepared area, starting from one side of the repair and working to the other side. Do not place the repair material in lifts. Work the material firmly into the bottom and sides of the repair. Screed the material to the desired level. Close up edges of the repair with a trowel. Finish the material to the desired texture. Do not re-temper the material. Clean the mixer and tools periodically with water to prevent build-up, especially in hot temperatures. As soon as the material sets, all exposed surfaces must be thoroughly saturated for 30 minutes.

413.05 Concrete Curb Head Replacement. Concrete curb head that was paved with the concrete pavement shall be constructed as follows:

1. Remove broken curb head and concrete pieces from sound concrete.
2. Place no. 4 deformed vertical bars, 18" O.C. by drilling. Place no. 4 horizontal bars across vertical bars.
3. Prior to pouring new curb head, sand blast existing concrete pavement at curb head location or use other cleaning method as approved by the Project Manager.
4. Saturate sand blasted area and remove standing water immediately prior to replacing concrete.
5. Consolidate concrete by use of high frequency internal vibrators.
6. Provide 1/8" open joint in curb head at existing contraction joints in concrete pavement.

### METHOD OF MEASUREMENT

413.05 All type of Concrete Patching (Structural “-“) shall include removal and hauling of the material to be removed and also includes surface preparation and removal of loose material and cleaning of the existing concrete surface as per material supplier’s recommendations according to the material product data sheets included in the submittal for any and all materials used for Concrete Patching (Structural “-“). Concrete surface patch shall be measured by the average of depth measured in inches patching multiplied by the square foot or as required by the Project Manager. All quantities to be submitted for payment must be measured in person by the Contractor with the Project Inspector and recorded by location in tabular form and summarized utilizing the Field Measurement Report (FMR), see FMR sample in APPENDICES at the end of the Technical Specifications, in manner acceptable to the Project Manager and be submitted for review and acceptance in advance of each pay application.

### BASIS OF PAYMENT

413.06 The accepted quantities will be paid for at the contract unit price for each of the pay items listed below that appear in the bid schedule.

Payment will be made under:

#### PAY ITEMS

#### PAY UNIT

Concrete Patching (Structural surface repair)  
Concrete Patching (Structural Curbhead)

SF-IN  
LF

Payment shall be full compensation for labor and materials including, but not limited to, reconditioning, grading, backfill including topsoil and soil amendments, compaction, quality control material testing, curing compound, control and expansion joint and sealant as required to complete these Pay Items.

When the contract does not include pay items for FIBERMESH® or APPROVED EQUIVALENT reinforcement additive, cure-sealer, curing compound, saw cut for construction, control or expansion joints and sealant will not be paid for separately but shall be included in the related concrete work.

Saw-cut Expansion Joint only includes those areas where existing pavement must be cut for the sole purpose of installing an expansion joint. Payment shall be full compensation for "soft cutting" and tooling necessitated by City and County of Denver Noise Control Ordinance (D.R.M.C. Chapter 36), saw cutting hardened concrete, cleaning out the saw cut, expansion material and sealant.

All work necessary and incidental to the concrete patching and curb head replacement will not be measured and paid for separately but shall be included in the work.

### END OF SECTION 413

PWSTM Standard Concrete Construction Details & Technical Specifications

**REVISION OF SECTION 601  
STRUCTURAL CONCRETE**

Section 601 of the Standard Specifications is hereby revised as follows:

Subsection 601.06, Item 7, is modified as follows:

(7) Supplier's Mix I.D. number

Subsection 601.07, (d) is deleted. Self-contained mobile mixers will not be allowed.

**METHOD OF MEASUREMENT**

601.19 Shall be revised as follows:

Pavestone® or equivalent product acceptable to the adjacent property owner as needed to repair or reconstruct existing stacked concrete block wall will be measured by the square foot of vertical face. Re-enforced Variable Height Concrete Retaining Wall will be constructed 8" thick between 9"-12" with Fibermesh® or approved equivalent only and 8" wall thickness from 12"-30" including #4 rebar placed 12" on center each way (minimum) with vertical to horizontal "L" rebar integrated into monolithically poured adjacent 8" thickened concrete flatwork thickened to 8" for a minimum of 24" from the vertical face be used as directed by the Project Inspector/Manager for Re-enforced Variable Height Concrete Retaining Walls greater than 9" to be measured by the square foot of the vertical face and SF area of 24" wide thickened horizontal adjacent concrete flatwork as directed by the Project Inspector/Manager. All type of Concrete Patching (Structural "-") shall include removal and hauling of the material to be removed and also includes surface preparation and removal of loose material and cleaning of the existing concrete surface as per material supplier's recommendations according to the material product data sheets included in the submittal for any and all materials used for Concrete Patching (Structural "-"). Curb head repair or replacement will be measured by the lineal foot along the front of the curb head. All quantities to be submitted for payment must be measured in person by the Contractor with the Project Inspector and recorded by location in tabular form and summarized utilizing the Field Measurement Report (FMR), see FMR sample in APPENDICES at the end of the Technical Specifications, in manner acceptable to the Project Manager and be submitted for review and acceptance in advance of each pay application.

**BASIS OF PAYMENT**

601.20 The accepted quantities will be paid for at the contract unit price for each of the pay items listed below that appear in the bid schedule.

Payment will be made under:

<u>PAY ITEMS</u>	<u>PAY UNIT</u>
Pavestone® Stacked Pre-cast Wall Blocks	SF
Reinforced Variable Height Concrete Retaining Wall	SF

PWSTM Standard Concrete Construction Details & Technical Specifications

Concrete Patching (Structural Curbhead)

LF

Payment shall be full compensation for labor, equipment and materials including, but not limited to, grade 60 reinforcing #4 rebar, soil reconditioning, grading, backfill and soil including topsoil and soil amendments, compaction, quality control material testing, curing compound, control and expansion joint and sealant as required to complete these Pay Items.

When the contract does not include pay items for FIBERMESH® or APPROVED EQUIVALENT reinforcement additive, cure-sealer, curing compound, saw cut for construction, control or expansion joints, zip-strip and sealant will not be paid for separately but shall be included in the related concrete work.

**END OF REVISION OF SECTION 601**

## **REVISION OF SECTION 603 CULVERTS AND SEWERS**

Section 603 of the Standard Specifications is hereby revised as follows:

### **MATERIALS**

Subsection 603.02 shall be replaced with:

Materials shall meet the requirements described in the current version of the City and County of Denver Wastewater Capital Projects Management Standard Construction Specifications Chapter 10.1 (Precast Concrete Pipe).

### **CONSTRUCTUION REQUIREMENTS**

Subsection 603.03 through 603.10 shall be replaced with:

Reinforced Concrete Pipe shall be constructed in accordance with the Wastewater Capital Projects Management Standard Construction Specifications as well as the current version of the Department of Public Works City and County of Denver Wastewater Management Division Standard Details.

### **METHOD OF MEASUREMENT**

Subsection 603.11 shall be replaced with:

The unit price bid per linear foot for the construction of each section of pipeline shall include all of the Contractor's costs of whatsoever nature for the complete construction of the pipeline, exclusive of manholes, appurtenances, or items otherwise provided for in the Contract Documents. The bid item shall include: trench sloping, benching, bracing, shoring and/or sheeting for pipe and associated appurtenances to assure safe working conditions; design of shoring, stamping and approval by an Engineer licensed in the State of Colorado, submittal as required; furnishing, transporting and installing all pipe and materials; tapping and/or connecting to mainline pipes, structures, stub outs or block outs; concrete coring; plugging of all abandoned lines crossed during construction; furnishing and installing special fittings, including: trash racks, concrete pipe plugs as required, transitional pipe sections required to properly connect different classes of pipe without a manhole or structure and any other special fittings not provided for elsewhere in the Contract Documents; joints and jointing materials, including: grout ,mortar, fiberglass resin, gaskets, seals, bolts, concrete collars, connecting bands, and other miscellaneous items as required to construct the specific pipe joint per manufacturer and City standards; saw cutting and/or roto-milling within mainline (Bf extents) and lateral trench extents prior to excavation; removal and disposal of pavement, roadway surface materials, concrete flatwork, sod, landscaping, stumps, brush, unsuitable material within the trench width and any other materials encountered prior to excavation; excavation, including exploratory excavation, as required by the Construction Project Manager; over- excavation to remove unsuitable foundation material and replacement with granular

or other approved select materials; constructing the specified bedding including the furnishing, placing, and compaction of sand, gravel and rock as required for class B bedding or approved substitution; supply and installation of protective coatings or wrappings; backfilling to include furnishing, transporting, and placement of any additional suitable backfill material required (except for those classified backfill materials provided for elsewhere in the Contract Documents); compaction and backfilling as specified, no additional or separate payment will be made for excess excavated material used as backfill or select material elsewhere on the project; restoration of ground surface to its original condition; grading and leveling; care and diversion of drainage courses; pumping and provision of facilities for diversion of flows; trench dewatering; protection and adjustment of aboveground and underground utilities and service connections or laterals, including water service reconnections and adjustments; sanitary sewer encasement; adjustment and reconnection of sanitary sewer services from mainline sewer to a point where proper connection and drainage can be achieved, unless provided for elsewhere in the Contract Documents; removal and replacement of hydrant laterals and assemblies damaged or relocated during crossing; coordination of gas service and electric relocates; crossing of existing and abandoned utilities; cutting and/or plugging of abandoned or crossed lines where indicated in the Contract Documents, or as directed by the Construction Project Manager; hauling and disposal of construction debris, excess excavated material, damaged materials, unsuitable materials and manifested contaminated materials at the Denver Arapahoe Disposal Site (DADS), recycle and salvage of materials as necessary; removal and replacement and/or relocation of signs, and pipe bollards; providing for additional traffic control, to include barricades, detours and flagmen unless provided for elsewhere in the Contract Documents; removal and replacement of all traffic signal and/or activated loops; QC testing for all associated work components; and all other related and necessary materials, labor and equipment required to construct a complete operable pipeline in accordance with the Contract Documents.

**BASIS OF PAYMENT**

Subsection 603.12 shall include the following:

The accepted quantities will be paid for at the contract unit price for each of the pay items listed below that appear in the bid schedule.

Payment will be made under:

<u>PAY ITEMS</u>	<u>PAY UNIT</u>
15" Reinforced Concrete Pipe (RCP)	LF
18" Reinforced Concrete Pipe (RCP)	LF

Payment shall be full compensation for labor, equipment and materials including, but not limited to, grade 60 reinforcing #4 rebar, soil reconditioning, grading, backfill and soil including topsoil and soil amendments, compaction, quality control material testing, curing compound, control and expansion joint and sealant as required to complete these Pay Items.

When the contract does not include pay items for FIBERMESH® or APPROVED EQUIVALENT PWSTM Standard Concrete Construction Details & Technical Specifications

reinforcement additive, cure-sealer, curing compound, saw cut for construction, control or expansion joints, zip-strip and sealant will not be paid for separately but shall be included in the related concrete work.

**END OF REVISION OF SECTION 603**



**REVISION OF SECTION 604  
MANHOLES, INLETS AND METER VAULTS**

Section 603 of the Standard Specifications is hereby revised as follows:

**CONSTRUCTION REQUIREMENTS**

Subsection 604.04 (c) shall include the following:

Inlets shall be constructed in accordance with the most current version of the Department of Public Works City and County of Denver Wastewater Management Division Standard Details.

Single #16 Inlets are shown on sheet S-616.1

#14 Inlet (L=6') are shown on sheet S-620.1 and S-620.2

**METHOD OF MEASUREMENT**

Subsection 604.06 shall be replaced with the following:

The unit price bid per inlet structure shall include all of the Contractor's costs of whatsoever nature. The price bid shall include: furnishing, transporting, and installing all materials; excavation, including over-excavation to remove unsuitable foundation materials; hauling and disposal of excess material, concrete, pipe collars, reinforcement steel, mortar and grout; manhole lids, rings, covers, grates, frames and curb boxes; open throat construction; galvanized steel rods; manhole steps; concrete ribbed deflectors; backfilling and compaction; removal and replacement of pavement, base coarse, sub-base materials, sod, decorative landscaping and any other surfacing materials; constructing and shaping of the base and invert; replacement of curb, gutter and sidewalk between the transitions as stipulated on the Details; and all other related and necessary materials, work, and equipment required to construct the storm inlet.

**BASIS OF PAYMENT**

Subsection 604.07 shall include the following:

The accepted quantities will be paid for at the contract unit price for each of the pay items listed below that appear in the bid schedule.

Payment will be made under:

**PAY ITEMS**

Number 14 Inlet

Single Number 16 Inlet

**PAY UNIT**

EA

EA

Payment shall be full compensation for labor, equipment and materials including, but not limited to, grade 60 reinforcing #4 rebar, soil reconditioning, grading, backfill and soil including topsoil and soil amendments, compaction, quality control material testing, curing compound, control and

PWSTM Standard Concrete Construction Details & Technical Specifications

Expansion joint and sealant as required to complete these Pay Items.

When the contract does not include pay items for FIBERMESH® or APPROVED EQUIVALENT reinforcement additive, cure-sealer, curing compound, saw cut for construction, control joints or expansion joints, zip-strip and sealant will not be paid for separately but shall be included in the related concrete work.

**END OF REVISION OF SECTION 604**

## **REVISION OF SECTION 608 SIDEWALKS AND BIKEWAYS**

Section 608 of the Standard Specifications is hereby revised as follows:

As a condition acceptance and of payment the Contractor must certify and shall be responsible to ensure that All Concrete Sidewalk and all Concrete Curb ramps shall be constructed by and additionally meet the requirements of the City of Denver Public Works Transportation Standards and Details for the Engineering Division. It shall be the Contractor's responsibility to assess the existing conditions and notify the Project Manager in advance of the work of any existing field conditions, obstacles or conflicts that might inhibit any section of sidewalk or curb ramp from meeting the design criteria outlined in the City of Denver Public Works Transportation Standards and Details for the Engineering Division. All concrete used for Sidewalks, Curb Ramps and Bikeways shall be Class P and shall be reinforced with polypropylene fibers. Polypropylene fibers shall be FIBERMESH® or APPROVED EQUIVALENT. Length of fibers shall be as recommended by the manufacturer. Add 1.5 pounds FIBERMESH® or APPROVED EQUIVALENT per cubic yard of concrete.

Subsection 608.02 shall be deleted in its entirety and replaced with the following:

Materials shall meet the requirements specified in subsection 705.11 joint Fillers. Concrete for sidewalks, curb ramps and bikeways shall be Portland Cement Concrete Pavement and shall be a minimum 4500 psi mix design with 5% maximum fly ash and shall be reinforced with polypropylene fibers, as specified in subsections 601.02 and 601.03, except that No. 67 coarse aggregate shall be used. The concrete curb ramp shall include the cost of an approved truncated dome material and its installations. A sample of the truncated dome material shall be submitted to the Project Manager for approval prior to construction. Only cast-iron ADA dome panels will be paid separately and will cover only the cost of the ADA cast iron dome panel material. The use of calcium chloride, as permitted under Revision of Section 412, subsection 412.04, is prohibited in colored concrete. It is the Contractor's responsibility to provide Quality Control for material density and strength testing and provide test results in a testing frequency, method and report as per Pre-construction submittal Quality Control Plan (QCP) that must be approved by the City Project Manager prior to starting work. Quality Control material testing, reports and submittals and unless provided for separately in this Contract will not be paid for separately but shall be included in the work.

The Quality Control Plan (QCP) is a required submittal that is Contract Specific and states how the process controls of materials, material testing, equipment, personnel and operations shall be maintained. As a minimum, the QCP shall include the following:

1. Project Contract Control Number and Name. Date of the NTP and subsequent close out date with respect to allotted calendar days.
2. The company name, personnel names and duties, telephone number(s), of all quality control personnel to be utilized from a certified lab including current copies of their certification letter.
3. Sub-grade compaction and concrete tests will be once weekly or additionally as needed

PWSTM Standard Concrete Construction Details & Technical Specifications

for Quality Control in critical conditions. Additional concrete tests are required for each instance High Early Strength Concrete is used.

4. Written test reports including all pertinent information in a form acceptable to the Project Manager. Test reports must be submitted in a timely fashion, as a minimum test reports must be submitted within 30 days of the test and acceptance of the related materials or product is contingent upon receipt of acceptable reports.

Subsection 608.03(a) shall be revised as follows:

Delete the third sentence and add:

Where excavation or fill to the finished grade elevation results in subgrade of unsuitable soil, the Project Manager or Project Inspector may designate the unsuitable material to be removed and replaced with approved material. Removal or reconditioning of unsuitable material, excavation and backfill with Class 6 Aggregate Base Course, in accordance with Revision of Section 203.05(c), or other material approved by the Project Manager shall not be paid separately but is included in the cost of the related concrete bid item. Excavation to proposed subgrade elevation will not be paid for separately but shall be included in the work associated with Section 201, Clearing and Grubbing or Section 202, Removal of Structures and Obstructions. Any forming and curb work to match existing surrounding landscaped or paved areas is included in the cost of the curb ramp and measured by the square yard of finished area.

Subsection 608.03(d) shall be revised to include the following:

Finishing shall occur only after the disappearance of bleed water. The addition of superficial water to the surface of the concrete to assist in finishing operations will not be permitted. Sprinkling of water or Con-film onto the freshly poured surface will not be permitted.

Subsection 608.03(e) shall be revised to include the following:

For Bikeways, control joints shall be zip-strip or saw cut to a minimum depth of  $\frac{1}{4}$  of the total slab thickness and no greater than  $\frac{1}{4}$  inch wide. Control joints shall be spaced at 10 feet on center or as noted on the plans. Any damage to the concrete such as spalling, dislodging of aggregate particles, or cracking will be repaired by the Contractor at no additional cost to the Project. If said damage cannot be adequately repaired to the satisfaction of the Project Manager, the Contractor shall remove and replace the damaged concrete at no additional cost to the Project.

Subsection 608.03(f) shall be revised to include the following:

The Contractor shall insure that new concrete items built under this contract drain properly and, as such, there are no areas of standing water on new concrete items.

The Contractor shall protect all new concrete items built under this Contract against defacement, or other injury, from any cause. If said damage cannot be adequately repaired to the satisfaction of the Project Manager, the Contractor shall remove and replace the unacceptable items at Contractor's expense.

Subsection 608.05 shall be revised to include the following:

Only Concrete Curb Ramp areas poured 6" thick that may include variable height curb as directed by the Project Inspector and are placed at a slope that meets minimum and maximum

slope requirements as per the latest revision of the City of Denver Transportation Standards and Details for the Engineering Division with respect to ADA accessibility standards shall be measured as Concrete Curb Ramp. Any variable height curb poured monolithically with the Concrete Curb Ramp will not be paid separately but shall be measured by the exposed square yard surface area and paid as Concrete Curb Ramp. The accepted quantities for “Concrete Sidewalk/Curb Ramp will be paid for at the contract unit price for each of the pay items listed below that appear in the Contract bid schedule. Payment shall be full compensation for all labor, equipment, time and materials for each unit bid item complete in place including saw cutting, scraping, sandblasting, removal, hauling and disposal of such items, excavation of subgrade material reconditioning or installation of aggregate base course and subsequent backfill, grading and compaction (with moisture/density control per the Revision of Subsection 203.07) to proposed subgrade elevation. The price shall also include salvageable materials removed, their custody, preservation, storage, hauling and disposal as provided herein.

When authorized for use by the Project Manager/Inspector the accepted quantities for “High Early Strength Concrete” and/or “Concrete Class D (Colored)” will be compensation only for the difference in concrete cost per cubic yard and extra labor per yard for all work performed using “High Early Strength Concrete” and will be measured by the cubic yard based on copies of the approved supplier’s concrete load tickets provided with a summary in tabular form with each Application for Payment.

Copies of all concrete tickets are required for concrete used during that pay period; a separate summary is required for the Quantity of High Early Strength Concrete and includes the ticket number, date and address where it was poured.

Saw-cut Expansion Joint only includes those areas where existing pavement must be cut for the sole purpose of installing an expansion joint. Payment shall be full compensation for "soft cutting" and tooling necessitated by City and County of Denver Noise Control Ordinance (D.R.M.C. Chapter 36), saw cutting hardened concrete, cleaning out the saw cut, expansion material and sealant.

All quantities to be submitted for payment must be measured in person by the Contractor with the Project Inspector and recorded by location in tabular form and summarized utilizing the Field Measurement Report (FMR), see FMR sample in APPENDICES at the end of the Technical Specifications, in manner acceptable to the Project Manager and be submitted for review and acceptance in advance of each pay application.

**PAY ITEM**

**PAY UNIT**

Concrete Sidewalk	SY
Concrete Curb Ramp	SY
Truncated Domes (Special Cast Iron) Material Only	SF

Payment shall be full compensation for labor and materials including, but not limited to, reconditioning, grading, backfill including topsoil and soil amendments, compaction, quality control material testing, curing compound, control and expansion joint and sealant as required to complete these Pay Items.

When the contract does not include pay items for FIBERMESH® or APPROVED EQUIVALENT

PWSTM Standard Concrete Construction Details & Technical Specifications

reinforcement additive, cure-sealer, curing compound, saw cut for construction, control or expansion joints, zip-strip and sealant will not be paid for separately but shall be included in the related concrete work.

**END OF REVISION OF SECTION 608**

## REVISION OF SECTION 609 CURB AND GUTTER

Section 609 of the Standard Specifications is hereby revised as follows:

All Concrete Gutter Overlay, Variable Height Curb Head with reinforcement, Curb and Gutter and Combination Curb, Gutter and Sidewalk shall additionally meet the requirements of the City of Denver Public Works Transportation Standards and Details for the Engineering Division. All concrete used shall be Portland Cement Concrete Pavement and shall be a minimum 4500 psi mix with 5% maximum fly ash and shall be reinforced with polypropylene fibers. Polypropylene fibers shall be FIBERMESH® or APPROVED EQUIVALENT. Length of fibers shall be as recommended by the manufacturer. Add 1.5 pounds FIBERMESH® or APPROVED EQUIVALENT per cubic yard of concrete.

Subsection 609.01 shall be revised to include the following:

Concrete Gutter Overlay  
Variable Height Curb with Reinforcement  
Curb and Gutter  
Combination Curb, Gutter and Sidewalk

Subsection 609.02 shall be revised as follows:

Reference to Section 703.07, Bed Course Material, shall be deleted.  
Additionally, Joint Filler must be approved by the Project Manager.  
Reference to Class B concrete shall be deleted and replaced with the following:  
Concrete shall conform to the requirements for Class "P" concrete as specified in subsections 601.02 and 601.03. When curb machines are used, the Contractor will be permitted to use AASHTO M 43 Size 57 or 67 aggregate in lieu of the coarse aggregate specified in Table 601-1, and a lesser slump will be permitted.

It is the Contractor's responsibility to provide Quality Control for material density and strength testing and provide test results in a testing frequency, method and report as per Pre-construction submittal Quality Control Plan (QCP) that must be approved by the City Project Manager prior to starting work. Quality Control material testing, reports and submittals will not be paid for separately but shall be included in the work.

The Quality Control Plan (QCP) is a required submittal that is Contract Specific and states how the process controls of materials, material testing, equipment, personnel and operations shall be maintained. As a minimum, the QCP shall include the following:

1. Project Contract Control Number and Name. Date of the NTP and subsequent close out date with respect to allotted calendar days.
2. The company name, personnel names and duties, telephone number(s), of all quality control personnel to be utilized from a certified lab including current copies of their certification letter.
3. Sub-grade compaction and concrete tests will be once weekly or additionally as needed for Quality Control in critical conditions. Additional concrete tests are required for each

PWSTM Standard Concrete Construction Details & Technical Specifications

instance High Early Strength Concrete is used.

4. Written test reports including all pertinent information in a form acceptable to the Project Manager. Test reports must be submitted in a timely fashion, as a minimum test reports must be submitted within 30 days of the test and acceptance of the related materials or product is contingent upon receipt of acceptable reports.

Subsection 609.03(a) shall be revised as follows:

Where excavation or fill to the finished grade elevation results in subgrade of unsuitable soil, the Project Manager or Project Inspector may designate the unsuitable material to be removed and replaced with approved material. Removal or reconditioning of unsuitable material, excavation and backfill with Class 6 Aggregate Base Course, in accordance with Revision of Section 203.05(c), or other material approved by the Project Manager shall not be paid separately but is included in the cost of the related concrete bid item.

Subsection 609.03(c) shall be revised to include the following:

The Contractor shall protect all new concrete items built under this Contract against defacement, or other injury, from any cause. If said damage cannot be adequately repaired to the satisfaction of the Project Manager, the Contractor shall remove and replace the unacceptable items at Contractor's expense.

Subsection 609.03(d) shall be revised to include the following:

For construction of curb and gutter adjacent to existing concrete pavement, the joint pattern shall match that of the concrete pavement. The joint pattern shall be approved by the Project Manager prior to construction.

Subsection 609.03(i) shall be revised to include the following:

The Contractor shall insure that new concrete items built under this contract drain properly and, as a condition of acceptance for payment, there shall be no areas of standing water on new concrete items.

Subsection 609.04 shall be revised to include the following:

Variable Height Curb with Reinforcement shall be used only at the request of the Project Manager and shall reference City of Denver Public Works Transportation Standards and Details STD. DWG. NO. 10.4 For Alley Curb Head.

Subsection 609.06 shall be revised to include the following:

All quantities to be submitted for payment must be measured in person by the Contractor with the Project Inspector and recorded by location in tabular form and summarized utilizing the Field Measurement Report (FMR), see FMR sample in APPENDICES at the end of the Technical Specifications, in manner acceptable to the Project Manager and be submitted for review and acceptance in advance of each pay application.

Subsection 609.07 shall be revised to include the following:

The accepted quantities for Concrete Gutter Overlay, Curb & Gutter Type ( ), Section ( ' ") and Combination Curb, Gutter and Sidewalk ( ' "), Median Cover (6" Patterned Colored Concrete) will



be paid for at the contract unit price for each of the pay items listed below that appear in the Contract bid schedule. Payment shall be full compensation for all labor, equipment, time and materials for each unit bid item complete in place including saw cutting, scraping, sandblasting, removal, hauling and disposal of such items, excavation of subgrade material reconditioning or installation of aggregate base course and subsequent backfill, grading and compaction (with moisture/density control per the Revision of Subsection 203.07) to proposed subgrade elevation. The price shall also include salvageable materials removed, their custody, preservation, storage, hauling and disposal as provided herein.

When authorized for use by the Project Manager/Inspector the accepted quantities for "High Early Strength Concrete" and "Concrete Class D (Colored)" will be compensation only for the difference in concrete cost per cubic yard and labor per yard for all work performed using High Early Strength Concrete and will be measured by the cubic yard based on copies of the approved supplier's concrete load tickets provided with a summary in tabular form with each Application for Payment.

Copies of all concrete tickets are required for concrete used during that pay period; a separate summary is required for the Quantity of High Early Strength Concrete and includes the ticket number, date and address where it was poured.

<b><u>PAY ITEM</u></b>	<b><u>PAY UNIT</u></b>
Concrete Gutter Overlay	LF
Curb & Gutter, Type ( ), (Section ' ")	LF
Combination Curb, Gutter and Sidewalk ( '___")	LF
Median Cover Material (6" Patterned Colored Concrete)	SY

Payment shall be full compensation for labor and materials including, but not limited to, reconditioning, grading, backfill including topsoil and soil amendments, compaction, quality control material testing, curing compound, control and expansion joint and sealant as required to complete these Pay Items.

When the contract does not include pay items for FIBERMESH® or APPROVED EQUIVALENT reinforcement additive, cure-sealer, curing compound, saw cut for construction, control or expansion joints and sealant will not be paid for separately but shall be included in the related concrete work.

Saw-cut Expansion Joint only includes those areas where existing pavement must be cut for the sole purpose of installing an expansion joint. Payment shall be full compensation for "soft cutting" and tooling necessitated by City and County of Denver Noise Control Ordinance (D.R.M.C. Chapter 36), saw cutting hardened concrete, cleaning out the saw cut, expansion material and sealant.

Excavation to proposed sub-grade elevation will not be paid for separately but shall be included in the related curb & gutter.

**END OF REVISION OF SECTION 609**

**REVISION OF SECTION 613  
LIGHTING**

Subsection 613.12 is revised to include the following:

All quantities to be submitted for payment must be measured in person by the Contractor with the Project Inspector and recorded by location in tabular form and summarized utilizing the Field Measurement Report (FMR), see FMR sample in APPENDICES at the end of the Technical Specifications, in manner acceptable to the Project Manager and be submitted for review and acceptance in advance of each pay application.

**PAY ITEM**

**PAY UNIT**

Loop Detector Wire

LF

When the contract does not include pay items for Lighting, this item will not be paid for separately but shall be included in the work.

**END OF REVISION OF SECTION 613**

**REVISION OF SECTION 614  
TRAFFIC CONTROL DEVICES**

Subsection 613.12 is revised to include the following:

All quantities to be submitted for payment must be measured in person by the Contractor with the Project Inspector and recorded by location in tabular form and summarized utilizing the Field Measurement Report (FMR), see FMR sample in APPENDICES at the end of the Technical Specifications, in manner acceptable to the Project Manager and be submitted for review and acceptance in advance of each pay application.

<u>PAY ITEM</u>	<u>PAY UNIT</u>
Reset Pull Box	EA

When the contract does not include pay items for Traffic Control Devices, this item will not be paid for separately but shall be included in the work.

**END OF REVISION OF SECTION 614**

## **REVISION OF SECTION 623 IRRIGATION SYSTEM**

Section 623 of the Standard Specifications is revised as follows: Subsection

623.01 is revised to include the following:

Irrigation systems within twelve inches (12") of the reconstruction areas which are damaged as a result of the reconstruction activity will be repaired and paid for. Irrigation systems beyond this limit which are damaged by the Contractor will be repaired by the Contractor at no expense to the City.

Subsection 623.02 is revised to include the following:

Materials required to be replaced shall be of like kind to those removed. If like kind materials are unavailable, the Contractor may substitute comparable materials of comparable quality, if approved by the Project Manager.

Materials used in areas under the jurisdiction of the City and County of Denver Parks and Recreation Department shall comply with the current specifications of that department.

Subsection 623.28 is revised to include the following:

Pipes and fittings will be measured by the lineal foot, regardless of type, size or manufacturer and shall be paid under "Sprinkler System – Irrigation Reconstruction."

New Sprinkler heads will be measured per each, regardless of type, size or manufacturer, and shall be paid under "Sprinkler System – Sprinkler Head."

Sprinkler heads to be adjusted will be measured per each regardless of type, size or manufacturer, and shall be paid under "Sprinkler System – Adjust Sprinkler Head."

PVC sleeves are required to be placed under new concrete as needed for current or future use and will be measured by the lineal foot, regardless of type, size or manufacturer and shall be paid under "Sprinkler System – Irrigation Reconstruction."

Subsection 623.32 is revised to include the following:

All quantities to be submitted for payment must be measured in person by the Contractor with the Project Inspector and recorded by location in tabular form and summarized utilizing the Field Measurement Report (FMR), see FMR sample in APPENDICES at the end of the Technical Specifications, in a manner acceptable to the Project Manager and be submitted for review and acceptance in advance of each pay application.

**PAY ITEM**

**PAY UNIT**

Sprinkler System – New Sprinkler Head	EA
Sprinkler System – Adjust Sprinkler Head	EA
Sprinkler System – Irrigation Reconstruction	LF

When the contract does not include pay items for Irrigation System, this item will not be paid for separately but shall be included in the work.

**END OF REVISION OF SECTION 623**

**REVISION OF SECTION 625  
CONSTRUCTION SURVEYING**

Section 625 of the Standard Specifications is hereby clarified with the following:

The Contractor shall furnish all equipment, materials and qualified personnel/labor as needed for construction staking and to establish lines and grades as necessary to complete the work and ensure drainage.

When the contract does not include pay items for Construction Surveying, this item will not be paid for separately but shall be included in the work.

**END OF REVISION OF SECTION 625**

**REVISION OF SECTION 626  
MOBILIZATION**

Section 626 of the Standard Specifications is revised as follows:

Section 626.01 shall be revised to including the following:

Prior to starting work the Contractor's staff including superintendents, foreman, lead workers, TCS, ECS, concrete lead-workers and sub-contractors shall attend a 2 hour preconstruction meeting that will include ADA ramp construction training and forum to coordinate, identify and discuss operating procedures regarding sensitive contract issues. The Contractor's TCS and designated lead worker may also be required to attend meetings specific to areas sensitive to the MHT including the Central Business District (Downtown between Broadway to Speer Boulevards from Colfax Avenue to I-25) and major arterial lane closures (Downtown Construction Coordination Meetings). The list of work locations for this project is not included within this Contract document. A sample of the "Potential Work Locations Map" is included in the APPENDICES at the end of the Technical Specifications. The scope of work with the locations will be assigned utilizing the "Work Initiation Form" by a location or groups of locations after the Notice to Proceed. Work assignments may be requested in these "Potential Work Locations" or other requested locations where spot repairs are needed utilizing the Work Initiation Form by the Project Manager. Concrete repair locations are citywide and generated through complaints or follow the City of Denver's current and projected Annual Street Paving Program with the focus on building curb ramps. There is no guarantee that all the locations assigned will be done under the Contract or that the locations will be done in any priority order. The Project Manager may revise, add or delete locations for which the Contractor will arrange Blue Stake locates; City of Denver Right-of-Way and Denver Parks permits and coordinate notification with all affected municipal, utility and property owner and provide on a weekly basis a three-week work schedule in advance to the Project Manager for approval prior to performing the work for each and all the assigned work locations. The Contractor shall normally not schedule work on Saturdays, Sundays, City of Denver observed Holidays or City of Denver furlough days. The Contractor must submit in writing requests to work longer than normal work hours (8 hours per day and 40 hours per week) or on Holidays or weekends the written request must be submitted to and approved by the Project Manager 48 hours in advance of the scheduled work.

Section 626.02 of the Standard Specifications is hereby revised as follows:

Payment for mobilization will be made if directed by Project Manager to mobilize outside of a quarter-section before 20 cubic yards of concrete is placed.

Meeting attendance by the contractor's personnel shall not be measured and paid for separately but shall be included in the price of the work.

**END OF REVISION OF SECTION 626**

**REVISION OF SECTION 627  
PAVEMENT MARKING**

Section 627 of the Standard Specifications is revised as follows:

Subsection 627.01 is revised to include the following:

The Contractor is responsible for installation and removal of temporary pavement marking. The Contractor shall coordinate the work of the striping Contractor, including traffic control devices and flaggers.

Subsection 627.03 is revised to include the following:

The Contractor shall replace permanent pavement markings damaged or removed as a result of the work. Pavement marking material shall be new material of the same type which existed prior to the work commencing.

Subsection 627.12 is revised as follows:

Installation and removal of temporary pavement marking will not be measured and paid for separately, but shall be included in the cost of item 412.

Permanent paving marking will not be measured and paid for separately, but shall be included in the cost of the related asphalt or Concrete Street paving bid item.

**END OF REVISION OF SECTION 627**



**REVISION OF SECTION 630  
CONSTRUCTION ZONE TRAFFIC CONTROL**

Section 630 of the Standard Specifications is hereby revised as follows:

Subsection 630.01 shall be modified to read:

...as required by, these plans and special specifications, conform to the Manual on Uniform Traffic Control Devices for Streets and Highways.

Subsection 630.02 through 630.08 shall be as provided in the MUTCD, latest edition. In addition, the following shall apply:

Traffic Control. Traffic control through the construction area is the responsibility of the Contractor. Before starting construction, the Contractor shall submit, in writing, the proposed Method of Handling Traffic (MHT) for the initial phase of construction. When a different MHT is required for a subsequent construction phase, it must be submitted two weeks prior to starting that phase. All proposed MHTs shall be approved, in writing, by the Project Manager. No phase of construction shall start until an acceptable MHT has been received and approved by the Project Manager. The proposed methods shall include, as a minimum, the following:

A detailed diagram that shows the location of all sign placements, including advance construction signs (if not previously approved) and speed limit signs; method, length and time duration for lane closures; and location of flag persons.

Certain traffic control devices may be used for more than one operation or phase.

Number of hours for uniformed traffic control shall be tabulated for submittal.

Approval of the proposed MHT is intended to indicate those devices for which payment is to be made. Such approval does not relieve the Contractor of liability specifically assigned to him under the contract. The Contractor shall erect and maintain warning lights, signs, barricades, and sufficient safeguards around all excavations, embankments, and obstructions.

Non-metallic drums may be substituted for vertical panel channelizing devices.

The Contractor shall, at the preconstruction conference, designate one of his employees, other than the Superintendent, to be responsible for traffic control management. This responsibility shall include management of the Contractor's signing and all other details covered by the Specifications which contribute to the convenience, safety, and orderly movement of traffic and to the comfort of the traveling public. The designated employee will have the Certification of the Traffic Control Supervisor as a Worksite Traffic Supervisor by the American Traffic Safety Services Association (ATSSA) in lieu of completion of the CDOT minimum training requirements.

PWSTM Standard Concrete Construction Details & Technical Specifications

Traffic control management shall be maintained on a 24-hour per day basis. The Contractor shall make arrangements so that the Traffic Control Supervisor or his approved representative will be available on every working day, "on call" at all times and available upon the Project Manager's request at other than normal working hours. The Traffic Control Supervisor shall have an up-to-date copy of part VI of the MUTCD, pertaining to traffic controls for street and highway construction, as well as the City and County Traffic Barricade manual, available at all times.

The flagger's STOP/SLOW sign paddle shall be 18 inches with letters six inches high.

Subsections 630.09 through 630.14 of the Standard Specifications shall apply except as otherwise provided herein.

Subsection 630.09 (4) shall be revised to include the following:

Access to driveways shall be maintained at all times during construction. The Contractor shall coordinate driveway work with the property owner.

The amount paid per day shall not exceed one unit of Traffic Control for an Arterial, one unit of traffic control for Local/Collector and includes all materials, equipment, personnel and traffic controls plans to conform to all Rules & Regulations for any Street Occupancy Request required to complete the assigned work by the City of Denver, adjacent municipalities and CDOT.

Subsection 630.15 shall be revised to include the following:

When the contract bid schedule includes Traffic Control pay items as a lump sum per day:

The PAY UNIT: LS/DAY for Traffic Control Arterial/Collector and Traffic Control Local shall be defined for the purposes of this Contract only include a work day when the Contractor is on-site completing some phase of the assigned repair work from 12:00 midnight to 12:00 midnight, furthermore weekends, City Holidays, City furlough days and days the Contractor is not on-site completing work other than Traffic Control are not included in this Pay Item. Traffic Control devices will not be measured but will be paid for on a lump sum basis. For a complete road closure in a residential street for a crossspan removal and repair the traffic control shall be paid as 1 LS/DAY of Traffic Control Arterial/Collector for that application for the entire duration at that location that shall include set-up, maintenance and take down for as many days needed to complete work at that location.

Payment for traffic control shall be as follows:

<b><u>PAY ITEM</u></b>	<b><u>PAY UNIT</u></b>
Traffic Control Arterial/Collector*	LS/DAY
Traffic Control Local*	LS/DAY
Uniformed Traffic Control Officer	HOUR

\* - The designation of which roads are Arterial/Collector and which roads are Local and shall be determined by the City's Right of Way Permitting Department. Arterials and collector streets generally

have center line striping.

When the contract bid schedule does not include pay items for Traffic Control; Payment for all Traffic Control shall be included in the work.

**END OF REVISION OF SECTION 630**

**REVISION OF SECTION 631  
PUBLIC INFORMATION SERVICES**

**DESCRIPTION**

631.01 The work consists of providing various public involvement activities for the project.

**REQUIREMENTS**

631.02 The Contractor shall provide the following public information services on an ongoing basis throughout the duration of the project:

631.02.1 A contact person and phone number for the project shall be designated by the Contractor at the pre-construction meeting. This individual shall be primarily responsible for maintaining communications with the Project Manager and affected businesses and property owners.

631.02.2 The Contractor will also distribute door hang tags to all property owners adjacent to construction and also all residences and businesses impacted by construction or road closures or detours no less than 48 hours (as per General Contract Conditions Section 703) prior to commencing removal operations, outlining the proposed work as well as the company name, phone number, and contact person familiar with the project. The hang tag wording shall be supplied by the City and it shall be the Contractor's responsibility to print an adequate number of hang tags one week in advance to properly notify all affected property owners/residents. Occasionally as needed supplemental written notices will be required to be delivered one week in advance at the direction of the Project Manager for issues such as construction conflicts related to business access, special landscape, and fence or tree removal. The cost of delivering the door hang tags and any other letter or notice to the public shall not be paid for separately, it is included in the related work.

631.02.3 The Contractor shall maintain a written log detailing the time, date, name, contact information, location, nature of the call or complaint and resolution (if needed) regarding any and all contacts from constituents. The Contractor will revise and submit a current copy of this log with each Application for Payment.

**METHOD OF MEASUREMENT**

631.03 Public information services will not be measured and paid for separately, but shall be included in the work.

**END OF SECTION 631**

**REVISION OF SECTION 705  
JOINT, WATERPROOFING AND BEARING MATERIALS**

Section 705 of the Standard specifications is hereby revised for this project as follows:

Subsection 705.01(a) shall be revised to include the following:

Sealant shall be heated only for the time limit recommended by the manufacturer. Also, the sealant shall not be reheated more times than recommended by the manufacturer.

Subsection 705.01 shall be revised to include the following:

*(c) Hot Joint Sealants, Concrete Pavement.* Hot-poured joint sealer material for concrete slab joints shall conform to the requirements of ASTM D 1190 or ASTM D 3405 and to the following:

Mortar blocks for the bond test shall be as described in ASTM D 1191

Coal tar base material is not acceptable.

The shipping containers shall be marked by the manufacturer with the name of the material, the name and brand of the manufacturer, the weight, the batch number and the safe heating temperature.

The materials shall be stored in accordance with manufacturer's recommendations, but they shall not be exposed to ambient temperatures in excess of 125 degrees F, or stored in direct sunlight.

The sealer material shall be melted in a heating kettle, or tank, constructed as a double boiler, with a space between the inner and outer shells filled with oil, asphalt, or other material for heat transfer and for positive temperature control.

The heating and melting unit shall be equipped so that the heat may be adjusted to provide control of the temperature of the heating medium used for melting the sealer material. The sealer material shall not be subjected to temperatures in excess of 450 degrees F at any stage or time during the melting operation.

When the contract bid schedule does not include pay items for Joint, Waterproofing and Bearing Materials; Payment for all Joint, Waterproofing and Bearing Materials shall be included in the work.

**END OF REVISION OF SECTION 705**

PWSTM Standard Concrete Construction Details & Technical Specifications

**REVISION OF SECTION 711  
CONCRETE CURING MATERIALS AND ADMIXTURES**

711.01 Concrete Curing Materials shall be modified; Liquid Membrane-Forming Compounds for Curing Concrete AASHTO M148, TYPE curing compound is deleted and shall additionally require:

For all Portland Cement Concrete Pavement placed on this project a combination cure-sealer shall be used that meets or exceeds ASTM-1315 Type I, Class A (clear, non-yellowing). The compound must be an acrylic copolymer type, non-freezing solvent based, with a minimum of 25% solids content. Compound must be VOC compliant in accordance with EPA 40 CFR Part 59. The final gloss appearance will serve as proof of application.

The Contractor shall use the cure-sealer according to the manufacturers recommendations so that when applied it will not adversely affect the skid resistance of the pavement.

The Contract does not include separate pay items for Concrete Curing Materials; these items will not be paid for separately but shall be included in the work.


**END OF REVISION OF SECTION 711**

2018 Citywide ADA Ramp and Concrete Repair

**APPENDICES**


- |  |       |
|--|-------|
| A. Potential Work Location Maps          | TS-74 |
| B. Field Measurement Report (FMR) Sample | TS-76 |
| C. Annotated Revisions                   | TS-74 |

# A. 2018 POTENTIAL WORK LOCATION MAPS





# 2018 Spot Repairs



## B. Field Measurement Report (FMR) Sample

Contract Control #	Map Name:	Page 1	Pay App #:	Date:																		
Street Name:	N/S/E/W:		Street From:	Street To:																		
Item Description	Pay Item	UNIT											TOTAL									
REMOVAL OF INLET	202-00019	EA																			0.00	
REMOVAL OF SIPHON	202-00033	EA																			0.00	
REMOVAL OF SIDEWALK	202-00200	W	20.0	3.3	4.5	61.0															20.78	
		L	1.5	3.8	5.0	2.0																
		SY	3.33	1.39	2.50	13.56																
		W																				
		L																				
		SY																				
REMOVAL OF CURBHEAD	202-00201	LF																			0.00	
REMOVAL OF CURB AND GUTTER	202-00203	LF		111.0	221.0	91.0	98.5	113.5	108.0												743.00	
REMOVAL OF COMBINATION CURB, GUTTER AND WALK	202-00204	LF																			0.00	
REMOVAL AND RESET FLAGSTONE (INCLUDES SALVAGE AND STORAGE)	202-00208	W																			0.00	
		L																				
		SY																				
		W																				
		L																				
		SY																				
REMOVAL OF CONCRETE PAVEMENT	202-00210	W	16.7	22.7	17.3	21.5	8.8	24.0													143.43	
		L	5.3	14.0	5.0	14.0	18.3	14.0														
		SY	9.83	35.31	9.61	33.44	17.89	37.33														
		W																				
		L																				
		SY																				
REMOVAL OF ASPHALT MAT	202-00220	W	236.0	221.0	213.0	251.0															204.67	
		L	2.0	2.0	2.0	2.0																
		SY	52.44	49.11	47.33	55.78																
		W																				
		L																				
		SY																				
REMOVAL OF FENCE	202-01000	LF																			0.00	
TRIP HAZARD SAWING (<= 5 LOCATIONS 1 WEEK COMPLETION)	202-05020	W																			0.00	
		D																				
		IN-FI																				
		W																				
		L																				
		IN-FI																				
TRIP HAZARD SAWING (>5 LOCATIONS 1 MONTH COMPLETION)	202-05021	W																			0.00	
		D																				
		IN-FI																				
		W																				
		L																				
		IN-FI																				
UNCLASSIFIED EXCAVATION	203-00200	CY	Calculated automatically from SY totals of Concrete Curb Ramp (608-00100)																0.00			
Additional Unclassified Excavation	203-00200	W																			0.00	
		L																				
		D																				
	203-00200	CY																			0.00	
Total Unclassified Excavation		CY																				

## C. Annotated Revisions since last publication

### **Subsection 412.03 (November 2016)**

All Portland Cement Concrete Pavement used on this Contract shall be a minimum 4500 psi 28 day design with 5% maximum fly ash and shall be reinforced with polypropylene fibers

(November 2017)

All Portland Cement Concrete Pavement used on this Contract shall be a minimum 4500 psi 28 day design with 10 % maximum fly ash and shall be reinforced with polypropylene fibers

### **Subsection 626.02 (November 2016)**

Mobilization and meeting attendance by the contractor's personnel shall not be measured and paid for separately but shall be included in the price of the work.

(November 2017)

Payment for mobilization will be made if directed by Project Manager to mobilize outside of a quarter section before 20 cubic yards of concrete is placed.

Meeting attendance by the contractor's personnel shall not be measured and paid for separately but shall be included in the price of the work.