



47 South Limestone, Jamestown, OH 45335
 Phone: 937.675.9581 Fax: 937.675.3982
 dmaynard@twistinc.com www.twistinc.com

**45 TON HYDRONIC AIR HANDLERS (AHU) BID
 PROPOSAL 29010**

Quote Number: 191110
 Quote Revision: 00
 Date Quoted: 10/11/19

Quote Valid Through: 12/31/19
 Payment Terms: See Notes
 Quoted Lead Time: See Notes
 Agent:

Attachment A

Quoted To:

Denver International Airport

Quote Prepared By: Don Maynard
 Title: Sales Director



Project Description: AHU Air Handling Units and related accessories.

Attn: Steve Simpson

Project Location: Denver, Colorado

LINE	ITEM	DESCRIPTION/DETAILS	QUOTE QUANTITY	UNIT PRICE EACH	EXTENDED COST
001	AHU045480WH	45 Ton Hydronic Air Handling Unit. "C" Tunnel Bridge Mount. Design Features and Specifications: 1. Input power, 480VAC, 3PH, 60HZ, 60 AMPS. 2. Design Air Flow = 275 PPM 3. Static pressure at the end of the hose = 25 in. of H2O. 4. Unit is controlled by pushbutton start mode. 5. The unit is controlled by a DDC.. 6. Finish: RAL 9003 White. ACCESSORIES	16	\$52,750.00	\$844,000.00
002	PCA-MTKIT-114	Standard Mounting Brackets	16	\$989.00	\$15,824.00
003	PCA-HOSESTRAP	Hose Support Straps, 2 per outlet.	32	\$30.00	\$960.00
004	SH1483-03SS	J&B Superhose, 14" x 3' Starter Hose with Scuff Strip, Wire Reinforced. Entrance Cuff: Plain. Exit Cuff: Hook Velcro. One per outlet.	16	\$159.00	\$2,544.00
005	SH1483-10	J&B Superhose 10' x 14" Hose Section of Layflat, Spiral Wound, insulated. No Scuff Strip or wire. Entrance Cuff: Wing with Loop Velcro. Exit Cuff: Hook Velcro. One section per outlet.	16	\$345.00	\$5,520.00

006	SH1483-25	J&B Superhose 25' x 14" Hose Section of Layflat, Spiral Wound, insulated. No Scuff Strip or wire. Entrance Cuff:Wing with Loop Velcro. Exit Cuff: Hook Velcro. Two Sections per outlet.	32	\$516.00	\$16,512.00
007	JZ1410-01	14" x 8" Reducer with Scuff Strip and Wire Reinforced. Entrance Cuff:Wing with Loop Velcro. Exit Cuff: Hook Velcro. One per outlet.	16	\$258.00	\$4,128.00
008	JB729	8" Aircraft Coupler. One per outlet. Plus one extra per gate.	32	\$320.00	\$10,240.00
009	3 WHEEL HOSE TROLLY SYSTEM	2 Section, Heavy Duty, Stainless Steel, Single Hose Trolley System.	16	\$10,010.00	\$160,160.00
010	PCA-RB-200-RJ-NB	Stainless Steel Pushbutton Control Box.	16	\$871.00	\$13,936.00
011	PCA-RB-CABLE-075	75' of Control Cable.	16	\$375.00	\$6,000.00
012	PCA-TEMPPROBE	Temperature Probe	16	\$294.00	\$4,704.00
013	PCA-TEMPPROBE CABLE-075	75' Temperature Probe Cable.	16	\$115.00	\$1,840.00
014	PCA-BOXMT	Mounting Plate for Pushbutton Control Box.	16	\$182.00	\$2,912.00
015	MB GATEWAY	Ethernet/MOD BUS Conversion	16	\$350.00	\$5,600.00
016	316-02-22A30A	Extra Washable Filters 45 Ton AHU . Two per unit.	32	\$48.00	\$1,536.00
017	SPECIFICATION SPECIFIC OPTION	Honeywell Wireless Transmitters Connection.	16	\$4,175.00	\$66,800.00
018	AHU-045MAN	Operations & Maintenance Manuals. Hard Bound Copies \$225.00 Each.CDs provided at no cost.	1	\$225.00	\$225.00
MISCELLANEOUS EXPENSES					
019	COMMISSION	One person, 5 days total on site. One visit.. Quote includes labor, travel, hotel and meals.	1	\$7,040.00	\$7,040.00

020	STANDARD WARRANTY	12 Month Warranty. See Details in Quotation Notes.	16	\$0.00	\$0.00
021	EXTENDED WARRANTY	48 Month Additional Warranty. See Details in Quotation Notes.	16	\$4,833.00	\$77,328.00
022	BADGING	Customer to provide escort for commissioning.	0	\$6,450.00	\$0.00
023	ENGINEERING, PROJECT MANAGEMENT AND SITE VISIT	Engineering Support, Submittals, Project Management and Site Visit if necessary.	16	\$800.00	\$12,800.00
024	PACKAGING & CRATING	Packaging & Crating of unit.	16	\$350.00	\$5,600.00
025	SHIPPING	Shipping and Handling from Hose Trolley Manufacturer in Greenville, TX to Denver International Airport.	2	\$3,827.00	\$7,654.00
026	SHIPPING	Shipping and Handling from Jamestown, Ohio to Denver International Airport.	5	\$5,451.00 ✓	\$27,255.00

TOTAL QUOTED COST

\$1,301,118.00

QUOTATION NOTES:

- 1) Quoted pricing includes shipping from Jamestown, Ohio to Denver Intl. Airport, CO.
- 2) Quoted pricing based on standard one year warranty. Extended warranty to be covered separately.
- 4) Quotation based on PCA specifications supplied per bidding documents supplied for quoting purposes.
- 5) Quoted Pricing is based on US Dollars.
- 6) Quoted pricing is based on standard heat shrink packaging to protect against scratches during transit.
- 7) Quoted price includes units shipped on wooden pallet to access movement by lift truck.
- 8) Standard 12 month warranty details: Twist Inc. warrants that products supplied, will be free of defects in material and workmanship. In the event that a failure to comply with this warranty should be detected within twelve (12) months from the date of start-up, Twist Inc. shall, upon notification of non-compliance and after substantiation that the non-conformities are not due to tampering, misuse, or misapplication, rectify the problem by suitable repair or replacement F.O.B. factory.
- 9) Standard White Finish, RAL 9003. Other colors available but would result in upcharge and may increase lead time.
- 10) Submittal Lead Time: Two weeks ARO.
- 11) No Performance or Payment Bond is included in this quotation. If required, applicable cost must be added to quote.
- 12) No Sales Tax is included in this quotation. If required, applicable percentage would have to be added to quote.
- 13) Payment Terms: 30% down with order. Balance 30 days after equipment arrives on site.
- 14) Lead Time: Delivery Schedule to be determined ARO.
- 15) Twist's quote is based on responses provided per Addendums 1 and 2.
- 16) The Condensate shall drain to apron as specified.
17. Quote DOES NOT include Install, Pantographs, Power, Network or Interlock cables.