STAPLETON FILING NO. 50

A PART OF THE SOUTH HALF OF SECTION 26, TOWNSHIP 3 SOUTH, RANGE 67 WEST OF THE SIXTH PRINCIPAL MERIDIAN,

LEGAL DESCRIPTION:

Know all men by these presents that Park Creek Metropolitan District, a quasi-municipal corporation and political subdivision of the State of Colorado and FC Stapleton II, LLC, a Colorado Limited Liability Company as owners, have laid out, platted and subdivided into tracts as shown on this map, the land described as follows:

PARCEL 1:

A part of the Southwest Quarter of Section 26, Township 3 South, Range 67 West of the Sixth Principal Meridian, City and County of Denver, State of Colorado, more particularly described as follows:

COMMENCING at the South Quarter Corner of said Section 26;

R.O.W. for Martin Luther King, Jr. Blvd, said Stapleton Filing No. 15;

thence North 57°40'19" West a distance of 2693.66 feet to the northeast corner of Tract AC, Future R.O.W. for Iola St., Stapleton Filing No. 15 as recorded at Reception Number 2005107063 in the Clerk and

Recorder's Office of said City and County of Denver and the POINT OF BEGINNING:

thence parallel with the northerly line of Tract M, Stapleton Filing No. 16 as recorded at Reception Number 2012018815 in said Clerk and Recorder's Office the following two (2) courses: 1. South 90°00'00" East a distance of 46.36 feet to a point of curve;

2. along the arc of a curve to the right having a radius of 549.00 feet, a central angle of 26°44'23", an arc length of 256.22 feet and whose chord bears South 76°37'48" East a distance of 253.90 feet to the westerly line of Tract A. Future R.O.W. for Ironton St., said Stapleton Filing No. 16;

thence North 2816'03" East, along said westerly line of Tract A, Future R.O.W. for Ironton St., a distance of 73.62 feet to the southerly right-of-way line of Havana Way as described in Ordinance 127, Series of 1954 and recorded in Book 7504 at Page 176 in said Clerk and Recorder's Office: thence North 45°42'14" West, along said southerly right-of-way line of Havana Way as described in Ordinance 127, Series of 1954 and recorded in Book 7504 at Page 176, a distance of 351.38 feet to the most easterly corner of Tract AD. Future

thence along the easterly line of said Stapleton Filing No. 15 the following six (6) courses: 1. South 45'42'07" West a distance of 42.66 feet to the most southerly corner of said Tract AD, Future R.O.W. for Martin

- 2. North 44°17'53" West, along the southwesterly line of said Tract AD, Future R.O.W. for Martin Luther King, Jr. Blvd., a distance of 6.06 feet to the most easterly corner of Tract BB, Future R.O.W. for Iola St. and a point of non-tangent
- 3. along the arc of a curve to the left having a radius of 194.00 feet, a central angle of 41°37'30", an arc length of 140.94 feet and whose chord bears South 20°48'45" West a distance of 137.86 feet;
- 4. South 00°00'00" East a distance of 15.70 feet to the southeast corner of said Tract BB, Future R.O.W. for lola St. and a point on the northerly line of Tract J, Future R.O.W. for 29th Dr.;
- 5. South 90 00 00 East a distance of 7.00 feet to the northeast corner of said Tract J, Future R.O.W. for 29th Dr.; 6. South 00°00'00" East a distance of 81.50 feet to the **POINT OF BEGINNING**.

Containing 54,732 square feet or 1.256 acres, more or less.

A part of the Southwest Quarter of Section 26, Township 3 South, Range 67 West of the Sixth Principal Meridian, City and County of Denver, State of Colorado, more particularly described as follows:

COMMENCING at the South Quarter Corner of said Section 26;

thence North 53°36'11" West a distance of 2364.46 feet to the northeast corner of Tract A. Future R.O.W. for Ironton St., Stapleton Filing No. 16 as recorded at Reception Number 2012018815 in the Clerk and Recorder's Office of said City and County of Denver and a point on the southerly right-of-way line of Havana Way as described in Ordinance No. 127, Series of 1954 and recorded in Book 7504 at Page 176 in said Clerk and Recorder's Óffice and the POINT OF BEGINNING;

thence along said southerly right—of—way line of Havana Way as described in Ordinance No. 127, Series of 1954 and recorded in Book 7504 at Page 176 the following three (3) courses:

1. South 45°42'14" East a distance of 119.55 feet to a point of curve;

- 2. along the arc of a curve to the left having a radius of 1196.00 feet, a central angle of 50°24'41", an arc length of
- 1052.29 feet and whose chord bears South 70'54'34" East a distance of 1018.68 feet;
- North 83°53'05" East a distance of 31.92 feet to the northwest corner of Tract B, Future R.O.W. for Kingston St., Stapleton Filing No. 35 as recorded at Reception Number 2012065645 in said Clerk and Recorder's Office;

thence South 05°00'00" East, along the westerly line of said Tract B, Future R.O.W. for Kingston St., a distance of 50.01 feet to the northeast corner of Lot 11. Block 1, said Stapleton Filing No. 35:

thence along the northerly line of said Stapleton Filing No. 35 the following two (2) courses: 1. South 83.53.05" West a distance of 30.94 feet to a point of curve;

2. along the arc of a curve to the right having a radius of 1246.00 feet, a central angle of 48°33'30", an arc length of 1055.99 feet and whose chord bears North 71°50'10" West a distance of 1024.67 feet to the northeast corner of Tract N. said Stapleton Filing No. 16:

thence along the northerly line of said Stapleton Filing No. 16 the following three (3) courses:

- 1. along the arc of a curve to the right having a radius of 1246.00 feet, a central angle of 2°58'48", an arc length of 64.81 feet and whose chord bears North 46.04.01" West a distance of 64.80 feet to a point of reverse curve; 2. along the arc of a curve to the left having a radius of 400.00 feet, a central angle of 11°21'42", an arc length of 79.32 feet and whose chord bears North 50°15'28" West a distance of 79.19 feet to the northwest corner of Lot 1, Block 2,
- said Stapleton Filing No. 16 and a point on the easterly line of said Tract A, Future R.O.W. for Ironton St.; 3. North 2816'03" East, along said easterly line of said Tract A, Future R.O.W. for Ironton St., a distance of 58.31 feet to the **POINT OF BEGINNING**.

Containing 61,033 square feet or 1.401 acres, more or less.

A part of the Southwest Quarter of Section 26, Township 3 South, Range 67 West of the Sixth Principal Meridian, City and County of Denver, State of Colorado, more particularly described as follows:

COMMENCING at the South Quarter Corner of said Section 26;

thence North 37°09'32" West a distance of 1251.00 feet to the northeast corner of Tract B, Future R.O.W. for Kingston St., Stapleton Filing No. 35 as recorded at Reception Number 2012065645 in the Clerk and Recorder's Office of said City and County of Denver and a point on the southerly right—of—way line of Havana Way as

described in Ordinance No. 127, Series of 1954 and recorded in Book 7504 at Page 176 in said Clerk and Recorder's Office

and the **POINT OF BEGINNING**: thence along said southerly right-of-way line of Havana Way as described in Ordinance 127, Series of 1954 and recorded in

Book 7504 at Page 176 the following two (2) courses: 1. North 83°53'05" East a distance of 656.67 feet to a point of curve:

2. along the arc of a curve to the right having a radius of 624.10 feet, a central angle of 4.55.00", an arc length of 53.55 feet and whose chord bears North 86°20'35" East a distance of 53.54 feet to the northwest corner of Tract B. Future R.O.W. for Lima St., Stapleton Filing No. 40 as recorded at Reception Number 2013109191 in said Clerk and Recorder's Office;

thence along the northerly line of said Stapleton Filing No. 40 the following three (3) courses: 1. South 00°00'00" East, along the westerly line of said Tract B, Future R.O.W. for Lima St., a distance of 67.96 feet to the northeast corner of Lot 25, Block 1, said Stapleton Filing No. 40 and a point of non-tangent curve;


- 2. along the arc of a curve to the left having a radius of 1097.50 feet, a central angle of 10.55.07, an arc length of 209.14 feet and whose chord bears South 89°20'38" West a distance of 208.83 feet: 3. South 83°53'05" West a distance of 374.99 feet to the northeast corner of Tract U, said Stapleton Filing No. 35;

thence along the northerly line of said Stapleton Filing No. 35 the following two (2) courses: 1. South 83°53'05" West a distance of 121.02 feet to the northwest corner of Lot 1, Block 2, said Stapleton Filing No. 35 and a point on the easterly line of said Tract B, Future R.O.W. for Kingston St., said Stapleton Filing No. 35:

2. North 05°00'00" West, along said easterly line of Tract B, Future R.O.W. for Kingston St., a distance of 50.01 feet to the POINT OF BEGINNING.

Containing 36,762 square feet or 0.844 acres, more or less.

CITY AND COUNTY OF DENVER, STATE OF COLORADO



A part of the Southeast Quarter of Section 26, Township 3 South, Range 67 West of the Sixth Principal Meridian, City and County of Denver, State of Colorado, more particularly described as follows:

COMMENCING at the South Quarter Corner of said Section 26:

thence North 00°47'24" East a distance of 1068.52 feet to the northeast corner of Tract B, Future R.O.W. for Lima St., Stapleton Filing No. 40 as recorded at Reception Number 2013109191 in the Clerk and Recorder's Office of said City and County of Denver and a point on the southerly right—of—way line of Havana Way as described in Ordinance No. 127, Series of 1954 and recorded in Book 7504 at Page 176 in said Clerk and Recorder's Office and the **POINT OF BEGINNING**;

thence along said southerly right—of—way line of Havana Way as described in Ordinance 127, Series of 1954 and recorded in Book 7504 at Page 176 and along the arc of a curve to the right having a radius of 624.10 feet, a central angle of 47°30'13", an arc length of 517.44 feet and whose chord bears South 61°33'58" East a distance of 502.74 feet to the northeast corner of Lot 1. Block 2. said Stapleton Filing No. 40 and a point of non-tangent curve:

thence along the northerly line of said Stapleton Filing No. 40 the following two (2) courses: 1. along the arc of a curve to the left having a radius of 1097.50 feet, a central angle of 24°50'58", an arc length of

- 475.99 feet and whose chord bears North 69°24'33" West a distance of 472.27 feet to the northwest corner of Lot 2,
- 2. North 00°00'00" West, along the easterly line of said Tract B, Future R.O.W. for Lima St., a distance of 73.29 feet to the **POINT OF BEGINNING**.

Containing 25,961 square feet or 0.596 acres, more or less.

TOGETHER WITH PARCEL 5:

A part of the Southeast Quarter of Section 26. Township 3 South, Range 67 West of the Sixth Principal Meridian, City and County of Denver, State of Colorado, more particularly described as follows:

COMMENCING at the Southeast Corner of said Section 26; thence South 89'39'23" West, along the southerly line of said Southeast Quarter of Section 26, a distance of 60.00 feet to a point 60.00 feet westerly of the easterly line of said Southeast Quarter of Section 26 and the POINT OF BEGINNING:

thence South 89°39'23" West, along said southerly line of the Southeast Quarter of Section 26, a distance of 843.50 feet to a point of non-tangent curve that is 903.50 feet from said Southeast Corner of Section 26; thence along the arc of a curve to the right having a radius of 1224.00 feet, a central angle of 11°03'53", an arc length of 236.37 feet and whose chord bears North 62°27'02" West a distance of 236.01 feet; thence North 56°55'06" West a distance of 80.45 feet;

thence South 33°04'54" West a distance of 23.00 feet; thence North 56°55'06" West a distance of 76.00 feet; thence North 33°04'54" East a distance of 23.00 feet:

thence North 56°55'06" West a distance of 789.47 feet; thence South 33°04'54" West a distance of 52.57 feet to a point of curve;

thence along the arc of a curve to the left having a radius of 293.00 feet, a central angle of 19°04'48", an arc length of 97.57 feet and whose chord bears South 23°32'30" West a distance of 97.12 feet to the northeasterly right-of-way line of Havana Way as described in Ordinance 127, Series of 1954 and recorded in Book 7504 at Page 176 in the Clerk and

Recorder's Office of said City and County of Denver and a point of non-tangent curve: thence along said northeasterly right-of-way line of Havana Way as described in Ordinance 127. Series of 1954 and recorded in Book 7504 at Page 176 and along the arc of a curve to the left having a radius of 724.10 feet, a central angle of

39°43'49", an arc length of 502.11 feet and whose chord bears North 24°20'28" West a distance of 492.11 feet to a point of non-tangent curve; thence along the arc of a curve to the right having a radius of 1215.00 feet, a central angle of 02°10'43", an arc length of

46.20 feet and whose chord bears South 58'00'27" East a distance of 46.20 feet: thence South 56°55'06" East a distance of 257.27 feet;

thence North 33°04'54" East a distance of 7.25 feet: thence South 56°55'06" East a distance of 125.62 feet; thence South 33°04'54" West a distance of 7.25 feet;

thence South 56°55'06" East a distance of 740.69 feet; thence North 33°04'54" East a distance of 7.50 feet; thence South 56'55'06" East a distance of 125.43 feet;

thence South 33.04.54" West a distance of 7.50 feet to a point of non-tangent curve; thence along the arc of a curve to the left having a radius of 1182.50 feet, a central angle of 20°37'01", an arc length of

425.50 feet and whose chord bears South 67°13'36" East a distance of 423.21 feet; thence North 12°27'53" East a distance of 7.50 feet to a point of non-tangent curve; thence along an arc of a curve to the left having a radius of 1175.00 feet, a central angle of 05'48'12", an arc length of

119.01 feet and whose chord bears South 80°26'13" East a distance of 118.96 feet; thence South 06'39'41" West a distance of 7.50 feet to a point of non-tangent curve;

thence along an arc of a curve to the left having a radius of 1182.50 feet, a central angle of 6°39'41", an arc length of 137.48 feet and whose chord bears South 86°40'09" East a distance of 137.41 feet:

thence South 89°59'47" East a distance of 197.87 feet: thence North 83°20'58" East a distance of 21.70 feet;


thence North 90°00'00" East a distance of 147.19 feet; thence North 45°01'27" East a distance of 23.97 feet to a point 60.00 feet westerly of said easterly line of the Southeast

Quarter of Section 26: thence South 00°54'42" East, parallel with and 60.00 feet westerly of said easterly line of the Southeast Quarter of Section 26, a distance of 57.23 feet to the **POINT OF BEGINNING**.

Containing 225,800 square feet or 5.184 acres, more or less.

Resulting in a total area of 404,288 square feet or 9.281 acres, more or less.

Under the name and style of STAPLETON FILING NO. 50.



Clerk and Recorder

STAPLETON FILING NO. 50

A PART OF THE SOUTH HALF OF SECTION 26, TOWNSHIP 3 SOUTH, RANGE 67 WEST OF THE SIXTH PRINCIPAL MERIDIAN,
CITY AND COUNTY OF DENVER, STATE OF COLORADO
SHEET 2 OF 6

NOTES:

- 1. Notice: According to Colorado law you must commence any legal action based upon any defect in this survey within three years after you first discover such defect. In no event, may any action based upon any defect in this survey be commenced more than ten years from the date of certification shown hereon.
- 2. BASIS OF BEARING: Bearings are based on the southerly line of the Southeast Quarter of Section 26, Township 3 South, Range 67 West of the Sixth Principal Meridian, City and County of Denver, State of Colorado, bearing North 89°39'23" East based on NAD 83/92 Colorado Central Zone State Plane Coordinates. The South Quarter corner of said Section 26 is a found 3—1/4" aluminum cap in a monument box Stamped: URS CORP PLS 20683. The Southeast corner of said Section 26 is a found 3" brass cap in a monument box Stamped: City of Aurora 16419.
- 3. BENCHMARK: NGS 320B: Found City and County of Denver (CCD) brass cap on the northwest corner of the intersection of Central Park Blvd. and Montview Blvd. in turn island, 2.4' west of west flowline, 18.6' north of north flowline. Elevation = 5322.50' (NGS Data Sheet) NAVD 88. A temporary site benchmark is marked by a 1.5" Aluminum Cap on the intersection of Havana Way and Moline St. Elevation = 5346.83 NAVD 88.
- 4. Any person who knowingly removes, alters or defaces any public land survey monument or land monument or accessory, commits a class two (2) misdemeanor pursuant to C.R.S. 18-4-508.
- 5. All dimensions shown hereon are in U.S. Survey Feet. All bearings shown hereon are in Degrees-Minutes-Seconds.
- 6. FLOOD ZONE DESIGNATION: By scaled map location, according to the Flood Insurance Rate Map, Map Number 0800460113H, Map Revised: November 20, 2013. No field surveying was performed to determine this zone.
- Zone X, other areas; areas determined to be outside the 0.2% annual chance floodplain;
- 7. STATE PLANE COORDINATES: The Colorado State Plane Coordinates, Central Zone, NAD83/92 in feet, for the indicated section Corners are:

| SECTION CORNER | NORTHING | EASTING |
|---|-------------|-------------------------|
| SW Corner Sec. 26, T. 3 S., R. 67 W., 6th P.M. | 1700419.024 | 3178318 .030 |
| S 1/4 Corner Sec. 26, T. 3 S., R. 67 W., 6th P.M. | 1700432.396 | 3180978.546 |
| SE Corner Sec. 26, T. 3 S., R. 67 W., 6th P.M. | 1700448.338 | 3183636.372 |
| Center of Sec. 26, T. 3 S., R. 67 W., 6th P.M. | 1703081.515 | 3180946.738 |


- 8. There are 6 Tracts in Stapleton Filing No. 50.
- 9. The responsibility for infrastructure development described on this plat is set forth in the Master Facilities Development Agreement ("MFDA"), among the Park Creek Metropolitan District, Forest City Enterprises, Inc., and the City and County of Denver, on file with the Denver City Clerk in file No. 01—124. The infrastructure is to be constructed by Forest City Stapleton, Inc. and/or Park Creek Metropolitan District in accordance with any Individual Facilities Development Agreement ("IFDA") executed for Stapleton Filing No. 50.
- 10. Tracts A, B, C, D, E and F are for future rights—of—way and associated infrastructure therein and shall be owned and maintained by the Park Creek Metropolitan District until such rights—of—way are conveyed and accepted by the City and County of Denver.
- 11. Access rights necessary for the installation and maintenance of electric, telephone, gas, cable television, and postal facilities, or for facilities to be constructed on behalf of the Metro Wastewater Reclamation District or the Denver Water Board, within future rights—of—way prior to dedication shall be licensed by the Owner.
- 12. Certain infrastructure to support the development described in this plat will be constructed outside the plat boundaries. Off—plat easements and/or licenses for such infrastructure will be provided, as needed, by separate document.
- 13. Easements for utility appurtenances (e.g. transformers and switch cabinets) and edsements for electric, telephone, gas, cable television and postal facilities outside future public rights—of—way are to be conveyed by separate document.
- 14. A right of access for emergency services is hereby granted on and across all areas for police, fire, medical and other emergency vehicles and for the provision of emergency services.
- 15. An access easement for municipal services provided by the City and County of Denver is hereby granted on and across all private streets and alleys for the provision of such City services.
- 16. Martin Luther King, Jr. Blvd. (MLK) is an urban arterial with a forecast average daily traffic (ADT) volume of approximately 28,000 vehicles in 2040. Per analysis using Colorado Department of Transportation (CDOT) Noise Abatement Criteria, the 66 decibel (dBA) limit for the noise generated by this traffic will extend approximately 140 feet south of the southern limit of the east bound travel lane between Moline St. and Peoria St. and will extend outside the MLK right—of—way as shown on the Stapleton Filing No. 50 Plat. Owners, builders and buyers of property adjacent to the roadway are hereby made aware of this exterior noise condition. Any noise mitigation measures are at the discretion of the future property owners.

NOTES (CONTINUED):

- 17. This survey does not constitute a title search by AECOM to determine title or easements of record. Title Commitment Number No. NCS-771926-CO having an Effective Date of October 20, 2017 at 5:00 P.M. prepared by First American Title Insurance was relied upon for all information regarding easements of record, rights-of-way, title of record and civil court actions of record.
- 18. The land described herein lies within or partially within the legal description or exhibits found in the following recorded instruments as set forth in the above referenced Title Commitment and may therefore be subject to the terms, provisions, covenants, conditions, restrictions, obligations and reservations contained therein.


| DE | SCRIPTION | DECEDTION NO |
|-------------|---|---------------|
| A | Stapleton Development Plan — South Area | RECEPTION NO. |
| B | Community Declaration | 2001043010 |
| - C | -First Amended | 2001167472 |
| | -First Amended -First Amendment to the First Amended | 2002086362 |
| | -First Amendment to the First Amended | 2005217062 |
| | | 2007003744 |
| | -Supplemental Declaration | 2007022702 |
| | -Supplemental Declaration | 2005016990 |
| | -Supplemental Declaration | 2012001704 |
| | -Supplemental Declaration | 2012030553 |
| | -Supplemental Declaration | 2013037636 |
| - | -Supplemental Declaration | 2013038285 |
| | -Supplemental Declaration | 2016130305 |
| <u>C</u> | Deed CCD to SDC | 2005016984 |
| ļ | -Quit Claim Deed | 2005016985 |
| | -Quit Claim Deed | 2005016988 |
| | -Quit Claim Deed | 2005016992 |
| <u>D</u> | Amended and Restated Design and Architectural Declaration | 2005016986 |
| E | Recordation of Development Agreement | 2005016989 |
| F | Subject property in the Westerly Creek Metropolitan District | 2005060273 |
| G | Deed CCD-SDC | 2012001605 |
| | —Quit Claim Deed | 2012001606 |
| | —Quit Claim Deed | 2012001702 |
| | —Quit Claim Deed | 2012001706 |
| H | Amended and Restated Design and Architectural Declaration | 2002249150 |
| | | 2012001607 |
| | Recordation of Development Agreement | 2004176011 |
| | | 2012001703 |
| J | Inclusion of subject property in the Westerly Creek Metropolitan District | 2012044241 |
| K | Deed CCD-SDC | 2012030480 |
| | -Quit Claim Deed | 2012030481 |
| | -Quit Claim Deed | 2012030551 |
| | -Quit Claim Deed | 2012030555 |
| L | Amended and Restated Design and Architectural Declaration | 2002249150 |
| | | 2012030482 |
| М | Recordation of Development Agreement | 2004176011 |
| | -Agreement | 2012030552 |
| N | Subject property in the Westerly Creek Metropolitan District | 2012068872 |
| 0 | Deed | 2013037630 |
| | —Quit Claim Deed | 2013037631 |
| | -Quit Claim Deed | 2013037634 |
| | -Quit Claim Deed | 2013037638 |
| Р | Amended and Restated Design and Architectural Declaration | 2002249150 |
| | _ | 2013037632 |
| Q | Agreement Regarding Recordation of Development Agreement | 2004176011 |
| | -Agreement | 2013037635 |
| R | Inclusion of subject property in the Westerly Creek Metropolitan District | 2013037633 |
| S | Deed CCD-SDC | 2005156207 |
| <u> </u> | —Quit Claim Deed | 2005156207 |
| | -Quit Claim Deed | 2005156206 |
| T | Amended and Restated Design and Architectural Declaration | |
| ι | Inclusion of subject property in the Westerly Creek Metropolitan District | 2005161547 |
| V - | Public Service Company of Colorado Easement | 2006009654 |
| W | | 2005177724 |
| X | Public Service Company of Colorado Easement (Does not effect) | 2005177725 |
| Ŷ | (Intentionally Deleted) | |
| | Deed CCD-SDC | 2016130300 |
| | -Quit Claim Deed | 2016130301 |
| | -Quit Claim Deed | 2016130304 |
| Z | Amended and Restated Design and Architectural Declaration | 2011028773 |
| | -Supplemental Declaration | 2016130302 |
| AA | | 2004176011 |
| | Agreement Regarding Recordation of Development Agreement | 2016134249 |
| AB | | 2001100014 |
| <u> </u> | - Amendment | 2017109709 |
| L AC | Inclusion of subject property | 2016161179 |





STAPLETON FILING NO. 50


A PART OF THE SOUTH HALF OF SECTION 26, TOWNSHIP 3 SOUTH, RANGE 67 WEST OF THE SIXTH PRINCIPAL MERIDIAN, CITY AND COUNTY OF DENVER, STATE OF COLORADO SHEET 6 OF 6



PARK

PREPARED BY:

A COM



LEGEND

- SET #5 REBAR WITH 1-1/4" YELLOW PLASTIC CAP STAMPED: URS CORP PLS 20683
- O SET #6 REBAR WITH PLS NUMBER ON DURABLE CAP IN RANGE BOX (AFTER CONSTRUCTION)

R.O.W. RIGHT-OF-WAY

- 1 BLOCK NUMBER
- 1 LOT NUMBER

